


UNIVERSITY OF TORONTO



3 1761 01199756 6



ART IN NEEDLEWORK

BY THE SAME AUTHOR.

ENAMELLING.

PATTERN DESIGN.

ORNAMENT AND ITS APPLICATION.

NATURE IN ORNAMENT.

Third Edition.

WINDOWS: A BOOK ABOUT STAINED  
AND PAINTED GLASS.

Second Edition.

ALPHABETS OLD AND NEW.

Second Edition.

LETTERING IN ORNAMENT. \*

MOOT POINTS: FRIENDLY DIS-  
PUTES UPON ART AND INDUSTRY.

In conjunction with Walter Crane.



27452P

III

# ART IN NEEDLEWORK

A BOOK ABOUT  
EMBROIDERY

BY

LEWIS F. DAY

AUTHOR OF 'WINDOWS,' 'ALPHABETS,  
'LETTERING IN ORNAMENT,' & OTHER  
TEXT-BOOKS OF ORNAMENTAL DESIGN

& MARY BUCKLE

THIRD EDITION REVISED AND  
ENLARGED

LONDON  
B. T. BATSFORD, 94 HIGH HOLBORN

1907

65-288  
14/1

NK

9206

D38

1907

## PREFACE.

EMBROIDERY may be looked at from more points of view than it would be possible in a book like this to take up seriously. Merely to hover round the subject and glance casually at it would serve no useful purpose. It may be as well, therefore, to define our standpoint: we look at the art from its practical side, not, of course, neglecting the artistic, for the practical use of embroidery is to be beautiful.

The custom has been, since woman learnt to kill time with the needle, to think of embroidery too much as an idle accomplishment. It is more than that. At the very least it is a handicraft: at the best it is an art. This contention may be to take it rather seriously; but if one esteemed it less it would hardly be worth writing about, and the book, when written, would not be worth the attention of students of embroidery, needle-workers, and designers of needlework to whom it is addressed. It sets forth to show what decorative stitching is, how it is done, and what it can do. It is illustrated by samplers of stitches; by diagrams, to explain the way stitches are done; and by examples of old and modern work, to show the artistic application of the stitches.

A feature in the book is the series of samplers designed to show not only what are the available

stitches, but the groups into which they naturally gather themselves, as well as the use to which they may be put: and the back of the sampler is given too: the reader has only to turn the page to see the other side of the stitching—which to a needlewoman is often the more helpful. Lest that should not be enough, the stitches are described in the text, and a marginal note shows at a glance where the description is given. This should be read needle and thread in hand—or skipped. Samplers and other examples of needlework are uniformly on a scale large enough to show the stitch quite plainly. The examples of old work illustrate always, in the first place, some point of workmanship; still they are chosen with some view to their artistic interest.

In other respects Art is not overlooked; but it is Art in harness. Design is discussed with reference to stitch and stuff, and stitch and stuff with reference to their use in ornament. It has been endeavoured also to show the effect needlework has had upon pattern, and the ways in which design is affected by the circumstance that it is to be embroidered.

The joint authorship of the work needs, perhaps, a word of explanation. This is not just a man's book on a woman's subject. The scheme of it is mine, and I have written it, but with the co-operation throughout of Miss Mary Buckle. Our classification of the stitches is the result of many a conference between us. The description



of the way the stitches are worked, and so forth, is my rendering of her description, supplemented by practical demonstration with the needle. She has primed me with technical information, and been always at hand to keep me from technical error. With reference to design and art I speak for myself.

My thanks are due to the authorities at South Kensington for allowing us to handle the treasures of the national collection, and to photograph them for illustration; to Mrs Walter Crane, Miss Mabel Keighley, and Miss C. P. Shrewsbury, for permission to reproduce their handiwork; to Miss Argles, Mrs Buxton Morrish, Colonel Green, R.E., and Messrs Morris and Co., for the loan of work belonging to them; and to Miss Chart for working the cross-stitch sampler.

I must also acknowledge the part my daughter has had in the production of this book: without her constant help it could never have been written.

LEWIS F. DAY.

*January 1st, 1900.*

---

### NOTE TO THIRD EDITION.

IN addition to revising the text, I have added a chapter on white work, which formed part of the original plan of the book, but was not ready in time for the first edition. I have to thank Mr James Jeffrey for his help in getting the samplers of white work executed by trade workers in Belfast.

*October 1907.*





Digitized by the Internet Archive  
in 2007 with funding from  
Microsoft Corporation

# CONTENTS.

CHAP.	PAGE
1. EMBROIDERY AND EMBROIDERY STITCHES .	I
2. CANVAS STITCHES . . . . .	12
3. CREWEL-STITCH . . . . .	26
4. CHAIN-STITCH . . . . .	38
5. HERRING-BONE-STITCH . . . . .	47
6. BUTTONHOLE-STITCH . . . . .	55
7. FEATHER AND ORIENTAL STITCHES . . . . .	62
8. ROPE AND KNOT STITCHES . . . . .	71
9. INTERLACINGS, SURFACE STITCHES, AND DIAPERS	83
10. SATIN-STITCH AND ITS OFFSHOOTS . . . . .	91
11. DARNING . . . . .	106
12. LAID-WORK . . . . .	112
13. COUCHING . . . . .	122
14. COUCHED GOLD . . . . .	131
15. APPLIQUÉ . . . . .	144
16. INLAY, MOSAIC, AND CUT-WORK . . . . .	153
17. EMBROIDERY IN RELIEF . . . . .	159
18. RAISED GOLD . . . . .	165
19. QUILTING . . . . .	171
20. STITCH GROUPS . . . . .	175
21. ONE STITCH OR MANY? . . . . .	180

CHAP.	PAGE
22. OUTLINE . . . . .	185
23. SHADING . . . . .	188
24. FIGURE EMBROIDERY . . . . .	198
25. THE DIRECTION OF THE STITCH . . . . .	208
26. CHURCH WORK . . . . .	216
27. WHITE WORK . . . . .	225
28. A PLEA FOR SIMPLICITY . . . . .	237
29. EMBROIDERY DESIGN . . . . .	244
30. EMBROIDERY MATERIALS . . . . .	254
31. A WORD TO THE WORKER . . . . .	262
INDEX . . . . .	269

## DESCRIPTIVE LIST OF ILLUSTRATIONS.

1. TAPESTRY—to illustrate work on a warp, not on a web. From Akhmin in Upper Egypt. Ancient Coptic. (In the Victoria and Albert Museum.)
2. DRAWN-WORK ON FINE LINEN, embroidered with gold and colour. Oriental. (From the collection of Mrs Lewis F. Day.)
3. DARNING AND SATIN-STITCH on square mesh—The darning on leaf, green, following the lines of the stuff; outlined with yellow, veined with pink and white; stem, yellow, its foliation pink, outlined with white, and ribbed with blue and white. Italian. 17th century. (V. & A. Museum.)
4. CROSS-STITCH UPON LINEN. Hungarian. Compare Illustration 45.
5. CROSS-STITCH SAMPLER—A and B, solid; C, line work; D, stroke-stitch—called also Holbein-stitch; E, stroke and cross stitches combined.
6. CANVAS-STITCH in coloured silk upon linen. The band Italian, the foliated diaper Oriental. (Mrs L. F. D.)
7. CANVAS-STITCH—Design comparatively free, but showing in its outline the influence of the rectangular lines of the weaving. Cretan. (Mrs L. F. D.)
8. CANVAS-STITCH SAMPLER — A, tent-stitch; B, half-cross-stitch; C, cushion-stitch; D, Moorish-stitch, so called; E, plait-stitch; F, couching on canvas.

9. CUSHION AND SATIN-STITCHES UPON CANVAS—The satin-stitches follow the lines of the stuff, and form a diaper built upon them. Compare Illustration 71.
10. TWO VARIETIES OF CANVAS-STITCH, the pattern in the bare linen, the background worked—A, plait-stitch, the ornament outlined; B, stitches drawn tightly together so as to pull the threads of the linen apart, giving very much the effect of drawn-work. Compare Illustration 2. (Mrs L. F. D.)
- 11 & 12. CREWEL-STITCH SAMPLER—A and C, crewel-stitch; B and D, outline-stitch; E, back-stitch; F, spots; G and H, stem-stitch; J, crewel and outline-stitches in combination.
13. CREWEL-WORK—The stem only worked in crewel-stitch. Embroidered in green, blue, and brown wools upon white cotton. Old English. (Coll. of Miss Argles.)
14. CREWEL-WORK, in which crewel-stitch hardly occurs. Embroidered in coloured wools upon white cotton. Old English. (Coll. of J. M. Knapp, Esq.)
15. CREWEL-STITCH IN TWISTED SILK—The scroll in green upon a brownish-purple ground; the smaller leafage upon the scroll in brighter green; the flowers and butterflies in blue and pink. Modern. (Mrs L. F. Day.)
16. CHAIN-STITCH AND KNOTS—Part of the same piece of work as Illustration 24. Indian. (V. & A. M.)
- 17 & 18. CHAIN-STITCH SAMPLER—A, chain-stitch solid and in line; B, magic stitch; C, church chain; D, cable chain; E, Vandyke chain; F, Mountmellic chain; G, Mountmellic cable—all so called.
19. CHAIN AND SURFACE STITCHES—the latter a kind of button-holing, only occasionally worked *into* the stuff. Part of a lectern cover in white thread upon a thin, greyish white linen stuff. German, 14th century. (V. & A. M.)



- 20 & 21. HERRING-BONE SAMPLER—A, B, C, varieties of herring-bone ; D, a combination of A and C ; E, fishbone ; F, a close variety of A ; G, tapestry stitch, so called.
- 22 & 23. BUTTONHOLE SAMPLER—A, B, C, ordinary buttonhole and variations upon it ; D, two rows of buttonhole worked slanting one into the other ; E, crossed buttonhole ; F, tailor's buttonhole ; G, ladder (called also Cretan) stitch ; H, herring-bone buttonhole ; J, buttonhole diaper.
24. BUTTONHOLE, CHAIN, AND KNOT STITCHES—chiefly in white floss silk on dark purple satin, with touches of crimson at the points from which the stitches radiate. The rings on the outer ground are not worked, but done in the dyeing of the satin. Part of the same piece of work as 16. Modern Indian from Surat. (V. & A. M.)
- 25 & 26. FEATHER-STITCH SAMPLER—A to G, ordinary feather-stitch and its variations ; G G, feather chain.
- 27 & 28. ORIENTAL-STITCH SAMPLER—A to E, Oriental-stitch and its varieties ; F, Oriental-stitch worked into buttonhole ; G, not properly a form of Oriental-stitch, though bearing some resemblance to it.
- 29 & 30. ROPE AND KNOT-STITCH SAMPLER—A, rope-stitch ; B, open rope-stitch ; C, what is called German knot-stitch ; D, open German knot-stitch ; E, Old English knot-stitch, so called ; F, bullion-stitch ; G, French knots.
31. A TOUR-DE-FORCE IN KNOTS—Worked entirely in the one stitch ; the drawing lines expressed by voiding. In white and coloured silks upon a very dark blue ground. Chinese. (Mrs L. F. D.)
- 32 & 33. INTERLACING-STITCH SAMPLER—A, interlaced crewel-stitch ; B, interlaced back-stitch ; C, back-stitch twice interlaced ; D, interlaced chain-stitch ; E, interlaced darning ; F, interlaced herring-bone ; G, herring-bone twice interlaced ; H, an interlaced version of C in Illustration 20 ; J, interlaced Oriental-stitch ; K, interlaced feather-stitch.

34. SURFACE-STITCH SAMPLER—A, D, G, various surface stitches ; B, surface buttonhole ; H and C, surface darning ; E, Japanese darning, as it is called ; F, net passing ; J, surface buttonhole over bars ; K, surface buttonhole over slanting stitches.
35. LACE OR SURFACE-STITCH AND SATIN-STITCH, much of it worn away. In straw-coloured floss upon pale blue silk. Part of a dress. French. Late 18th century. (Mrs L. F. D.)
- 36 & 37. SATIN-STITCH SAMPLER—Worked in floss, the stitch in various directions, to give different effects. Incidentally it shows various ways of breaking up a surface in satin-stitch. Compare with Illustration 38, which shows the effect of the stitch in twisted silk.
38. SATIN-STITCH IN COARSE TWISTED SILK.
39. SATIN-STITCH IN TWISTED SILK—Outlines voided. Worked in white and occasional red and yellow upon black satin. Modern. Indian. (V. & A. M.)
40. SATIN-STITCH AND, on the birds' bodies, PLUMAGE-STITCH—The ends of the stalks worked in French knots ; the veins of the leaves in fine white cords laid on to the satin-stitch. The outlines voided, and the voiding occasionally worked across with stitches wide enough apart to show the ground between. In white and bright-coloured silk floss upon a black satin ground. Chinese. (Mrs L. F. D.)
- 41 & 42. SAMPLER — Showing offshoots from satin and crewel stitches, and incidentally illustrating various ways of shading. A, crewel-stitch ; B, plumage-stitch, worked in the hand ; C, split-stitch ; D, plumage-stitch, worked in the frame.
43. DARNING SAMPLER—Except in the background the stitches follow the lines of the drawing, regardless of the weaving of the stuff. The customary outlining of the pattern is here omitted, to show how far it may, or may not, be needful.

44. DARNING — DESIGNED BY WILLIAM MORRIS. In delicate colours upon a sea-green ground, outlined with black and white. Part of the border of a table-cloth, the property of Messrs Morris & Co.
  
45. FLAT DARNING—Solid and open, following the lines of a square mesh, and stepping in tune with it; the outline voided; all in white thread. Old German. (Gewerbs Museum; Munich.)
  
46. LAID-WORK SAMPLER, showing various ways (spilt-stitch and couching) in which the sewing down may be done, and the various directions it may take — vertical, horizontal, following the ornamental forms, or crossing them.
  
47. LAID-WORK — The couching crosses the flower forms in straight lines; and in the eye of the flower where the threads cross, the two are sewn down at a single stitch. The spiral stems a sort of laid cord. Flower in blue, sewn with blue and outlined with gold; leaves, a bright fresh green stitched with olive. Japanese. (V. & A. M.)
  
48. LAID-WORK. The sewing down of the leaves crosses them in curved lines which suggest roundness. The stem in gold basket pattern. Part of a coverlet. Worked upon a cedar-coloured ground chiefly in dark blue and white, the blue couched with white, the white and other colours couched with red. Indo-Portuguese. 17th century. (V. & A. M.)
  
49. LAID-WORK AND SOME SURFACE-STITCH. The stitching which sews down the floss takes the direction of the scroll, &c., and gives drawing. The surface work in the stems is done upon a ladder of stitches across. Part of a chalice veil. Italian. Early 17th century. (V. & A. M.)
  
50. LAID-WORK SAMPLER—The straight lines of laid floss varied in colour to suggest shading. The stalk padded, and the pattern made by the stitching upon it thereby emphasised.

51. BULLION AND COUCHED CORD—A, the somewhat loose design of the border in bullion shows rather plainly the way it is done. B, the solid discs of spiral cord are unusual, but most characteristic of the method of couching. The stitches sewing down the cord are not apparent. Oriental. (Mrs L. F. D.)
52. SAMPLER OF COUCHED SILK—The broad central band and the narrow beaded lines are in floss, and show the effect of sewing it more or less tightly down. The two intermediate bands are in cord couched with threads in the direction of its twist, not very easily distinguishable unless by contrast of colour.
53. COUCHING IN LOOPED THREADS—The effect is not unlike that of chain-stitch or fine knotting. Rather over actual size. Worked in bright colours upon a pale green crêpe ground. Chinese. (Mrs L. F. D.)
54. REVERSE COUCHING—Showing on the face of it no sign of couching. (After the manner of the Syon Cope.)
55. BACK OF REVERSE COUCHING—Showing the parallel lines of couched linen thread which sew down the silk upon the surface (Illustration 54). The zigzag pattern of the stitching might equally well have taken other lines.
56. COUCHED GOLD SAMPLER—A, B, C, D, flat work; E, part flat, part raised; F, G, H, J, basket and other patterns raised over cords.
57. COUCHING IN VARIOUS DIAPER PATTERNS, outlined in part with "PLATE." Silver on pale pink silk. (Coll. of Mrs T. Buxton Morrish.)
58. GOLD COUCHING IN OPEN THREADS—A, the lines of gold which form a scale pattern on the dragon's body, are wide enough apart to let the red ground grin through. Elsewhere the couching, contrary to mediæval practice, follows the shapes, line within line until they are occupied. The floss embroidery, in white and colours, is in surface satin-stitch. Chinese. B, the open lines of gold look somehow richer than if the metal had been worked solid upon the crimson ground. Old Venetian. (Mrs L. F. D.)

## DESCRIPTIVE LIST OF ILLUSTRATIONS. xvii

59. COUCHED OUTLINE WORK ; only an occasional detail worked solid ; suggests damascening. The border is in gold, the filling in silver, thread on a greyish-green velvet. Part of an Italian housing or saddlecloth. 16th century. (V. & A. M.)
60. APPLIQUÉ—Satin upon velvet, outlined with two threads of gold couching.
61. APPLIQUÉ PANEL—Designed and executed by Miss Mabel Keighley, illustrating a poem by William Morris. (The property of the artist.)
62. A. COUNTER-CHANGE PATTERN, INLAY OR APPLIQUÉ—Yellow satin and crimson velvet. The outline, which is in gold, falls chiefly upon the yellow, so as not to disturb the exact balance of light and dark, which it is essential to preserve in counter-change. Part of a stole. Spanish. 16th century. (V. & A. M.)
- B. APPLIQUÉ, of deep crimson velvet upon white satin, outlined with paler red cord. The outlines, meeting together, form a stem of double cord. Italian. 17th century. (V. & A. M.)
63. APPLIQUÉ, with couched outline, and stitching upon the appliqué band or ribbon. The dots in the centre of the grapes are French knots. The pattern is in satin of various colours, upon a figured green silk damask, outlined with yellow silk sewn down with yellow. Italian. (V. & A. M.)
64. INLAY IN COLOURED CLOTHS, outlined with chain stitch. Magic stitch also occurs. A characteristic example of the kind of work done at Retsht, in Persia. (Mrs L. F. D.)
65. CUT-WORK IN LINEN—A fret of this kind was often outlined with coloured silk, and the detail within the fretted outline further embroidered in coloured silk. (Coll. of Mrs Drake.)



66. SAMPLER OF RAISED WORK, showing underlays: A, of cloth; B, of twisted cords; C, of parchment; D, of cotton wool; E, first of cotton cord and then of cotton thread; F, of cord; G, of string; H, of sewing.
67. RAISED WORK, showing underlay of linen, and the way it is sewn down—The work is in flax thread, red, yellow, and white, upon a blue linen ground. The stem is dotted with white beads, the ground with gold spangles. Part of an altar frontal. German. 15th century. (V. & A. M.)
68. RAISED GOLD BASKET PATTERNS, &c., upon white satin. The stalk in flat wire. Spanish. 17th century. (Mrs L. F. D.)
69. QUILT, WORKED IN CHAIN-STITCH from the back—which has precisely the effect of back-stitch. Yellow silk upon white linen. Old English. (V. & A. M.)
70. RAISED QUILTING, in black silk upon pale sea-green satin. Part of the border of a prayer cushion. Old Persian. (Mrs L. F. D.)
71. DIAPER OF SATIN-STITCH IN THE MAKING—Something between canvas-stitch and satin-stitch. The leafage is in tent-stitch. Compare with Illustration 9. (V. & A. M.)
72. STITCHES IN COMBINATION—Among them Oriental, ladder, buttonhole, chain, crewel, satin, and herring-bone stitches, worked in dark blue silk upon unbleached linen. Old Cretan, so called. (Mrs L. F. D.)
73. FINE NEEDLEWORK UPON CAMBRIC—The substance of which is apparent upon the upper edge of the work. In the ground-work of the pattern generally the threads are drawn together to form an open net. The stitches occurring in the collar of which this is part are, buttonhole, satin, chain, herring-bone, cross, and back stitches. The outline is mostly in fine cross-stitch. Nothing could exceed the delicacy of the workmanship, which is in its kind perfect. Old English. (Coll. of Col. Green, R.E.)

## DESCRIPTIVE LIST OF ILLUSTRATIONS. xix

74. PART OF A DESIGN BY WALTER CRANE, cunningly adapted to execution in needlework. Shows the direction of the stitch, and the part it can be made to play in expressing form. Worked in coloured silks upon linen by Mrs Walter Crane, whose property the work is.
75. SHADING IN CHAIN-STITCH in silk and chenille upon a satin ground. The shading very deliberately schemed by the designer. In natural colours upon white. French. Louis Seize. (V. & A. M.)
76. SHADING IN SHORT STITCHES; picturesque to the point of a touch of white in the glistening yellow of the dove's eye. Chenille, in chain-stitch, is used for the wreath and in the leaves of the flower sprigs. These are in colours, the birds are in silvery greys, all on a white satin ground. French. Louis Seize. (V. & A. M.)
77. SHADING IN LONG-AND-SHORT AND SPLIT STITCHES, with more regard to expression of form than to neatness of execution. German. 16th century. (V. & A. M.)
78. CHAIN-STITCH, showing in the figures of the little men how much a draughtsman can express in a few stitches. Full size. Chinese. (Mrs L. F. D.)
79. FIGURE WORK — The flesh in straight, upright stitches, the drapery laid and couched. English. 15th century. (V. & A. M.)
80. CONSUMMATE FIGURE EMBROIDERY—Canvas ground entirely covered. Flesh in coloured silks, short-stitch; drapery in coloured silks over gold, which only gleams through in the high lights. Architecture closely couched gold. Part of an orphrey. Florentine. 16th century. (V. & A. M.)
81. CHINESE FIGURES—The flesh in short satin-stitches, the rest in chain-stitch; chiefly in blue and white upon a figured white silk ground. About actual size. (Mrs L. F. D.)

82. SATIN-STITCH, showing the influence of its direction upon the tone of colour. The pattern is all in one shade of yellow-brown floss upon white linen. The outline steps with the weaving, and shows the connection between satin and canvas stitches. Italian. 17th century. (V. & A. M.)
83. MEANINGLESS DIRECTION OF STITCH—Satin and herring-bone stitches. From an altar-cloth. German. 17th century. (V. & A. M.)
84. MORE EXPRESSIVE LINES OF STITCHING—To compare with Illustration 83.
85. SATIN AND PLUMAGE STITCHES chiefly, the bird's crest in French knots, the clouds about him in knotted braid. The direction of the stitch is most artfully chosen, and the precision of the work is faultless. The satin ground is of brilliant orange-red; the crane, white, with black tail feathers, scarlet crest, and yellow beak and legs; the clouds, black and white and blue. Japanese. (Mrs L. F. D.)
86. RENAISSANCE CHURCH WORK IN GOLD AND SILVER, partly flat, partly in relief, upon pale blue satin, with touches of pink and crimson silk to give emphasis. Spanish. 18th century. Compare the stem with Illustration 66, B. (V. & A. M.)
87. GOTHIC CHURCH WORK—The flesh, &c., in split-stitch; the vine-leaves green, getting yellower as it nears the crimson silk ground. Part of a cope embroidered with a representation of the Tree of Jesse. English. *Ca.* 1340. (V. & A. M.)
88. MODERN CHURCH WORK ON LINEN, in long-and-short stitch. Veins padded with embroidery cotton and worked over with two threads of filo-floss, a green and a blue; the rest of the leaves worked in one shade of stout floss. All this applied to velvet with a couching of brown filoselle, and the tendrils added. Designed and executed by Miss C. P. Shrewsbury. (The property of the artist.)

89. APPLIQUÉ SPRIG, with subsidiary lines of gold embroidery upon the velvet to disguise the application. From a late Gothic altar frontal.
90. WHITE WORK on fine linen—Chiefly in satin-stitch and seeding. Designed by James Jeffrey, and worked (like the other illustrations to this chapter) by trade workers for the Irish factories.
91. WHITE WORK on linen, in satin-stitch, seeding, and matting. The vase shape outlined with sparring or spoke-stitch.
92. DETAILS—Designed to be worked chiefly in short satin-stitches; some matting in the leaves; the berries formed by eyelets.
93. WHITE WORK—Leaves and outlines in satin-stitch, heart shapes filled with seeding and matting.
94. WHITE WORK—In satin-stitch with appliqué of rectangular pieces of cambric, seeding and eyelets in the sprigs.
95. WHITE WORK — Satin-stitch and drawn-work, the centre appliqué.
96. BUTTERFLY—In satin-stitch, seeding, and sparring (which follows the lines of the wings and body). Eyelets for the eyes.
97. SIMPLE STITCHING ON LINEN, the broader bands in a canvas-stitch in yellow, the finer lines in back-stitch in pale grey silk. Italian. (Mrs L. F. D.)
98. SIMPLE COUCHED OUTLINE WORK, in purplish silk cord upon linen. Part of an altar-cloth. Italian. 16th century. (V. & A. M.)
99. RENAISSANCE ORNAMENT—Most gracefully designed arabesque. The raised outline (couched) has somewhat the effect of cloisons, the satin-stitch (in colours) of brilliant enamel. It is upon a white satin ground. The foreshortened face in the picture is *painted* upon satin. Italian. Ca. 1700. (V. & A. M.)

100. **APPLIQUÉ DESIGN**, in yellow satin upon crimson velvet—  
Double outline; next the red, white, sewn with pale blue;  
next the yellow, gold. Midrib of the leaf couched silver.  
Spanish, 16th century. (V. & A. M.)
101. **SATIN-STITCH**—Except that the heart-shaped features at the  
base and the lily-shaped flowers, of which only the tips  
are shown, are outlined with fine white cord. Part of a  
fan, worked by Miss Buckle, from a design by L. F. D.  
(The property of the worker.)
102. **LEATHER APPLIQUÉ UPON VELVET**—The stitching well within  
the edge of the leather.



# ART IN NEEDLEWORK

## EMBROIDERY AND STITCHING.


Embroidery begins with the needle, and the needle (thorn, fish-bone, or whatever it may have been) came into use so soon as ever savages had the wit to sew skins and things together to keep themselves warm—modesty, we may take it, was an afterthought—and if the stitches made any sort of pattern, as coarse stitching naturally would, that was *embroidery*.

The term is often vaguely used to denote all kinds of ornamental needlework, and some with which the needle has nothing to do. That is misleading; though it is true that embroidery does touch, on the one side, *tapestry*, which may be described as a kind of embroidery with the shuttle, and, on the other, *lace*, which is needlework pure and simple, construction “in the air” as the Italian name has it.

The term is used in common parlance to express any kind of superficial or superfluous ornamentation. A poet is said to embroider the truth;

But such metaphorical use of the word hints at the real nature of the work—embellishment, enrichment, *added*. If added, there must first of all be something it is added *to*—the material, that is to say, on which the needlework is done. In weaving (even tapestry weaving) the pattern is got by the inter-threading of warp and weft. In lace, too, it is got out of the threads which make the stuff. In embroidery it is got by threads worked *on* a fabric first of all woven on the loom, or, it might be, netted.


There is inevitably a certain amount of overlapping of the crafts. For instance, take a form of embroidery common in all countries, Eastern, Hungarian, or nearer home, in which certain of the weft threads of the linen are *drawn out*, and the needlework is executed upon the warp threads thus revealed. This is, strictly speaking, a sort of tapestry with the needle, just as, it was explained, tapestry itself may be described as a sort of embroidery with the shuttle. That will be clearly seen by reference to Illustration I, which shows a fragment of ancient tapestry found in a Coptic tomb in Upper Egypt. In the lower portion of it the pattern appears light on dark. As a matter of fact, it was wrought in white and red upon a linen warp; but, as it happened, only the white threads were of linen, like the warp, the red were woollen, and in the course of fifteen hundred years or so much of this red wool has perished, leaving the



I. TAPESTRY, SHOWING WARP.

white pattern intact on the warp, the threads of which are laid bare in the upper part of the illustration.

It is on just such upright lines of warp that all tapestry, properly so called, is worked—whether with the shuttle or with the needle makes no matter—and there is good reason, therefore, for the name of “tapestry stitch” to describe needlework upon the warp threads only of a material (usually linen) from which some of the weft threads have been *withdrawn*.



2. DRAWN WORK.

The only difference between true tapestry and drawn work, an example of which is here given, is, that the one is done on a warp that has not before been woven upon, and the other on a warp from which the weft threads have been

*drawn*. The distinction, therefore, between tapestry and embroidery is, that, worked on a warp, as in Illustration 1, it is tapestry; worked on a mesh, as in Illustration 3, it is embroidery.

With regard, again, to lace. That is itself a web, independent of any groundwork or foundation





3. STITCHING ON A SQUARE MESH.



to support it. But it is possible to work it *over* a silken or other surface ; and there is a kind of embroidery which only floats on the surface of the material without penetrating it. A fragment of eighteenth-century silk given in Illustration 35 shows plainly what is meant.

Embroidery is enrichment by means of the needle. To embroider is to work on something : a groundwork is presupposed. And we usually understand by embroidery, needlework in thread (it may be wool, cotton, linen, silk, gold, no matter what) upon a textile material of some kind. In short, it is the decoration of a material woven in thread by means still of thread. It is thus the consistent way of ornamenting stuff—most consistent of all when one kind of thread is employed throughout, as in the case of linen upon linen, silk upon silk. The enrichment may, however, rightly be, and oftenest is, perhaps, in a material nobler than the stuff enriched, in silk upon linen, in wool upon cotton, in gold upon velvet. The advisability of working upon a precious stuff in thread less precious is open to question. It does not seem to have been satisfactorily done ; but if it were only the background that was worked, and the pattern were so schemed as almost to cover it, so that, in fact, very little of the more beautiful texture was sacrificed, and you had still a sumptuous pattern on a less attractive background—why not? But then it would be because you wanted that less

precious texture there. The excuse of economy would scarcely hold good.

In the case of a material in itself unsightly, the one course is to cover it entirely with stitching, as did the Persian and other untireable people of the East. But not they only. In the Middle Ages Western embroiderers were hardly less industrious. The famous Syon cope is worked all over. Much of the work so done competes in effect with tapestry or other weaving; and its purpose was similar: it is a sort of amateur way of working your own stuff. But in character it is no more nearly related to the work of the loom than other needlework—it is still work upon a stuff. For all-over embroidery one would naturally choose a coarse canvas ground to work on; and it more often happens that one chooses canvas because it is proposed to cover it, than that one works all over a ground because it is unpresentable.

Embroidery is merely an affair of stitching; and the first thing needful alike to the worker in it and the designer for it, is a thorough acquaintance with the stitches; not, of course, with every modification of a modification of a stitch which individual ingenuity may have devised—it would need the space of an encyclopædia to chronicle them all—but with the broadly marked varieties of stitch which have been employed to best purpose in ornament.

They are derived, naturally, from the stitches

first used for quite practical and prosaic purposes—button-hole stitch, for example, to keep the edges of the stuff from fraying; herring-bone, to strengthen and disguise a seam; darning, to make good a worn surface; and so on.

The difficulty of discussing them is greatly increased by the haphazard way in which they are commonly named. A stitch is called Greek, Spanish, Mexican, or what not, according to the country whence came the work in which some one first found it. Each names it after his or her individual discovery, or calls it, perhaps, vaguely Oriental; and so we have any number of names for the same stitch, names which to different people stand often for quite different stitches.

When this confusion is complicated by the invention of a new name for every conceivable combination of thread-strokes, or for each slightest variation upon an old stitch, and even for a stitch worked from left to right instead of from right to left, or for a stitch worked rather longer than usual, the task of reducing them to order seems almost hopeless.

Nor do the quasi-learned descriptions of old stitches help us much. One reads about *opus* this and *opus* that, until one begins to wonder where, amidst all this parade of science, art comes in. But you have not far to go in the study of the authorities to discover that, though they may concur in using certain high-sounding Latin terms,

they are not of the same mind as to their meaning. In one thing they all agree, foreign writers as well as English, and that is, as to the difficulty of identifying the stitch referred to by ancient writers, themselves probably not acquainted with the *technique* of stitching, and as likely as not to call it by a wrong name. It is easier, for example, to talk of *Opus Anglicanum* than to say precisely what it was, further than that it described work done in England ; and for that we have the simple and sufficient word—English. There is nothing to show that mediæval English work contained stitches not used elsewhere. The stitches probably all come from the East.

Nomenclature, then, is a snare. Why not drop titles, and call stitches by the plainest and least mistakable names? It will be seen, if we reduce them to their native simplicity, that they fall into fairly marked groups, or families, which can be discussed each under its own head.

Stitches may be grouped in all manner of arbitrary ways—according to their provenance, according to their effect, according to their use, and so on. The most natural way of grouping them is according to their structure ; not with regard to whence they came, or what they do, but according to what they are, the way they are worked. This, at all events, is no arbitrary classification, and this is the plan it is proposed here to adopt.

The use of such classification hardly needs pointing out.

A survey of the stitches is the necessary preliminary, either to the design or to the execution of needlework. How else suit the design to the stitch, the stitch to the design? In order to do the one the artist must be quite at home among the stitches; in order to do the other the embroidress must have sympathy enough with a design to choose the stitch or stitches which will best render it. An artist who thinks the working out of his sketch none of his business is no practical designer; the worker who thinks design a thing apart from her is only a worker.

This is not the moment to urge upon the needlewoman the study of design, but to urge upon the designer the study of stitches. Nothing is more impractical than to make a design without realising the labour involved in its execution. Any one not in sympathy with stitching may possibly design a beautiful piece of needlework, but no one will get the utmost that is to be got out of the needle without knowing all about it. One must understand the ways in which work can be done in order to determine the way it shall in any particular case be done.

Certain stitches answer certain purposes, and strictly only those. The designer must know which stitch answers which purpose, or he will in the first place waste the labour of the embroidress,



and in the second miss his effect—which is to waste his own pains too. The effective worker (designer or embroiderer) is the one who works with judgment. And you cannot judge unless you know. When it is remembered that the character of needlework, and by rights also the character of its design, depends upon the stitch, there will be no occasion to insist further upon the necessity of a comprehensive survey of the stitches.

A stitch may be defined as the thread left on the surface of the cloth or what not, after each ply of the needle.

And the simple straightforward stitches of this kind are not so many as one might suppose. They may be reduced indeed to a comparatively few types, as will be seen in the following chapters.

## CANVAS STITCHES.

The simplest, as it is most likely the earliest used, stitch-group is what might best be called CANVAS stitch—of which cross-stitch is perhaps the most familiar type, the class of stitches which come of following, as it is only natural to do, the mesh of a coarse linen, net, or open web upon which the work is done.

A stitch bears always by rights some relation to the material on which it is worked ; but canvas or very coarse linen almost compels a stitch based upon the cross lines of its woof. At all events it suggests designs of typically rigid construction, which we find in embroidery no matter where it was done. In ancient Byzantine or Coptic work, in modern Cretan work, and in peasant embroidery all the world over, pattern work on coarse linen has run persistently into angular lines—in which, because of that very angularity, the plain outcome of a way of working, we find artistic character. Artistic design is always expressive of the mode of workmanship.

Work of this kind is not too lightly to be dismissed. There is art in the rendering of form by means of angular outlines, art in the choice of

forms which can be expressed by such lines. It is not uncharitable to surmise that one reason why such work (once so universal and now quite out of fashion) is not popular with needlewomen may be, the demand it makes upon the designer's draughtsmanship: it is much easier, for example, to draw a stag than to render the creature satisfactorily within jagged lines determined by a linen mesh.



4. CROSS-STITCH.

The piquancy about natural or other forms thus reduced to angularity argues, of course, no affectation of quaintness on the part of the worker, but was the unavoidable outcome of her way of work. There is a pronounced and early limit to art of this rather naïve kind, but that there is art in some of the very simplest and most modest peasant work built up on those lines no artist will deny. The art in it is usually in proportion to its modesty. Nothing is more futile than to put it to anything

like pictorial purpose. The wonderfully wrought pictures in tent-stitch, for example, bequeathed to us by the seventeenth century, are painful object-lessons in what not to do.

The origin of the term cross-stitch is not far to seek: the stitches worked upon the square mesh do cross. But, falling naturally into the lines of the mesh which governs them, they present not so much the appearance of crosses as of squares, reminding one of the *tesseræ* employed in mosaic.

TO WORK  
CROSS-  
STITCH.

To explain the process of working cross-stitch would be teaching one's grandmother indeed. It is simply, as its name implies, crossing one stitch by another, following always the lines of the canvas. But the important thing about it is that the stitches must cross always in the same way; and, more than that, they must be worked in the same direction, or the mere fact that the stitches at the *back* of the work do not run in the same way will disturb the evenness of the surface. What looks like a seam on the sampler opposite is the result of filling up a gap in the ground with stitches necessarily worked in vertical, whereas the ground generally is in horizontal, lines. On the face of the work the stitches cross all in the same way.

The common use of cross-stitch and the somewhat geometric kind of pattern to which it lends itself are shown in the sampler, Illustration 5.

The broad and simple leafage, worked solid (A) or left in the plain canvas upon a groundwork of





5. CROSS-STITCH SAMPLER.



solid stitching (B), and the fretted diaper on vertical and horizontal lines (C), show the most straightforward ways of using it.

The criss-cross of alternating cross-stitches and open canvas framed by the key pattern (C) shows a means of getting something like a tint half-way between solid work and plain ground. The mere line work—or “stroke-stitch,” not crossed (D), is a perfectly fair way of getting a delicate effect; but design in that stitch has a way of working out rather less happily than it promised.

The addition of such stroke-stitching to solid cross-stitch (E) is not at best a very happy device. It seems rather like a confession of dissatisfaction on the part of the worker with the simple means of her choice. As a device for, as it were, correcting the stepped outline it is at its worst. Timid workers are always afraid of the stepped outline which a coarse mesh gives. In that they are wrong. One should employ canvas stitch only where there is no objection to a line which keeps step with the canvas; there is then a positive charm (for frank people at least) in the frank confession of the way the work is done.

There are many degrees in the frankness with which this convention has been accepted, according perhaps to the coarseness of the canvas ground, perhaps to the personality of the worker. The animal forms at the top of Illustration 6 are uncompromisingly square; the floral devices on



6. CANVAS-STITCH.

B

the same page, though they fall, as it were inevitably, into square lines, are less rigidly formal. The inevitableness of the square line is apparent in the sprig below (7). It was evidently meant to be freely drawn, but the influence of the mesh betrays



7. CANVAS STITCH.

itself; and the design, if it loses something in grace, gains also thereby in character.

There is literally no end to the variety of stitches, as they are called, belonging to this group, and their names are a babel of confusion. Florentine, Parisian,

Hungarian, Spanish, Moorish, Cashmere, Milanese, Gobelin, are only a few of them; but they stand, as a rule, rather for stitch arrangements than for stitches. A small selection of them is given in Illustration 8.

TENT-  
STITCH  
A.


What is known as tent-stitch (A in the sampler opposite) is a sort of half cross-stitch; its peculiarity is that it covers only one thread of the



8. CANVAS-STITCH SAMPLER.



canvas at a stroke, and is therefore on a more minute scale than stitches which are two or three threads of the canvas wide, as cross-stitch may, and cushion-stitch must, be. It derives its name from the old word *tenture*, or *tenter* (*tendere*, to stretch), the frame on which the embroidress distended her canvas. The word has gone out of use, but



9. CUSHION AND SATIN STITCHES.

we still speak of *tenter-hooks*. The stitch is serviceable enough in its way, but is discredited by the monstrous abuse of it referred to already. A picture in *tent-stitch* is even more foolish than a picture in *mosaic*. It cannot come anywhere near to pictorial effect; the *tesseræ* will pronounce themselves, and spoil it.

This kind of half cross-stitch worked on the larger scale of ordinary cross-stitch would look



meagre. It is filled out, therefore (B), by horizontal lines of the thread laid across the canvas, and over these the stitch is worked.

CROSS-  
STITCH  
B.

Cushion-stitch consists of diagonal series of upright stitches, measuring in the sampler (C) six threads of the canvas, so that after each stitch the needle may be brought out just three threads lower than where it was put in. By working in zigzag instead of diagonal lines, a familiar pattern is produced, more often described as "Florentine"; but the stitch is in any case the same.

CUSHION-  
STITCH  
C.

The stitch at D (sometimes called Moorish stitch) is begun by working a row of short vertical stitches, slightly apart, and completed by diagonal stitches joining them.

CANVAS-  
STITCH  
D.

Unless the silk employed is full and soft, this may not completely cover the canvas, in which case the diagonal stitches must further be crossed as shown on Illustration 89.

If the linen is loosely woven, and the thread is tightly drawn in the working, the mesh will be pulled apart, giving the effect of an open lattice of the kind shown at B, on Illustration 10, in which the effect is something like drawn work; but here the threads of the linen are not drawn out but drawn together.

The way of working the stitch at E is described on page 51, under the name of "fish-bone." Worked on canvas it has somewhat the effect of

CANVAS-  
STITCH  
E.


plaiting, and goes by the name of "plait-stitch." It is worked in horizontal rows alternately from left to right and from right to left.

CANVAS-  
STITCH  
F.

The stitch at F is a sort of couching (see page 124). Diagonal lines of thread are first laid from edge to edge of the ground space, and these are sewn down by short overcasting stitches in the cross direction.

Admirable canvas-stitch work has been done upon linen in silk of one colour—red, green, or blue—and it was a common practice to work the background leaving the pattern in the bare stuff. It prevailed in countries lying far apart, though probably not without inter-communication. In fact, the influence of Oriental work upon European has been so great that even experts hesitate sometimes to say whether a particular piece of work is Turkish or Italian. In Italian work, at least, it was usual to get over the angularity of silhouette inherent in canvas stitches by working an outline separately. When that is thin, the effect is proportionately feeble. The broader outline (shown at A, Illustration 10) justifies itself; and in the case of a stitch which falls into horizontal lines it appears to be necessary. This is plait-stitch, known also by the name of Spanish stitch—not that it is in any way peculiar to Spain. It is allied to herring-bone stitch, to which a special chapter is devoted.

Darning is also employed as a canvas stitch.



10. PLAIT AND OPEN CANVAS STITCHES.

There is beautiful sixteenth-century Italian work (in coloured silks on dark net of the very open square mesh of the period), which is most effective, and makes no pretence of disguising the stepped outline. In the very early days of Christian art in Egypt and Byzantium, linen was darned in little square tufts of wool upstanding on its surface, which look so much like the tesserae of mosaic as to suggest a doubt whether it was not worked in deliberate imitation of it.

Again, in the fifteenth century satin-stitch was worked on fine linen with strict regard to the lines of its web; and the Persians, ancient and modern, embroider white silk upon linen, also in satin-stitch, preserving piously the rectangular and diagonal lines given by the material. They have their reward in producing most characteristic needlework. The diapered ground in Illustration 9 (page 20) is satin-stitch upon coarse linen.

The filling-in patterns used to such delicate and dainty purpose in the marvellous work on fine cambric (Illustration 73) which competes in effect with lace, though it is strictly embroidery, all follow in their design the lines of the fabric, and are worked thread by thread according to its woof: they afford again instances of perfect adaptation of stitch to material and of design to stitch.

Satin and other stitches were worked by the old Italians (Illustration 3) on square-meshed canvas, frankly on the square lines given by it,

for the filling in of ornamental details, though the outline might be much less formal. That is to say, the surface of freely drawn leaves, &c., instead of being worked solid, was diapered over with more or less open pattern work constructed on the lines of the weaving.


A cunning use of the square mesh of canvas has sometimes been made to guide the worker upon other fabrics, such as velvet. This was first faced with net: the design was then worked, over that, on to and into the velvet, and the threads of the canvas were then drawn out. That is a device which may serve on occasion. The design may even be traced upon the net.



## CREWEL-STITCH.

For work in the hand, CREWEL-STITCH is perhaps, on the whole, the easiest and most useful of stitches ; whence it comes that people sometimes vaguely call all embroidery crewel


work ; though, as a matter of fact, the stitch properly so called was never very commonly employed, even when the work was done in "crewel," the double thread of twisted wool from which it takes its name.




THE WORKING OF A ON CREWEL-STITCH SAMPLER.

TO WORK  
A.

CREWEL-STITCH proper is shown at A on the sampler opposite, where it is used for line work. It is worked as follows :—Having made a start in the usual way, keep your thread downwards under your left thumb and below your needle—that is,



II. CREWEL-STITCH SAMPLER.



12. CREWEL-STITCH SAMPLER (BACK).

to the right; then take up with the needle, say  $\frac{1}{8}$ th of an inch of the stuff, and bring it out through the hole made in starting the stitch, taking care not to pierce the thread. This gives the first half stitch. If you proceed in the same way your next stitch will be full length. The test of good workmanship is that at the back it should look like back-stitch (Illustration 12), described on page 30.

OUTLINE-STITCH (B on sampler) differs from crewel-stitch only in that the thread is always kept upwards above the needle, that is to the left. In the doing it one is very apt to untwist the thread, and it wants constantly re-twisting. The stitch is



TO WORK  
B.

THE WORKING OF 'B' ON CREWEL-  
STITCH SAMPLER.


useful for working single lines and for outlining solid work. The muddled effect of much crewel work is due to the confusion of this stitch with crewel-stitch proper.

THICK CREWEL-STITCH (C on sampler) is only a little wider than ordinary crewel-stitch, but it gives a heavier line, in higher relief. In effect it resembles rope-stitch, but it is more simply worked. You begin as in ordinary crewel-stitch,

TO WORK  
C.



but after the first half-stitch you take up  $\frac{1}{8}$ th of an inch of the material in advance of the last stitch, and bring out your needle at the point where the first half-stitch began. You proceed,



THE WORKING OF G ON CREWEL-STITCH SAMPLER.

always putting your needle in  $\frac{1}{8}$ th of an inch in front of, and bringing it out  $\frac{1}{8}$ th of an inch behind,

the last stitch, so as to have always  $\frac{1}{4}$ th of an inch of the stuff on your needle.

TO WORK  
D.

THICK OUTLINE-STITCH (D on sampler) is like thick crewel-stitch with the exception that, as in ordinary outline-stitch (B), you keep your thread always above the needle to the left.

TO WORK  
E.

In BACK-STITCH (E), instead of first bringing the needle out at the point where the embroidery is to begin, you bring it out  $\frac{1}{8}$ th of an inch in advance of it. Then, putting your needle back, you take up this  $\frac{1}{8}$ th together with another  $\frac{1}{8}$ th in advance. For the next stitch you put your needle into the hole made by the last stitch, and so on, taking care not to split the thread in so doing.

TO WORK  
F.

To work the SPOTS (F) on sampler—having made a back-stitch, bring your needle out through the same hole as before, and make another back-stitch above it, so that you have in what appears





13 CREWEL WORK AND CREWEL-STITCH.

to be one stitch, two thicknesses of thread; then bring your needle out some distance in advance of the last stitch, and proceed as before. The distance between the stitches is determined by the effect you desire to produce. The thread should not be drawn too tight.

TO WORK  
G.


You begin STEM-STITCH (G) with the usual half-stitch. Then, holding the thread downwards, instead of proceeding as in crewel-stitch (A) you slant your needle so as to bring it out a thread or two higher up than the half-stitch, but precisely above it. You next put the needle in  $\frac{1}{8}$ th of an inch in advance of the last stitch, and, as before, bring it out again in a slanting direction a thread or two higher. At the back of the work (Illustration 12) the stitches lie in a slanting direction.

TO WORK  
H.

To work wider STEM-STITCH (H). After the first two stitches, bring your needle out precisely above and in a line with them, and put it in again  $\frac{1}{8}$ th of an inch in advance of the last stitch, producing a longer stroke, which gives the measure of those following. The slanting stitches at the back (Illustration 12) are only two-thirds of the length of those on the face.

CREWEL AND OUTLINE STITCHES worked (J) side by side give somewhat the effect of a braid. The importance of not confusing them, already referred to, is here apparent.

CREWEL-STITCH is worked SOLID in the heart-shape in the centre of the sampler. On the left



14. CREWEL WORK IN VARIOUS STITCHES

side the rows of stitching follow the outline of the heart ; on the right they are more upright, merely conforming a little to the shape to be filled. This is the better method.

TO WORK  
SOLID  
CREWEL-  
STITCH.

The way to work solid crewel-stitch will be best explained by an instance. Suppose a leaf to be worked. You begin by outlining it ; if it is a wide leaf, you further work a centre line where the main rib would be, and then work row within row of stitches until the space is filled. If on arriving at the point of your leaf, instead of going round the edge, you work back by the side of the first row of stitching, there results a streakiness of texture, apparent in the stem on Illustration 13. What you get is, in effect, a combination of crewel and outline stitches, as at J, which in the other case only occurs in the centre of the shape where the files of stitches meet.

To represent shading in crewel-stitch, to which it is admirably suited (A, Illustration 41), it is well to work from the darkest shadows to the highest lights. And it is expedient to map out on the stuff the outline of the space to be covered by each shade of thread. There is no difficulty then in working round that shape, as above explained.

In solid crewel the stitches should quite cover the ground without pressing too closely one against the other.

It does not seem that Englishwomen of the seventeenth century were ever very faithful to the stitch we know by the name of crewel. Old ex-





15. CREWEL-STITCH IN TWISTED SILK.



amples of work done entirely in crewel-stitch, as distinguished from what is called crewel work, are seldom if ever to be met with. The stitch occurs in most of the old English embroidery in wool ; but it is astonishing, when one comes to examine the quilts and curtains of a couple of hundred years or so ago, how very little of the woolwork on them is in crewel-stitch. It is only in the main stem and in some of the outlines of the detail given on page 31 that the stitch is used, though the illustration (13) was chosen because it contained more of it than any other equal portion of the handsome and typical English hanging of which it is part. And it appears to have been the prevailing practice to use crewel-stitch for stems and outlines, and for little else but the very simplest forms. The filling in of the leafage, the diapering within the leaf shapes, and the smaller and more elaborate details generally were done in long-and-short-stitch, or whatever came handiest. In fact, the thing to be represented, fruit, berry, flower, or what not, seems to have suggested the stitch, which it must be confessed was sometimes only a sort of scramble to get an effect.

Of course the artist always chooses her stitch, and she is free to alter it as occasion may demand ; but a good workwoman (and the embroidress is a needlewoman first and an artist afterwards, perhaps) adopts in every case a method, and departs from it only for very good reason. It looks as if these ancestors of ours had set to work

without system or guiding principle at all. No doubt they got a bold and striking effect in bed-hangings and the like ; but there is in their work a lack of that conscious aim which goes to make art. Theirs is art of the rather artless sort which is just now so popular. Happily it was kept in the way it should go by unconscious adherence to traditional pattern. We, unfortunately, have broken with tradition.

Quite in the traditional manner is Illustration 14. One would fancy at first sight that the work was almost entirely in crewel-stitch. As a matter of fact, there is little which answers to the name, as an examination of the back of the work shows plainly enough. What the stitches are it is not easy to say. The mystery of many a stitch is to be unravelled only by literally picking out the threads, which one is not always at liberty to do, although, in the ardour of research, a keen embroidress will do it—not without remorse in the case of beautiful work, but relentlessly all the same.

The only piece of embroidery entirely in crewel-stitch which I could find for illustration (15) is worked, as it happens, in silk ; nor was the worker aware when she worked it that she was doing anything out of the common. Another instance of crewel-stitch is given in the divided skirt, let us call it, of the personage in Illustration 72.

Beautiful back-stitching occurs in the Italian work on Illustration 97, and the stitch is used for sewing down the *appliqué* in Illustration 102.

## CHAIN-STITCH.



16. CHAIN-STITCH AND KNOTS.

CHAIN and TAMBOUR STITCH are in effect practically the same, and present the same rather granular surface. The difference between them is that chain-stitch is done in the hand with an ordinary needle, and tambour-stitch in a

frame with a hook sharper at the turning point than an ordinary crochet hook. One takes it rather for granted that work which was presumably done in the hand (a large quilt, for example) is chain-stitch, and that what seems to have been done in a frame is tambour work, though it is possible, but not advisable of course, to work chain-stitch in a frame.

Chain-stitch is not to be confounded with split-stitch (see page 105), which somewhat resembles it.

TO WORK  
A.

To work chain-stitch (A on the sampler, Illustration 17) bring the needle out, hold the thread



17. CHAIN-STITCH SAMPLER.





18. CHAIN-STITCH SAMPLER (BACK).



down with the left thumb, put the needle in again at the hole through which you brought it out, take up  $\frac{1}{4}$  of an inch of stuff, and draw the thread through: that gives you the first link of the chain. The back of the work (18) looks like back-stitch. In fact, in the quilted coverlet, Illustration 69 (as in much similar work of the period), the outline pattern, which you might take for back-stitching, proves to have been worked from the back in chain-stitch. The same thing occurs in the case of the Persian quilt in Illustration 70.

A playful variation upon chain-stitch (B on the sampler, Illustration 17) is effected by the use of two threads of different colour. Take in your needle a dark and a light thread, say the dark one to the left, and bring them out at the point at which your work begins. Hold the dark thread under your thumb, and, keeping the light one to the right, well out of the way, draw both threads through; this makes a dark link; the light thread disappears, and comes out again to the left of the dark one, ready to be held under the thumb while you make a light link. This "magic stitch," as it has been called, is no new invention. It is to be found in Persian, Indian, and Italian Renaissance work. An instance of it occurs in Illustration 64.

TO WORK  
B.

A variety of chain-stitch (C on the sampler, Illustration 17) used often in church work, and more solid in appearance, the links not being so

TO WORK  
C. open, is rather differently done. Begin a little in advance of the starting point of your work, hold the thread under your thumb, put the needle in again at the starting point slightly to the left, bring your needle out about  $\frac{1}{8}$  of an inch below where it first went in but precisely on the same line, and you have the first link of your chain.


TO WORK  
D. To work what is known as cable-chain (D on the sampler, Illustration 17) keep your thread to the right, put in your needle, pointing downwards, a little below the starting point, and bring it out about  $\frac{1}{4}$  of an inch below where you put it in; then put it through the little stitch just formed, from right to left, hold your thread towards the left under your thumb, put your needle through the stitch now in process of making from right to left, draw up the thread, and the first two links of your chain are made.

TO WORK  
E. A zigzag chain, of a rather fancy description, goes by the name of Vandyke chain (E on the sampler, Illustration 17). To make it, bring your needle out at a point which is to be the left edge of your work, and make a slanting chain-stitch from left to right; then, putting your needle into that, make another slanting stitch, this time from right to left—and so to and fro to the end.

TO WORK  
F. The braid-stitch shown at F on the sampler (Illustration 17) is worked as follows, horizontally from right to left. Bring your needle out at a point which is to be the lower edge of your work,

throw your thread round to the left, and, keeping it all the time loosely under your thumb, put your needle under the thread and twist it once round to the right.

Then, at the upper edge of your work, put in the needle and slide the thread towards the right, bring the needle out exactly below where you put



it in, carry your thread under the needle towards the left, draw the thread tight, and your first stitch is done.

A yet more fanciful variety of braid-stitch (G on the sampler, Illustration 17) is worked vertically, downwards. Having, as before, put your needle under the thread and twisted it once round, put it in at a point which is to be the left edge of your work, and, instead of bringing it out immediately below that point, slant it to the right, bringing it out on that edge of the work, and finish your stitch as in the case of F.

TO WORK  
G.

These braid-stitches look best worked in stout thread of close texture.

In covering a surface with chain-stitch (needlework or tambour) the usual plan is to follow the

contour of the design, working chain within chain until the leaf or whatever it may be is filled in. This stitch is rarely worked in lines across the forms, but it has been effectively used in that way, following always the lines of the warp and weft of the stuff. Even in that case the successive



THE WORKING  
OF G ON CHAIN-  
STITCH SAMPLER.

lines of stitching should be all in one direction—not running backwards and forwards—or it will result in a sort of pattern of braided lines. The reason for the more usual practice of following the outline of the design is obvious. The stitch lends itself to sweeping, even to perfectly spiral, lines—such as occur in Greek wave patterns: it was, in fact, made use of in that way by the Greeks some four or five centuries B.C.

We owe the tambour frame, they say, to China ; but it has been largely used, and abused indeed, in England. Tambour work, when once you have the trick of it, is very quickly done—in about one-sixth of the time it would take to do it with the needle. It has the further advantage that it serves equally well for embroidery on a light or on a heavy stuff, and that it is most lasting. The misfortune is that the sewing machine has learnt to





19. CHAIN AND SURFACE STITCHES.

do something at once so like it and so mechanically even, as to discredit genuine hand-work, whether tambour work or chain-stitch. For all that, neither is to be despised. If they have often a mechanical appearance that is not all the fault of the stitch: the worker is to blame. Indian embroiderers depart sometimes so far from mechanical precision as to shock the admirers of monotonously even work. Artistic use of chain-stitch is made in many of our illustrations: for outlines in Illustrations 24 and 72; for surface covering in Mr Crane's lion, Illustration 74; to represent landscape in Illustration 78, where everything except the faces of the little men is in chain-stitch; and again for figure work in Illustration 81. In Illustration 19 it occurs in association with a curious surface stitch; in Illustration 64 it is used to outline and otherwise supplement inlay. The old Italians did not disdain to use it. In fact, wherever artists have employed it they show that there is nothing inherently inartistic about the stitch.

## HERRING-BONE-STITCH.

HERRING-BONE is the name by which it is customary to distinguish a variety of stitches somewhat resembling the spine of a fish such as the herring. It would be simpler to describe them as "fish-bone"; but that term has been appropriated to describe a particular variety of it. One would have thought it more convenient to use fish for the generic term, and a particular fish for the specific. However, it saves confusion to use names as far as possible in their accepted sense.

It will be seen from the sampler, Illustration 20, that this stitch may be worked open or tolerably close; but in the latter case it loses something of its distinctive character. Fine lines may be worked in it, but it appears most suited to the working of broadish bands and other more or less even-sided or, it may be, tapering forms, more feathery in effect than fish-bone-like, such as are shown at E on sampler.

Ordinary herring-bone is such a familiar stitch that the necessity of describing it is rather a matter of literary consistency than of practical importance.

The two simpler forms of herring-bone (it is always worked from left to right, and begun with a half-stitch) marked A and C on the sampler are strikingly different in appearance, and are worked in different ways—as will be seen at once by reference to the back of the sampler (Illustration 21), where the stitches take in the one case a horizontal and in the other a vertical direction.

TO WORK  
A.

To work A, bring your needle out about the centre of the line to be worked; put it into the lower edge of the line about  $\frac{1}{8}$ th of an inch further on; take up this much of the stuff, and, keeping the thread to the right, above the needle, draw it through. Then with the thread below it, to the right, put your needle into the upper edge of the line  $\frac{1}{4}$ th of an inch further on, and, turning it backwards, take up again  $\frac{1}{8}$ th of an inch of stuff, bringing it out immediately above where it went in on the lower edge.


TO WORK  
B.

What is called "Indian Herring-bone" (B) is merely stitch A worked in longer and more slanting stitches, so that there is room between them for a second row in another colour, the two colours being, of course, properly interlaced.


TO WORK  
C.

To work C, bring your needle out as for A, and, putting it in at the upper edge of the line to be worked and pointing it downwards, whilst your thread lies to the right, take up ever so small a piece of the stuff. Then, slightly in advance of the last stitch, the thread still to the right,





20. HERRING-BONE SAMPLER.




21. HERRING-BONE SAMPLER (BACK).

your needle now pointing upwards, take another similar stitch from the lower edge.

TO WORK  
D.

The variety at D is merely a combination of A and C, as may be seen by reference to the back of the sampler (opposite); though the short horizontal stitches there seen meet, instead of being wide apart as in the case of A.



THE WORKING OF E ON HERRING-BONE SAMPLER.

What is known as "fish-bone" is illustrated in the three feathery shapes on the sampler (E), two of which are worked rather open. It is characteristic of this stitch that it has a sort of spine up the centre where the threads cross. Suppose the stitch to be worked horizontally. Bring your needle out on the under edge of the spine about  $\frac{1}{4}$ th of an inch from the starting point of the work, and put it in on the upper edge of the work at the starting point, bringing it out immediately below that on the lower edge of the work. Put it in again on the upper edge of the spine, rather in

TO WORK  
E.

advance of where it came out on the lower edge of it before, and bring it out on the lower edge of this spine immediately below where it entered.

TO WORK  
F.

In close herring-bone (F on the sampler, Illustration 20) you have always a long stitch from left to right, crossed by a shorter stitch which goes from right to left. Having made a half-stitch, bring the needle out at the beginning of the line to be worked, at the lower edge, and put




THE WORKING OF F ON HERRING-BONE SAMPLER.

it in  $\frac{1}{8}$ th of an inch from the beginning of the upper edge. Bring it out again at the beginning of this edge and put it in at the lower edge  $\frac{1}{4}$ th of an inch from the beginning, bringing it out on the same edge  $\frac{1}{8}$ th of an inch from the beginning. Put the needle in again on the upper edge  $\frac{1}{8}$ th of an inch in front of the last stitch on that edge, and bring it out again, without splitting the thread, on the same edge as the hole where the last stitch went in.

If you wish to cover a surface with herring-bone-stitch, you work it, of course, close, so that each



successive stitch touches its foregoer at the point where the needle enters the stuff (F on the sampler, Illustration 20). It will be seen that at the back (21) this looks like a double row of back-stitching. Worked straight across a wide leaf, as in the lower half of sampler, it is naturally very loose. A better method of working is shown in the side leaves, which are worked in two halves, beginning at the base of a leaf on one side and working down to it on the other. There is here just the suggestion of a mid-rib between the two rows.



THE WORKING OF G ON HERRING-BONE SAMPLER.

The stitch at G on sampler, which has the effect of higher relief than ordinary close herring-bone (F), is sometimes misleadingly described as tapestry stitch. It is worked, as the back of the sampler (21) clearly shows, in quite a different way. You TO WORK  
get there parallel rows of double stitches. Having G.

made a half-stitch entering the material at the upper edge of the work, bring the needle out on the lower edge of it immediately opposite. Then going back, put it in at the beginning of the upper edge, and bring it out at the beginning of the lower one. Thence take a long slanting stitch upwards from left to right, bring the needle out on the lower edge immediately opposite, cross it by a rather shorter stitch from right to left, entering the stuff at the point where the first half-stitch ended, bring this out on the lower edge, opposite, and the stitch is done.

The artistic use of herring-bone-stitch is shown in the leaves of the tulip (84), and a closer variety of it in the pink, or whatever the flower may be, in the hand of the little figure in Illustration 72.

## BUTTONHOLE-STITCH.

BUTTONHOLE is more useful in ornament than one might expect a stitch with such a very utilitarian name to be. It is, as its common use would lead one to suppose, pre-eminently a one-edged stitch, a stitch with which to mark emphatically the outside edge of a form. There is, however, a two-edged variety known as ladder-stitch, shown in the two horn shapes on the sampler, Illustration 22.

By the use of two rows back to back, leaf forms may be fairly expressed. In the broad leaves on the sampler, the edge of the stitch is used to emphasise the mid rib, leaving a serrated edge to them. The character of the stitch would have been better preserved by working the other way about, and marking the edge of the leaves by a clear-cut line, as in the case of the solid leaves in Illustration 73.

The stitch may be used for covering a ground or other broad surface, as in the pot shape (J) on the sampler, where the diaper pattern produced by its means explains itself the better for being worked in two shades of colour.

The simpler forms of the stitch are the more

useful. Worked in the form of a wheel, as in the rosettes at the side of the vase shape (A), the ornamental use of the stitch is obvious.

TO WORK

A.

One need hardly describe BUTTONHOLE-STITCH. The simple form of it (A) is worked by (when you have brought your needle out) keeping the thread under your thumb to the right, whilst you put the needle in again at a higher point slightly to the right, and bring it out immediately below, close to where it came out before. This and other one-edged stitches of the kind are sometimes called "blanket-stitch."

The only difference between versions such as B and C on the sampler, and simple buttonhole, is that the stitches vary in length according to the worker's fancy.

TO WORK

E.

The CROSSED BUTTONHOLE-STITCH at E is worked by first making a stitch sloping to the right, and then a smaller buttonhole-stitch across this from the left.

The border marked D in sampler consists merely of two rows of slanting buttonhole-stitch worked one into the other. Needlewomen have wilful ways of making what should be upright stitches slant awkwardly in all manner of ways, with the result that they look as if they had been pulled out of the straight.

The border at F, known as "TAILOR'S BUTTONHOLE," is worked with the firm edge from you, instead of towards you, as you work ordinary





22. BUTTONHOLE SAMPLER.



23. BUTTONHOLE SAMPLER (BACK).

buttonhole. Bringing the thread out at the upper edge of the work to the left, and letting it lie on that side, you put your needle in again still on the same edge, and bring it out, immediately below, on the lower one. You then, before drawing the thread quite through, put your needle into the loop from behind, and tighten it upwards.

In order to make your "Ladder-stitch" (G) square at the end, you begin by making a bar of the width the stitch is to be. Then, holding the thread under your thumb to the right, you put the needle in at the top of the bar and, slanting it towards the right, bring it out on a level with the other end of the bar somewhat to the right. This makes a triangle. With the point of your needle, pull the slanting thread out at the top, to form a square; insert the needle; slant it again to the right; draw it out as before, and you have your second triangle.



TO WORK  
G.

THE WORKING OF H  
ON BUTTONHOLE  
SAMPLER.

The difference between the working of the lattice-like band at H, and ladder-stitch G, is that, having completed your first triangle, you make, by means of a buttonhole-stitch, a second triangle pointing the other way, which completes a rectangular shape.

TO WORK  
H.





24. BUTTONHOLE, CHAIN, AND KNOT STITCHES.



In the solid work shown at J, you make five buttonhole-stitches, gathering them to a point at the base, then another five, and so on. Repeat the process, this time point upwards, and you have the first band of the pot shape.

Characteristic and most beautiful use is made of buttonhole-stitch in the piece of Indian work in Illustration 24, where it is outlined with chain stitch, which goes most perfectly with it.

Cut work, such as that on Illustration 65, is strengthened by outlining it in buttonhole-stitch.

Ladder-stitch occurs in the cusped shapes framing certain flowers in Illustration 72, embroidered all in blue silk on linen. It is not infrequent in Oriental work, and, in fact, goes sometimes by the name of Cretan-stitch on that account.

## FEATHER AND ORIENTAL STITCHES.

FEATHER-STITCH is simply buttonholing in a slanting direction, first to the right side and then to the left, keeping the needle strokes in the centre closer together or farther apart according to the effect to be produced.

It owes its name, of course, to the more or less feathery effect resulting from its rather open character. Like buttonhole, it may be worked solid, as in the leaf and petal forms on the sampler, Illustration 25, but it is better suited to cover narrow than broad surfaces. The jagged outline which it gives makes it useful in embroidering plumage, but it is not to be confounded with what is called "plumage-stitch," which is not feather-stitch at all, but a version of satin-stitch.

The feathery stem (A) on sampler is simply a buttonholing worked alternately from right to left and left to right.

TO WORK  
B.

The border line at B requires rather more explanation. Presume it to be worked vertically. Bring your needle out at the left edge of the band; put it in at the right edge immediately opposite, keeping your thread under the needle to the right;



25. FEATHER-STITCH SAMPLER.



26. FEATHER-STITCH SAMPLER (BACK).




bring it out again still on the right edge a little lower down, and then, keeping your thread to the left, put the needle in on the left edge, opposite to where you last brought it out, and bring it out again on the same edge a little lower down.

The border at C is merely an elaboration of the above, with three slanting stitches on each edge instead of a single one in the direction of the band.

Bands D, E, F, G, are variations of ordinary feather-stitch, requiring no further explanation than the back view of the work (26) affords. On the face of the sampler it will be noticed that lines have been drawn for the guidance of the worker. These are always four in number, indicating that the stitch is made with four strokes of the needle, and showing the points at which it is put in and out of the stuff.

In working G G, suppose four guiding lines to have been drawn as above—numbered, 1, 2, 3, 4, from left to right. Bring your needle out at the top of line 1. Make a chain-stitch slanting downwards from line 1 to line 2. Put your needle into line 3 about  $\frac{1}{4}$ th of an inch lower down, and, slanting it upwards,



THE WORKING OF G G  
ON FEATHER-STITCH  
SAMPLER.

TO WORK  
G G.

bring it out on line 4, level with the point where you last brought it out. Make a chain-stitch slanting downwards, this time from right to left, and bring your needle out on line 3. Lastly, put your needle into line 2,  $\frac{1}{8}$ th of an inch below the last stitch, and, slanting it upwards, bring it out on line 1.

Feather-stitch is not adapted to covering broad surfaces solidly, but may be used for narrow ones.


ORIENTAL-STITCH is the name given to a close kind of feather-stitch much used in Eastern work. The difference between the two, at once apparent to the eye, is that, whereas for the mid-rib of a band or leaf of feather-stitching (25) you have cross lines, in Oriental-stitch (27) you have a straight line—longer or shorter as the case may be.

Oriental-stitch is sometimes called "Antique-stitch," and is a stitch in three strokes, just as feather-stitch is a stitch in four. It is usually worked horizontally, though shown upright on the sampler. Like feather-stitch (compare diagrams on pages 65 and 69), it is worked on four guiding lines, faintly visible on the sampler.


TO WORK

A,  
B,  
C.

Stitches A, B, and C are worked in precisely the same way. Bring your needle out at the top of line 1. Keep the thread under your thumb to the right and put your needle in at the top of line 4, bringing it out into line 3 on the same level. Then put it in again at line 2, just on the other side of the thread, and bring it out on line 1 ready to begin the next stitch.




27. ORIENTAL-STITCH SAMPLER.



28. ORIENTAL-STITCH SAMPLER (BACK).



It will be seen that the length of the central part (or mid-rib, as it was called above) makes the whole difference between the three varieties of stitch. In A the three parts are equal: in B the mid-rib is narrow: in C it is broad,



THE WORKING OF A, B, C ON ORIENTAL-STITCH SAMPLER.

as is most plainly seen on the back of the sampler (28). The difference is only a difference of proportion.

The sloping stitch at D is worked in the same way as A, B, C, except that instead of straight strokes with the needle you make slanting ones.

TO WORK  
D.

Stitch E differs from D in that the side strokes slant both in the same direction. It is worked from right to left instead of from left to right.

TO WORK  
E.

Stitch F is a combination of buttonhole and Oriental stitches. Between two rows of button-

TO WORK  
F.

holing (dark on sampler) a single row of Oriental-stitch is worked.

The stitch employed for the central stalk, G, has really no business on this sampler, except that it looks rather like a continuous Oriental-stitch.

Oriental-stitch is one of the stitches used in the mixed embroidery in Illustration 72.


## ROPE AND KNOT STITCHES.

A single sampler is devoted to ROPE and KNOTTED STITCHES. They are more nearly akin than they look, for rope-stitch is all but knotted as it is worked.

ROPE-STITCH is so called because of its appearance. It takes a large amount of silk or wool to work it, but the effect is correspondingly rich. It is worked from right to left, and is easier to work in curved lines than in straight.

Lines A on the sampler, Illustration 29, represent the ordinary appearance of the stitch ; its construction is more apparent in the central stalk B, which is a less usual form of the same stitch, worked wider apart.


Having brought out your needle at the right end of the work, hold part of the thread towards the left, under the thumb, the rest of it falling to the right ; put your



TO WORK  
A, B.

THE WORKING OF A, B, ON ROPE-STITCH  
SAMPLER.

needle in above where it came out, slant it towards you, and bring it out again a little in advance of where it came out before, and just below the thread held under your thumb. Draw the thread through, and there results a stitch which looks rather like a distorted chain stitch (B). The next step is to make another similar stitch so close to the foregoing one that it overlaps it partly. It



THE WORKING OF C ON ROPE-STITCH SAMPLER.

is this overlapping which gives the stitch the raised and rope-like appearance seen at A.

A knotted line (C on the sampler, Illustration 29) is produced by what is known as "GERMAN KNOT-

STITCH," effective only in thick soft silk or wool.

TO WORK C. Begin as in rope-stitch, keeping your thread in the same position. Then put your needle into the stuff just above the thread stretched under your thumb, and bring it out just below and in a line with where it went in; lastly, keep the needle above the loose end of the thread, draw it through, tightening the thread upwards, and you have the first of your knots: the rest follow at intervals determined by your wants.

TO WORK D. The more open stitch at D is practically the same





29. ROPE-STITCH AND KNOT-STITCH SAMPLER.



30. ROPE-STITCH AND KNOT-STITCH SAMPLER (BACK).


thing, except that in crossing the running thread you take up more of the stuff on each side of it.

What is known by the name of "OLD ENGLISH KNOT-STITCH" (E) is a much more complicated stitch. Keeping your thread well out of the way TO WORK  
to the right, put your needle in to the left, and E.  
take up vertically a piece of the stuff the width of the line to be worked at its widest, and draw the thread through. Then, keeping it under the thumb to the left, put your needle, eye first, downwards, through the slanting stitch just made; draw the thread not too tight, and, keeping it as before under the thumb, put your needle, eye first, this time through the upper half only of the slanting stitch, making a kind of buttonhole-stitch round the last, and draw out your thread.

The importance of these rather ragged-looking and fussy knotted rope stitches, by whatever name they are called, may easily be over-rated. They are not much more than fancy stitches. KNOTS used separately are of much more artistic account.

BULLION or ROLL-STITCH is shown in its simplest form in the petals of the flowers F on the sampler, Illustration 29. To work one such petal, begin TO WORK  
by attaching the thread very firmly; bring your F.  
needle out at the base of the petal, put it in at the tip, and bring it out once more at the base, only drawing it partly through. With your right hand wind the thread, say seven times, round the projecting point of the needle from left to right. Then,

holding the coils under your left thumb, your thread to the right, draw your needle and thread through; and, dropping the needle, and catching the thread round your little finger, take hold of the thread with your thumb and first finger and draw the coiled stitch to the right, tightening it gently



THE WORKING OF F ON KNOT-STITCH SAMPLER.


until quite firm. Lastly, put the needle through at the tip of the petal, and the stitch is complete and ready to be fastened off.

The leaves of these flowers consist simply of two bullion stitches. The bullion knots at the side of the central stalk are curled by taking up in the first instance only the smallest piece of the stuff.



To work FRENCH KNOTS (G), having brought TO WORK  
 out your needle at the point where the knot is to G.  
 be, hold the thread under your thumb, and, letting  
 it lie to the right, put your needle under the  
 stretched part of it. Turn the needle so as to  
 twist the thread once round it. That done, put  
 the needle in again about where it came out,  
 draw it through from the back, and bring it out  
 where the next knot is to be.

For large knots use two or more threads  
 of silk, and do not  
 twist them more than  
 once. With a single  
 thread you may twist  
 twice, but the result  
 of twisting three or  
 four times is never  
 happy.



THE WORKING OF G ON  
 KNOT-STITCH SAMPLER.

The use of knots is well shown in Illustration  
 24. Worked there in white silk floss upon a dark  
 purple ground, they are quite pearly in appear-  
 ance, whether in rows between the border lines,  
 or scattered over the ground. They are most  
 useful in holding the design together, giving it  
 mass, and go admirably with chain-stitching, to  
 which, when close together, they have at first  
 sight some likeness. A single line of knots may  
 almost be mistaken for chain-stitch; but of them-  
 selves they do not make a good outline, lacking  
 firmness. A happier use of them is to fringe an

outline, as for example in the peacock's tail on page 38 ; but this expedient must be used with reticence, or it results in a rather rococo effect. Good use is sometimes made of knots to pearl the inner edge of a pattern worked in outline, or to pattern the ornament (instead of the ground) all over. Differencing of this kind may be an after-thought—and a happy one—affording as it does a ready means of giving texture or of qualifying a colour which may not have worked out quite to the embroiderer's liking.

The obvious fitness of knots to represent the stamens of flowers is exemplified in Illustration 101. Worked close together, they represent admirably the eyes of composite flowers, as on the sampler ; they give, again, valuable variety of texture to the crest of the stork in Illustration 85.

The effect of knotting in the mass is shown in Illustration 31, embroidered entirely in knots, contradicting, it might seem, what was said above about its unfitness for outline work. The lines, even the voided ones, are here as sharp as could be ; but then, it is not many of us who work, knot by knot, with the marvellous precision of a Chinaman. His knotted texture is not, however, always what it seems. He has a way of producing a knotted line by first knotting his thread (it may be done with a netting needle), and then stitching it down on to the surface of the material, which gives a




31. A TOUR DE FORCE IN KNOTS.


pearled or beaded line not readily distinguishable from knot stitch.

The Japanese embroiderer, instead of knotting his own thread, employed very often a crinkled braid. This is shown in the cloud work in Illustration 85. The only true knotting there is in the top-knot of the bird.





32. INTERLACING-STITCH SAMPLER.



33. INTERLACING-STITCH SAMPLER (BACK).

## INTERLACINGS, SURFACE STITCHES, AND DIAPERS.

The samplers so far discussed bring us, with the exception of Darning, Satin-stitch, and some stitches presently to be mentioned, practically to the end of the stitches, deserving to be so called, generally in use.

By combining two or more stitches endless complications may be made; and there may be occasions when, for one purpose or another, it may be necessary, as well as amusing, to invent them. In this way stitches are also sometimes worked upon stitches, as shown on the sampler, Illustration 32. You will see, on referring to the back of it (33), that only the white silk is worked into the stuff: the dark threads are surface work only. There is no end to such possible INTERLACINGS. Those on the sampler do not need much explanation; but it may be as well to say that A starts with crewel-stitching; B and C with back-stitching; D with chain-stitching; E with darning or running; F, G, and H with varieties of herring-bone-stitch; J with Oriental-stitch; and K with feather-stitch. It is not difficult by following the interlacings of the darker threads to detect

the surface work upon the white. C and G undergo a second course of interlacing.

The danger of splitting the first stitches in



THE WORKING OF F ON INTERLACING-STITCH SAMPLER.

working the interlacing ones, is avoided by passing the needle eye first through them.

Other surface work, sometimes called LACE-STITCH, is illus-

trated in the sampler, Illustration 34. There is really no limit to patterns of this kind. Some are better worked in a frame, but that is very much a matter of personal practice.

TO WORK  
H.


In the Surface Darning at H (34) long threads are first carried from edge to edge of the square, there only piercing the stuff, and then darned across by other stitches, again only piercing it at the edges.

An oblique version of this is given at C (34).

TO WORK  
B.

The Lace Button-holing at B (34) is worked as follows:—Buttonhole three stitches into the stuff from left to right, not quite close together, and further on three more; then, working from right to left, make three buttonhole stitches into the thread connecting the stitch groups; but do not stitch into the stuff except at the ends of the rows. The last row must, of course, be worked into the stuff again.





34. SURFACE-STITCH SAMPLER.

TO WORK F. Net Passing, as at F (34), is not very differently worked from A, only it is much more open. The first row of horizontal stitches is crossed by two opposite rows of oblique stitches, which are made to interlace.

TO WORK G. The square at G is worked by first making rows of short upright stitches worked into the stuff, and then threading loose stitches through them.

TO WORK D. The square at D is worked on the open lattice shown ; the solid parts are produced by interlacing stitches from side to side, starting at the angle.

In the square at E (Japanese Darning) horizontal lines are first darned, and then zigzag lines are worked between them, much as in G ; but, as they penetrate the material, this is scarcely a surface stitch.

TO WORK A. The horizontal lines at top and bottom of the square at A are back-stitching, the intermediate ones simply long threads carried from one side to the other ; they are laced together by lines looped round them.

TO WORK L. The band at L is begun by making horizontal bar stitches. A row of crewel-stitch and one of outline-stitch, worked on to the bars and not into the stuff, makes the central chain.

TO WORK K. The band at K is merely surface buttonholing over a series of slanting stitches.

TO WORK J. The band at J is buttonhole stitching wide apart, the bars filled in with surface crewel-stitch.

Most delicate surface stitching occurs in Illus-



35. LACE OR SURFACE STITCH.

tration 35, the fine net being worked only from edge to edge of the spaces it fills, and not elsewhere entering the stuff; which accounts for most of it being worn away. The flower or scroll-work is substantial embroidery, worked through the stuff. The delicate network of fine stitching, which once covered the whole of the background, is neither more nor less than a floating gossamer of lacework. One cannot deny that this is embroidery, though it has to be admitted that *lace-stitches* are employed in it.

Stern embroiderers would like to deny it. Of course it is frivolous, and in a sense flimsy, but it is also delicate and dainty to a degree. It is suited only to dress, and that of the most exquisite kind. A French marquise of the Regency might have worn it, and possibly did wear it, with entire propriety—if the word is not out of keeping with the period.

The frailty of this kind of thing is too obvious to need mention, and that, of course, is a strong argument against it.

All attempt to give separate names to diapers of this kind, whether worked upon the surface or into the stuff, is futile. They ought not even to be called stitches, being, in fact, neither more nor less than stitch patterns, to which there is no possible limit, unless it be the limit of human invention. Every ingenious workwoman will find out patterns of her own more or less. They are very useful for



filling in surfaces (pattern or background) which it may be inexpedient to work more solidly.

The greater part of such patterns are geometric (Illustrations 35 and 73), following, that is to say, the mesh of the material, and making no secret of it. On Illustration 3, where, by the way, the relation of stitch to stuff is obvious, you see very plainly how the rectangular diaperings are built up geometrically on the square lines of the mesh, as was practically inevitable working on such a ground. In any case, however, preceptible weaving lines facilitate the setting out of geometric diaper.

The choice of stitch patterns of this kind is inevitably left to the needlewoman. The utmost a designer need do is to indicate on his drawing that a "full," "open," or "intermediate" diaper is to be used. Still, the alternation of lighter and heavier diapers should be planned and not left altogether to impulse, though the pattern may be. Moreover, there is room for the exercise of considerable taste in the choice of simpler or more elaborate patterns, freer or more geometric. Many a time the shape of the space to be filled, as well as its extent, will suggest the appropriate ornament. The diaper design is not, of course, drawn on the stuff, but points of guidance may be indicated through a kind of fine stencil plate, supposing the weave of the stuff not to be plain enough to go by.

The patterns used for background diapering

need not, as a rule, be intrinsically so interesting as those which diaper the design itself, nor are they usually so full. They take more often the form of spot or sprig patterns, not continuous, in which the geometric construction need not be obvious. Nor is it necessary. In either case the prime object of the stitching is not so much to make ornamental patterns as to give a tint to the stuff without entirely hiding it; and the worker chooses a lighter or heavier diaper according to the tint required.

For a background, simple darning more or less open, in stitches not too regular, is often the best solution of the difficulty. The effect of the ground colour grinning through is delightful.

In white work the purpose of the stitching is to give texture.

## SATIN-STITCH AND ITS OFFSHOOTS.

SATIN-STITCH is *par excellence* the stitch for fine silk work. I do not know if the name of "satin-stitch" comes from its being so largely employed upon satin, or from the effect of the work itself, which would certainly justify the title, so smooth and satin-like is its surface. Given a material of which the texture is quite smooth and even, showing no mesh, satin-stitch seems the most natural and obvious way of working upon it. In it the embroidress works with short, straight strokes of the needle, just as a pen draughtsman lays side by side the strokes of his pen ; but, as she cannot, of course, leave off her stroke as the penman does, she has perforce to bring back the thread on the under side of the stuff, so that, if very carefully done, the work is the same on both sides.

Satin-stitch, however, need not be, and never was, confined to work upon silk or satin. In fact it was not only worked upon fine linen, but often followed the lines of its mesh, stepping, as in Illustration 9, to the tune of the stuff. This may be described as satin-stitch in the making—at any

rate, it is the elementary form of the stitch, its relation to canvas-stitch being apparent on the face of it. Still, beautiful and most accomplished work has been done in it alike by Mediæval, Renaissance, and Oriental needleworkers.

TO WORK  
A.

To cover a space with regular vertical satin stitches (A on the sampler, Illustration 36), the best way of proceeding is to begin in the centre of the space and work from left to right. That half done, begin again in the centre and work from right to left.

In order to make sure of a crisp and even edge to your forms, always let the needle enter the stuff there, as it is not easy to find the point you want from the back.


In working a second row of stitches, proceed as before, only planting your needle between the stitches already done. Fasten off with a few tiny surface stitches and cut off the silk on the right side of the stuff: it will be worked over.

TO WORK  
B.


To cover a space with horizontal satin stitches (B on sampler), begin at the top, and work from left to right. The longer stretches there are not, of course, crossed at one stitch; they take several stitches, dovetailed, as it were, so as not to give lines.

The easiest, most satisfactory, and generally most effective way of working flat satin stitch is in oblique or radiating lines (C, D, E), working in those instances, as in the case of A, from the





36. SATIN-STITCH SAMPLER.



37. SATIN-STITCH SAMPLER (BACK).

centre, first from left to right and then from right to left.

Stems, narrow leaflets, and the like, are best worked always in stitches which run diagonally and not straight across the form.

In the case of stems or other lines curved and worked obliquely, the stitches must be very much closer on the inner side of the curve than on the outside: occasionally a half-stitch may be necessary to keep the direction of the lines right, in which case the inside end of the half-stitch must be quite covered by the stitch next following.

Satin-stitch is seen at its best when worked in floss. Heavy or twisted silk looks coarse in this stitch, as may be seen by comparing the petal D in the sampler, Illustration 36, with the petal in twisted silk here given (38). Even the needle-



38. SATIN-STITCH IN COARSE  
TWISTED SILK.

workers of India, astonishingly skilful as they are, get rather broken lines when they work in thick twisted silk (Illustration 39). The precision of line a skilled worker can get in floss is wonderful. An Oriental will get sweeping lines as clean and firm



as if they had been drawn with a pen, and this not merely in the case of an outline, but in voided lines of which each side has to be drawn with the needle. The voided outline, by the way, as on Illustrations 39, 40, is not only the frankest way of defining form, but seems peculiarly proper to satin-stitch. And it is a test of skill in workmanship: it is so easy to disguise uneven stitching by an outline in some other stitch. The voiding in the wings of the birds in Illustration 40 is perfect; and the occasional softening of the voided line, as in the wing of the bird at the bottom of Illustration 40, by stitching in threads comparatively wide apart, is quite the right thing to do. It would have been more in keeping to void the veins of the lotus leaves than to plant them on in cord in the way that has been adopted.

Satin-stitch must not be too long; and it is often a serious consideration with the designer how to break up the surfaces to be covered so that only shortish stitches need be used. You might follow the veining of a leaf, for example, and work from vein to vein. But all leaves are not naturally veined in the most accommodating manner. Treatment is accordingly necessary, and so we arrive at a convention appropriate to embroidery of this kind. It takes a draughtsman properly to express form by stitch distribution. The Chinese convention in the lotus flowers (Illustration 40) is admirable.

It is the rule of the game to lay satin-stitch





39. SATIN-STITCH IN FINE TWISTED SILK.

very evenly. Worked in floss, the mere surface of satin-stitch is beautiful. A further charm lies in the way it lends itself to gradation of colour. Beautiful results may be obtained by the use of perfectly flat tints of colour, as in Illustration 40; but the subtlest as well as the most deliberate gradation of tint may be most perfectly rendered in satin-stitch.

TO WORK  
SURFACE  
SATIN-  
STITCH.

SURFACE SATIN-STITCH (not the same on both sides), though it looks very much like ordinary satin-stitch, is worked in another way. The needle, that is to say, after each stitch is brought *immediately* up again, and the floss is carried back on the upper instead of the under side of the stuff. Considerable economy of silk is effected by thus keeping the threads as much as possible on the surface, but the effect is apt to be proportionately poorer. Moreover, the work is not so lasting as when it is solid. The satin-stitch in Illustration 58 is all surface work. It looks loose, which it is always apt to do unless it is kept stretched on the frame, on which satin-stitch is for the most part worked. Very effective Indian work is done of this kind—loose and flimsy, but serving a distinct artistic purpose. It is to embroidery of more precious kind what scene painting is to serious mural decoration.

Embroidery is often described as being in “long-and-short-stitch,” a term properly descriptive not of a stitch, but of its dimensions. Whether you



40. CHINESE SATIN-STITCH.

use stitches of equal or of unequal length is a question merely of the adaptation of the stitch to its use in any given instance; there is nothing gained by calling an arrangement of alternating stitches, "long and short," or by calling them "plumage-stitch," or, which is more misleading, "feather-stitch," when they radiate so as to follow the form, say, of a bird's breast. The bodies of the birds in Illustrations 40 and 85 are in plumage-stitch so called. This adaptation of stitch to bird or other forms gives the effect of fine feathering perfectly. But there is no good reason for applying the term "satin-stitch" exclusively to parallel lines of stitches all of a length.

"Long - and - short - stitch," then, is a sort of satin-stitch; only, instead of the stitches being all of equal length, they are worked one *into* the others or *between* them, as in the faces in Illustrations 79 and 80.

A little further removed from satin-stitch is what is known as "split-stitch," in which the needle is brought up *through* the foregoing stitch, and splits it. The way of working this stitch is more fully described on page 105.

The worker adapts, as a matter of course, the length of the stitch to the work to be done, directing it also according to the form to be expressed, and so arrives, almost before he is aware of it, by way of satin-stitch, at what is called plumage-stitch.





41. OFFSHOOTS FROM SATIN AND CREWEL STITCHES.



42. OFFSHOOTS FROM SATIN AND CREWEL STITCHES (BACK).

The distinction between the stitches so far described is plain enough, and an all-round embroidress learns to work them; but workers end in working their own way, modifying the stitch according to the work it is put to do, and constantly arrive at results it would be difficult to describe and pedantic to find fault with. Even short, however, of such individual treatment, the mere adaptation of the stitch to the lines of the design removes it from the normal. It makes a difference, too, whether it is worked in a frame or in the hand: in the one case you see more likeness to one stitch, in the other to another. The flower at B, for example, and the leaf at D on the sampler, Illustration 41, are both



THE WORKING OF B ON  
SAMPLER 41.

worked in what is commonly called "plumage," or "embroidery" stitch, though the term "dovetail," sometimes employed, is used with quite as much, if not more, reason. Instance B, however, is worked in the hand, and D in a frame—from which very fact it follows that the worker is naturally disposed



to regard B as akin to crewel-stitch and D to satin-stitch, between which two stitches "dovetail," or whatever it is to be called, may be regarded as the connecting link.

TO WORK  
B.

The petals at B are worked in the method illustrated in the diagram on page 103. The first step is to edge the shape with satin-stitches in threes, successively long, shorter, and quite short. This done, starting at the base again, you put your needle in on the upper or right side of the first short stitch, and bring it out through the long stitch (as shown in the diagram). You then make a short stitch by putting your needle downwards through the material, and taking up a small piece of it. You have finally only to draw the needle through, and it is in position to make another long stitch. As the concentric rings of stitching become smaller, you make, of course, shorter stitches, and you need no longer pierce the thread of the long stitch.

TO WORK  
D.

The working of the scroll at D on the sampler, Illustration 41, needs no detailed explanation. Any one who is acquainted with the way satin-stitch is worked (it has already been sufficiently explained), and has read the above account of the working of B, will understand at once how that is worked in the frame.

It will be seen that there is a slight difference in effect between framework and work done in the hand, arising from the fact that the one is necessarily



more loosely and not quite so evenly done as the other.

Split-stitch (C on the sampler), again, resembles either crewel-stitch or satin-stitch, according as it is worked in the hand or on a frame. In working in the hand, you take a rather shorter stitch back than in crewel-stitch, piercing with the needle the thread which is to form the next stitch. In working on a frame, you bring your needle always up through the last made satin-stitch in order to start the next. Whichever way it is done, split-stitch is often difficult to distinguish without minute examination from chain-stitch. It may be interesting to compare it with crewel-stitch (A on the sampler), which is also a favourite stitch for shading. Further reference to its use is made in the chapter on shading (page 188).

TO WORK  
SPLIT-  
STITCH  
C.


## DARNING.

It is the peculiarity of DARNING and RUNNING that you make several stitches at one passing of the needle.

Darning and running amount practically to the same thing. Darning might be described as consecutive lines of running. The difference is, in the main, a matter of multiplication ; but the distinction is sometimes made that in running the stitches may be the same length on the face as on the reverse of the stuff, whereas in darning the thread is mainly on the surface, only dipping for the space of a single thread or so below it.

It results from the way of working that you get in darning an interrupted line which is characteristic of the stitch. What is called "double darning," by which the breaks in the single darning are made good, has in effect no character of darning whatever.

Darning has a homely sound, but it is useful for more than mending. In embroidery you use it no longer to replace threads worn away, but to build up upon the scaffolding of a merely serviceable material what may be a gorgeous design in silk.



43. DARNING SAMPLER.

Darning is worked, of course, in rows backwards and forwards ; but if the stitches are long and in the direction of the weft, it is as well not to run the returning row next to the one just done, but to leave space for a second course of darning afterwards between the open rows.

The darning of the sampler, Illustration 43, is very simple. The flower is darned in stitches of fairly equal length, taking up one thread of the material, and covering a space of almost a quarter of an inch before taking up the next thread. The outline of a petal is first worked, and successive rows of darning follow the lines of the flower, expressing to some extent its form. Much depends upon the direction of the stitch.

The texture of the work depends upon the length of the stitches, and on the amount of the stuff showing through.

Darning is usually supplemented by outlining. The sampler is designed to show how far one can dispense with it. The flower stalk is defined by darning the first row in a darker colour ; for the rest, voiding is employed, but it is not easy to void in darning.

The background is darned diaper fashion. It gives, that is to say, deliberately diagonal lines. A background irregularly darned should be irregular enough never to run into lines the worker did not contemplate.

In the case of large leaves, veined, the veining





44. DARNING DESIGNED BY WILLIAM MORRIS.

should be worked first, and the stitches between them should radiate outwards to the edge of the leaf.

More accomplished work in darning is shown in the border by William Morris in Illustration 44, where, however, it appears much flatter than in the coloured silk. It is worked solid, the radiating stitches accommodating themselves to the forms of the leaves and petals, which, in fact, are designed with a view to their execution in this way. They are defined by outline-stitching—light or dark as occasion seemed to require.

Mention has already been made of darning *à propos* of canvas-stitch; and there is a sort of natural correspondence between the mechanism of darning in its simplest form and the network of open threads which gives to rectangular work like that opposite a character which more than compensates for its angularity in outline. The darning is there quite even in workmanship, but it is, as will be seen, of different degrees of strength—lighter for the surface of the pattern, heavier for the outline.

You may qualify the colour of a stuff by lightly darning it with silk of another shade; and very subtle tints may be got by thus, as it were, veiling a coloured ground with silks of various hues.



45. FLAT DARNING UPON A SQUARE MESH.




## LAID-WORK.

The necessity for something like what is called "LAID-WORK" is best shown by reference to satin-stitch. It was said in reference to it that satin-stitches should not be too long. There is a great deal of Eastern work in which surface satin-stitch, or its equivalent, floats so loosely upon the face of the stuff that it can only be described as flimsy. Nothing could be more beautiful in its way than certain Soudanese embroidery, in which coloured floss in stitches an inch or more long lies glistening on the stuff without any interruption of threads to fasten it down.

Embroidery of this kind, however, hardly comes within the scope of practical work. Long, loose stitches want sewing down. Some compromise has to be made between use and beauty. The problem is to make the work strong enough without seriously disturbing its lustrous surface, and the solution of it is "laid-work," at which we arrive thus almost of necessity.

It involves no new stitch, but is only another way of using stitches already described. In laid-work, long tresses of silk, as William Morris called





46. LAID-WORK SAMPLER.

H

them, floss by preference, are thrown backwards and forwards across the face of the stuff, only just dipping into it at the edges of the forms, and up again. These silken tresses are then caught down and kept, I will not say close to the ground, but in their place upon it, by lines of stitching in the cross direction.

Laid-work is not, at the best, a very strong or lasting kind of embroidery (it needs to be carefully covered up even as it is worked); but by no other means is the silky beauty of coloured floss so perfectly set forth. It is hardly worth doing in anything but floss.

Laid-work lends itself also to gradation of colour within certain limits—the limits, that is to say, of the straight parallel lines in which the floss is laid; the direction of these is determined often by the lines of sewing which are to cross them. In any case the direction of the threads is here more than ever important. The sewing down must take lines and may form a pattern.

The sampler, Illustration 46, wants little or no explanation. It illustrates the various ways of laying. In the leaf the floss is sewn down with split-stitch, which forms the veining. Elsewhere it is kept in place by “couching,” a process presently to be described (page 122). For the outlines, split-stitch and couching are employed. The last row of laid work in the grounding is purposely pulled



47. JAPANESE LAID-WORK.

out of the straight by the couching in order to give a waved edge. The diaper which represents the seeding of the flower is not, properly speaking, laid-work : separate threads of white purse silk are one by one couched down with dark.

For the transverse stitching, for which also it is best to use floss, either split-stitch may be used, as in the leaf in the sampler, Illustration 46, or a thread may be laid across and sewn down—couched, that is to say—as in the flower. The closer the cross lines the stronger the work, but the less lustrous the effect.

Laid floss may be employed to glorify the entire surface of a linen material, as in the sampler, or for the pattern only, as in Illustrations 47, 48, 49, if the ground is worth showing.

Laid-work will not give anything like modelling, and it is not best suited to figure design, except where it is quite flatly treated. An instance of its use in figure work occurs in Illustration 79. It is effective when quite naïvely and simply used in cross lines which do not appear to take any account of the forms crossed—as, for example, in Illustration 47, where the stitching does not pretend to express more than a flat surface. The floss, however, is there carefully laid at a different angle of inclination in each petal, so as to give variety of colour. The lines of sewing vary according to the lines of the laid floss, but do not cross them at right angles. The important thing is, of course, that they should





48. INDO-PORTUGUESE LAID-WORK.

catch the laid "tresses" at intervals not too far apart. If the lines which sew down the floss have also to express drawing, as in the case of the bird's wings in Illustration 48, the underlying floss must be laid in such a direction that they will cross it. In the case of the leaves in the same piece of work, the floss is laid in the direction in which the leaf grows, and the stitching across, which sews it down, is slightly curved so as to suggest roundness in them.

A more finished piece of work is shown in Illustration 49, where the laid floss crosses the forms, and the sewing down takes very much the place of veining in the flower, and of ribs in the scroll, expressing about as much modelling as can be expressed this way, and more, perhaps, than it is advisable often to attempt.

The sewing down asserts itself most, of course, when it is in a colour contrasting with the laid floss, as it does in the leaves in the smaller sampler overleaf (50).

The stitching down makes usually a pattern more or less conspicuous. On this same sampler it does so very deliberately in the case of the broad stalk. The rather sudden variation of the colour shown there in the leaves is harmless enough in bold work, to which the process is best suited. One may be too careful in gradating the tints: timidity in this respect prevails too much among modern needlewomen: an artist in floss



49. ITALIAN LAID-WORK.

should not want her work to look like a graduated wash of colour. The Italians of the sixteenth and seventeenth centuries (Illustration 49) were not afraid of rather abrupt transition in the shades of colour they used for laid-work.

When laid floss is kept in place by threads themselves sewn down across it, such threads are



50. LAID SAMPLER.

called "couched," and the work itself may be described as laid and couched. Hence arises some confusion between the two methods of work—laying and couching. It saves confusion to make a sharp distinction between the two—using the term "laid" only for stitches (floss) first loosely laid upon the surface of the stuff and then sewn



down by cross lines of stitching of whatever kind, and "couched" for the sewing down of cords, &c. (silk or gold), thread by thread or in pairs. Laid floss is sewn down *en masse*, couched silk in single or double threads. Accordingly laid-work answers best for surface covering, couched work for outlining, except in the case of gold, which even for surface covering is always couched.


## COUCHING.

COUCHING is the sewing down of one thread by another—as in the outline of the flower on the laid sampler, Illustration 46. The stitches with which it is sewn down, thread by thread, or in the case of gold, two threads at a time, are best worked from right to left, or, in outlining, from outside the forms inwards. A waxed thread is often used for the purpose. Naturally the cord to be sewn down should be held fairly tightly in place to keep the line even.

It is usual in couching to sew down the silk or cord with stitches crossing it at right angles, except in the case of a twisted cord, which should be sewn down with stitches in the direction of the twist.

Couching is best done in a frame; but it may be done in the hand by means of buttonhole-stitch.

When a surface is covered with couching, as in the seeding of the flower in the sampler, Illustration 46, the sewing down stitches make a pattern—all the plainer there, because the stitching is in a contrasting shade of colour. It is quite per-



51. A. BULLION. B. COUCHED CORD.

missible to call attention to the stitching when there is some artistic advantage in so doing. To disguise it by sewing *through* the cord is not a workmanlike practice. A worker should frankly accept a method of work. There is character to be got out of it.


Embroidresses have a clever way of untwisting a cord before each stitch and twisting it again after stitching through it—between the strands. This device by which the stitching is lost to sight is rather too clever. It shows a cord with no visible means of attachment to the ground, which is not desirable, however much desired. There is no advantage in attaching cords to the surface of silk so that they look as if they had been glued on to it. Conjuring tricks are highly amusing, but one does not think very highly of conjurers. Personally, I would much rather have seen more plainly the way the cord is sewn down in the graceful cross in Illustration 51, a design perfectly adapted to couching, and yet unlike the usual thing.

Where it is softish silk which is stitched down, it makes a great difference whether it is loosely held and tightly sewn, or the contrary. Contrast the short puffy lines nearest the corners in the sampler, Illustration 52, with the longer ones between the broad and narrow bands. The broad band is worked in rows of double filoselle, of various shades, sewn down with single filoselle. In the narrower bands twisted silk is sewn down



with stitches in the direction of its twist. This is more plainly seen in the upper of the two bands, where the sloping stitches are lighter in colour than the cord sewn down.

Characteristic use is made of rather puffy couching in the ornament of the lady's dress in Miss Keighley's panel, Illustration 61, where it has



52. COUCHING SAMPLER.

very much the richness of embroidery in seed pearls.

It was a common practice in Germany in the sixteenth century to work in solid couching upon cloth, employing a twisted thread and sewing it with stitches in the direction of the twist, so that at first sight one does not recognise it as couching. It looks like rather coarse stitching in the direction

of the forms, and expresses shading very well. The cloth ground accounts, perhaps, for the choice of method: the material is not otherwise a pleasant one to embroider upon.

A rather earlier German method was to couch in parallel lines of white upon white linen, and so get relief and texture but no modelling, though the drawing was helped by varying the direction of the parallel lines.

The entire surface of a linen ground was sometimes covered with couched threads of silk or fine wool—some of it in vertical and horizontal lines, some of it in the direction of the pattern. This, again, was a German practice, as may be seen in the Hildesheim Cope at South Kensington.

All-over couching may be used with advantage to renew the ground of embroidery so worn as to be unsightly; and it is more lasting than laid-work for the purpose. It is laborious to do, but more satisfactory when done than remounting; and one or the other is sometimes a necessity. The effect of age is, up to a certain point, pleasing: rags are not.

Couching, however (except with gold), was more commonly used for outlining, and is quite peculiarly suited to give a firm line. A beautiful example of outline work in coloured silk upon white linen is pictured in Illustration 98, in which the lines of delicate Renaissance arabesque are perfectly preserved. The rare practice of such work as



53. COUCHING IN LOOPED THREADS.

this, notwithstanding its distinguished appearance, is sufficiently accounted for by its modesty. It wants well-considered and definitely drawn design. There is no possible fudging with it.

The value of a couched cord as an outline to stitching (satin-stitch in this instance) is shown in Illustration 99, in which the singularly well-schemed and well-drawn lines of the ornament are given with faultless precision. This is a portion of an altogether admirable frame to an altogether foolish picture in needlework, of which a fragment only is shown.

The appropriateness of couched cord to the outlining of inlay or of appliqué is seen in the two examples which form Illustration 62. In the one (A) it defines the clear-cut counterchange pattern; in the other (B), being of a tint intermediate between the ground and the ornament, it softens the contrast between them. An interesting technical point in the design of this last is the way the cord outlining the leaves makes a sufficiently thick stalk, coming together, as it naturally does, double at the ends of the leaves.

This occurs again in Illustration 63, where the double threads which form the stalks, though separately stitched down, are couched again at intervals by bands crossing the two—at the springing of the stalks and tendrils, for example, where joins inevitably occur. The cords forming the central stalk are in one case looped.



Fantastic use has often been made of the looping of couched cord. The Spanish embroiderers made most ornamental use of a wee loop at the points of the leaves where the cord must turn; but the device of looping may easily be used to frivolous pur-




54. REVERSE COUCHING.

pose. A regularly looped line at once suggests lace. A perplexing Chinese practice is to couch fine cord in little loops so close together that they touch. A surface filled in after this manner, as in the butterflies on Illustration 53, might pass at first sight for French knots or chain-stitch: it is really another method of all-over couching.

A double course of couching forms the outline in Illustration 100, one of filoselle and one of cord, separately sewn; but the tendrils, which are of silver thread, are sewn down, both threads at a time, with double stitches, very obvious in the illustration. Over the couched silver threads which form the main rib of the leaf a pattern is stitched in silk.

*A propos* of couching, mention must be made of a



55. REVERSE COUCHING (BACK).

way of working used in the famous Syon Cope by way of background (Illustration 54). The ground stuff is linen, twofold, and it is worked in silk, which lies nearly all upon the surface. The stitch runs from point to point of the zigzag pattern; there it

penetrates the stuff, is carried round a thread of flax laid at the back of the material, and is brought to the surface again through the hole made by the needle in passing down. That is to say, the silken thread only *dips* through the linen at the points in the pattern, and is there caught down by a thread of flax on the under-surface of the linen. The reverse of the work (Illustration 55) shows a surface of flax threads couched with silk, for which reason the method may be described as reverse couching. On the face it gives an admirable surface diaper, flat without being mechanical. It is easily worked with a blunt needle; with a sharp one there would be a danger of splitting the stitch. It is a kind of work on which two persons might be employed, one on either side of the stuff.

## COUCHED GOLD.

Silk does not appear to have been couched in the East in early days ; and, as it was the custom to couch gold thread in Europe at least as early as the twelfth century, it is to be presumed that the method was first used for gold, which, except in the form of thin wire or extraordinarily fine thread, is not quite the thing to stitch with. Besides, it was natural to wish to keep the precious metal on the surface, and to let none of it be hidden away at the back of the stuff.

A distinguishing feature about gold is that by common consent it is used double and sewn down two threads at a time. This is not merely an economy of work ; but except in the case of thick cords or strips of gold, it has a more satisfactory effect—why it is not easy to say. Panels A, B, C, in the sampler, Illustration 56, are couched in double threads, D in single cords.

Gold couching is there used, as it mostly is, to cover a surface. In doing that, it is usual to sew the threads firmly down at the edges of the forms and cut them very sharply off ; but they may equally well be carried backwards and forwards


across the face of the stuff. The slight swelling of the gold thread where it turns gives emphasis to the outline ; but the turning wants carefully doing, and the gold thread must not be too thick. If you use a large needle (to clear the way for the thread), the turning of the gold may take place on the back instead of on the face of the material, but only in the case of very fine thread.

Gold threads often want stroking into position. This may be done with what is called a "pierce"; but a good stiletto, or even a very large needle, will answer the purpose. Sharply pointed scissors are indispensable.

In solid couching the stitches run almost inevitably into pattern; and it is customary, therefore, to start with the assumption that they will do so, and deliberately to make them into pattern—to work them, that is to say, in vertical, diagonal, or cross lines as at A, in zigzags as at B, or in some more complicated diaper pattern as at C. The stitching is there purposely in pronounced colour, that the pattern may be quite clearly seen; at D it has more its proper value, that the effect of it may be better appreciated. The pattern may, of course, be helped by the colour of the stitching. In making the necessary stitches into appropriate pattern there is scope for art.

In fact the ornamentist, being an ornamentist, naturally takes advantage of the necessity of stitching, to pattern his metallic surfaces with diaper,






56. COUCHED GOLD, SAMPLER.

using often, as in the scroll in Illustration 57, a diversity of pattern, which gives at once varied texture and fanciful interest to the surface. There is quite an epitome of little diapers in that fragment of needlework; and one can hardly doubt that the embroiderer found it great fun to contrive them. The flat strips of metal emphasising the backs of the curves are sometimes twisted as they are sewn.

Relief is given to the other diapers on the sampler, F, G, H, J, by underlying cords. They have been purposely left bare in parts to show the structure. These underlying cords must be firmly sewn on to the linen ground; and if the stitching follows the direction of the twist in them, the round surface is not so likely to be roughened by it. By rights, the cords should be laid farther apart than in the sampler, where the attempt to force the effect (for the purpose of demonstration) has not proved very successful. An infinity of basket patterns, as these may be called (basket *stitches* they are not), may be devised by varying the intervals at which the gold threads are sewn down, and the number of cords they cross at a time.

The central panel of the sampler (E) shows a combination of flat and raised gold. The outline of the heart is corded; the centre of it is raised by stitching, first with crewel wool and then with gold-coloured floss across that (it is difficult to prevent *white* stuffing from showing through



57. COUCHED SILVER.



gold). This gives only a hint of what may be done in the way of raised ornament upon a flat gold ground, and was done in mediæval work. A single quite thick cord may be sewn down to make a pattern in relief—leafage, scrollwork, or what not—which when the surface is all worked over with gold, has very much the effect of gilt gesso. If, for any reason, it is necessary to do heavy work of this kind on silk or satin, that must first be backed with strong linen.

In mediæval and church work generally the double threads are usually laid close together, forming, as in the diapers on sampler, a solid surface of gold; and that was largely done in Oriental embroidery too—in Chinese, for example, where, however, the threads, instead of being couched in straight lines, follow the outlines of the design, and are worked ring within ring until the space is filled, as in the dragon's face, A, Illustration 58. There is here, as in the working of the dragon's body, a certain economy of gold; a small amount of the ground is allowed to show between the lines of double gold thread—not enough to tell as ground, but enough to give a tint of the ground colour to the metal. Further, in this more open work the direction of the lines of couching goes for more than in solid embroidery. The pattern made by the gold thread is here not only ornamental but suggestive of the scaly body of the creature. It will be seen, too, how, in the working





58. COUCHED GOLD NOT QUITE SOLID.

of the legs, the relatively compact gold threads are kept well within the outline, by which means anything like harshness of silhouette is avoided.

That this less solid manner was not confined to the far East is shown by the Venetian valance, B, on the lower part of page 137, which has very much the appearance of gold lace.

A good example of outline (single thread) in gold is given in Illustration 59, part of an Italian housing, which reminds one both in effect and in design of damascening, to which it is in some respects equivalent; only, instead of gold and silver wire beaten into black iron or steel we have gold and silver thread sewn on to dark velvet. The design recalls also the French bookbindings of the period of Henri II., in which the tooled ornament was precisely of this character. The resemblance is none the less that an occasional detail is worked more solidly; but in the main this is outline work, and a beautiful example of it. The art in work of that kind is, of course, largely in the design. Gold thread work in spiral forms has very much the effect of filigree in gold wire.

The next step is where the cords of gold enclose little touches of embroidery in coloured floss, as in Illustration 99. These have the value of so many jewels or bits of bright enamel. In fact, just as outline work in simple gold thread resembles damascening or filigree, so this outlining of little spaces of coloured silk suggests enamel.



59. COUCHED OUTLINE WORK.

The cord of the embroiderer answers to the cloisons of the enameller, the surfaces of shining floss to the films of vitreous enamel.

Appliqué embroidery is constantly edged with gold or silver thread. An effective, if rather rude, example of this, the threads always double, is given in Illustration 60.

In couching more than one thread at a time there is a difficulty in turning the angles. The threads give, of necessity, only gently rounded forms. To get anything like a sharp point, you must stop short with the inner thread before reaching the extreme turning point, and take it up again on your way back. What applies to two threads, applies of course still more forcibly to three.

The colour with which gold thread is sewn is a question of considerable importance. If the stitches are close enough together to make sound work, they give a flush of colour to the gold. Advantage is commonly taken of this both in mediæval and Oriental work to warm the tint by sewing it down with red. The Chinese will even work with a deeper and a paler red to get two coppery shades. White stitching pales the gold, yellow modifies it least, green cools it, and blue makes it greener. The closer the stitches the deeper the tint of course.

You can get thus various shades of gold out of the same thread, and even gradation from one to another, as may be seen in a great deal of





60. APPLIQUÉ—SATIN ON VELVET.

Spanish work of the sixteenth century, in which the gold ornament is often quite delicately shaded from yellowish gold to ruddy copper on the one hand, and to bronzy green on the other. Similar use may be made of vari-coloured silks in couching white or other cord; but gold reflects the colour as silk does not, and gives proportionately more subtle effects.

The Flemings and Italians of the early Renaissance went further. They had a way of laying threads of gold and sewing them so closely over with coloured silk that in many parts it quite hid the gold. Only in proportion as they wanted to lighten the colour of the draperies in their pictorial embroideries did they space the stitches farther and farther apart, and let the gold gleam through. Except in the high lights it did not pronounce itself positively. The effect is not unlike what is seen in paintings of the primitive school, where the high lights of the red and blue draperies are hatched with gold. The practice of the embroiderer may be reminiscent of that, or that may be the origin of the primitive painters' convention. It is much as if the embroiderer wanted to represent a precious tissue, a stuff shot with gold.

Illustration 80 gives part of a figure worked in this way, relieved against a more golden architectural background worked, as you can see, over the very same double threads of gold which run

across the figures. In the architecture, however, they are couched in stitches which are never so near as to take away from the effect of the gold. The different degrees to which the gold may be obscured or clouded by oversewing are here shown in most instructive contrast. The cords, as usual, are laid in horizontal courses. That was the convenient way of working. It resulted in a corded look, which has very much the appearance of tapestry; and there is no doubt that resemblance to tapestry was in the end consciously sought. That the method here employed was laborious needs so saying; but it gave most beautiful, if at times pictorial, results.

## APPLIQUÉ.

Embroidery, it has been shown, is much of it on the surface of the stuff, not just needle stitches, but the stitching-on of something—cord, gold thread, or whatever it may be. And instances have been given where the design of such work was not merely in outline, but where certain details (Illustration 59) were filled in with stitching. Yet another practice, and one more strictly in keeping with the onlaying of cord, was to onlay the solid too, applying, that is to say, the surface colour also in the form of pieces of silk or other material cut to shape.

Patterns of this kind may be conceived as line work developing into more or less leafy terminations, the APPLIQUÉ only an adjunct to couching (Illustration 63); or they may be thought of as massive work eked out with line—the appliqué, that is to say, the main thing, the couching only supplementary (Illustration 100). An intermediate kind is where outline and mass—couching and appliqué—play parts of something like equal importance in the scheme of design (Illustration 60).



Couched cord or filoselle is used in covering the raw edge of the onlay, not merely masking the joints but making them slightly.

Appliqué must be carefully and exactly done, and is best worked in a frame. It is almost as much a man's work as a woman's. Embroidery proper is properly woman's work; but here, as in the case of tailoring, the man comes in. The getting ready for appliqué is not the kind of thing a woman can do best. In the East, by the way, embroidery is looked upon as man's work, and so it is in Brittany.

The finishing it may sometimes be done in the hand; and very bold, coarse work may possibly be worked throughout in the hand, and outlined with buttonhole-stitch (chain-stitch is not so appropriate); but when a couched outline is employed it must be done in a frame, and, indeed, work with any pretensions to finish is invariably executed from first to last in the frame.

To work appliqué you want, in fact, two frames—one on which to mount the material to be embroidered, and another on which to mount the material to be applied. The backing in each case should be of smooth holland. This is stretched on to the frame, and then pasted with stiff starch or what not; the silk or velvet is laid on to it, stroked with a soft rag until it adheres, and left to dry gently. When dry, the outlines

of the complete design are traced upon the one, and those of the details to be applied upon the other. (You may paste, of course, silks of two or three colours upon one backing for this.) The stuff to be applied is then loosened from its frame, the details are cleanly cut out with scissors, or, better still, a knife (in either case sharp), and transferred to their place in the design on the other frame. There they are kept in position by short steel pins planted upright into the stuff, and when you are sure they fit, tacked firmly down, with care that the stitches are such as will be quite covered by the final couching, chain stitch, or whatever is to be your outline.

In the case of silk or other delicate material, peculiar care must be taken that the paste is not moist enough to penetrate the stuff; but an experienced worker has no fear of that.

A firm outline is a condition of appliqué, and couched cord fulfils it most perfectly. Much depends upon a tasteful and tactful choice of colour for it. You fatten your pattern by outlining it with a colour which goes with it (Illustration 62, B). You thin it by one which merges into the ground. Very subtle use may be made of a double outline or of a corded line upon couched floss. There is a double outline to the ornament in Illustration 100: the inner one next to the yellow satin appliqué is of gold, the outer one next the crimson velvet ground is of white

and the harris blew up in the hall at noon two red roses across the moon spots  
 under the may she stooped to the crown all was odd there was nothing of brown



61. APPLIQUÉ PANEL BY MISS KEIGHLEY.

sewn with pale blue. This gives emphasis to the bold forms of the leafage. The mid-rib there is of silver couching; the minor veinings are stitched in silk, and are rather insignificant.

The less there is of extra stitching on appliqué the better as a rule. It disturbs the breadth, which is so valuable a characteristic of onlay. In no case is the mixing of opposite methods greatly to be desired; and if appliqué is to be supplemented, it had best be with couching, which is not so much stitching as stitched down, itself another form of applied work.

Appliqué of itself is not, of course, adapted to pictorial work, but that in association with judicious stitching and couching it may be used to admirable decorative purpose in figure design is shown by Miss Mabel Keighley's panel, Illustration 61. What an artist may do depends upon the artist. Miss Keighley's panel indicates the use that may be made of texture in the stuff onlaid.

Appliqué is especially appropriate to bold church work, fulfilling perfectly that condition of legibility so desirable in work necessarily seen oftenest from afar. Broadly designed, it may be as fine in its way as a mediæval stained glass window, and it gives to silk and velvet their true worth. The pattern may be readable as far off as you can distinguish colour.

Appliqué work is thought by some to be an inferior kind of embroidery. That is not so. It





62. A. COUNTERCHANGE.



B. APPLIQUÉ.

is not a lower but another kind of needlework, in which more is made of stuffs than of the stitches. In it the craft of the needleworker is not carried to its limit; but, on the other hand, it makes great demands upon design. You cannot begin by just throwing about sprays of natural flowers. It calls peremptorily for treatment—by which test the decorative artist stands or falls. Effective it must be; coarse it may be; vulgar it should not be; trivial it can hardly be. Mere prettiness is outside its scope. It lends itself to dignity of design and nobility of treatment. Of course, it is not popular.

A usual form of appliqué is in satin upon velvet. Velvet on satin (B, Illustration 62) is comparatively rare; but it may be very beautiful, though there is a danger that it may look like weaving.

Silk upon silk is shown in Illustration 63, designed to be seen from a nearer point of view, and less pronounced in pattern accordingly. The strap work, applied in ribbon, is broken by cross stitches in couples, which take away from the severity of the lines. The grape bunches are onlaid, each in one piece of silk, the forms of the separate grapes expressed by couching. The French knots in the centre of the grapes add greatly to the richness of the surface. The leaves are in one piece.

The application of leather to velvet as in Illustration 102, allows, if it does not actually involve,



63. APPLIQUÉ—SILK ON SILK DAMASK.

some modification in the way of execution, and of design adapted to it. Leather does not fray, and needs, therefore, no sewing over at the edge, but only sewing down, which may be done, as in this case, well within the edge of the material, giving the effect of a double outline. The Chinese do small work in linen, making similar use of the stitching within the outline, but turning the cut edge of the stuff under; it would not do to leave it raw. On a bolder scale, but in precisely the same manner, is embroidered the wonderful tent of François I<sup>er</sup>, taken at the battle of Pavia, and now in the Armoury at Madrid—obviously Arab work. Something of the kind was done also in Morocco; and this points to leather work as the possible origin of the method.

Another ingenious Chinese notion is to sew down little five-petalled flowers (turned under at the edges) with long stamen stitches radiating from a central eye of knots.



## INLAY, MOSAIC, CUT-WORK.

A step beyond the process of onlaying is INLAY, where a material is laid not on to the other but into it, both being perhaps backed by a common material. The process is, in fact, precisely analogous to that inlay of brass and tortoiseshell which goes by the name of its inventor, Boule. The work is difficult, but thorough. It does not recommend itself to those who want to get effect cheaply; and it is suited only to close-textured stuffs, such as cloth, which do not easily fray.

The materials are not pasted on to linen, as in the case of appliqué. The cloth to be inlaid is placed upon the other, and both are cut through with one action of the knife, so that the parts cannot but fit. The coherent piece of material (the ground, say, of the pattern) is then laid upon a piece of strong linen already in a frame; the vacant spaces in it are filled up by pieces of the other stuff, and all is tacked down in place. That done, the work is taken out of the frame, and the edges sewn together. The backing can then, if necessary, be removed; and in Oriental work it generally was.

TO WORK  
INLAY.

Inlay lends itself most invitingly to COUNTER-CHANGE in design. In the stole (A) on page 149 the light and dark portions of the pattern are identical. You cannot say that either is the ground ; each forms a ground to the other. And from the mere fact of the counterchanging you gather that it is inlaid and not onlaid.

TO WORK  
COUNTER-  
CHANGE.

Prior to inlaying in materials which are at all likely to fray, you first back them with paper, thin but tough, firmly pasted ; then, having tacked the two together, and pinned them with drawing-pins on to a board, you slip between it and the stuff a sheet of glass, and with a very sharp knife (kept sharp by an oilstone at hand) cut out the pattern. What was cut out of one material has only to be fitted into the other and sewn together as before, and you have two pieces of inlaid work—what is the ground in one forming the pattern in the other, and *vice versa*. By this ingenious means there is absolutely no waste of stuff. You get, moreover, almost invariably a broad and dignified effect : the process does not lend itself to triviality. It was used by the Italians, and more especially by the Spaniards of the Renaissance, who borrowed the idea, of course, from the Arabs.

In India they still inlay in cloth most marvelously, not only counterchanging the pattern, but inlaying the inlays with smaller patternwork, thus combining great simplicity of effect with wonderful minuteness of detail. The inlaid work of Retsht



64. INLAY IN COLOURED CLOTHS.

in Persia, Illustration 64, is of a more elaborate character. In both countries they mask the joins with chain-stitch, the colour of it artfully chosen with regard to the two colours of the cloth it divides or joins. Further, they often patch together pieces of this kind of inlay.

PATCH-  
WORK.

Inlay itself is a sort of PATCHWORK. You cut pieces out of your cloth, and patch it with pieces of another colour, covering the joins perhaps as in the Retsht work, with chain-stitch, which, by its likeness to wire filigree, suggests cloisonné enamel.

Where there is no one ground stuff to be patched, but a number of vari-coloured pieces of stuff are sewn together, they form a veritable MOSAIC of coloured stuffs, reminding one of what the mediæval glaziers did in coloured glass. Admirable heraldic work was done in Germany by this method; and it is still universally employed for flag making. The stuffs used should be as nearly as possible of one substance. In patchwork of loosely-textured material each separate piece of stuff may be cut large, turned in at the edge, and oversewn on the wrong side.

CUT-  
WORK.

The relation of CUT-WORK to inlay is clear—in fact, the one is the first step towards the other. You have only to stop short of the actual inlaying, and you have cut-work. Fill up the parts cut out in Illustration 65 with coloured stuff, and it would be inlay. The needlewoman has preferred to sew





65. CUT-WORK IN LINEN.

over the raw edges of the stuff, and give us a perfect piece of FRETWORK in linen. It is part of the game in cut-work to make the fret coherent, whole in itself. The design should tell its own tale. "Ties" of buttonhole-stitch, or what not, are not necessary, provided the designer knows how to plan a fret pattern. Their introduction brings the work nearer to lace than embroidery. The sewing-over may be in chain-stitch, satin-stitch (as in Illustration 65), or in buttonhole-stitch—which last is strongest.

As, in the case of appliqué, inlay, and mosaic, an embroidered outline is usually necessary to cover the join, so in the case of cut-work sewing-over is necessary to keep the edges from fraying. It may sometimes be advisable to supplement this outlining by further stitching to express veining, or give other minute details—just as the glassworker, when he could not get detail small enough by means of glazing, had recourse to painting to help him out. But there is danger in calling in auxiliary methods. It is best to design with a view to the method of work to be employed, and to keep within its limits. To worry the surface of applied, inlaid, or cut stuff with finnikin stitchery, is practically to confess either the inadequacy of the design or the fidgetiness of the worker. It should need, as a rule, no such enrichment.

## EMBROIDERY IN RELIEF.

Embroidery being work *upon* a stuff, it is inevitably raised, however imperceptibly, above the surface of it. But there is a charm in the unevenness of surface and texture thus produced; and the aim has consequently often been to make the difference of level between ground-stuff and embroidery more appreciable by UNDERLAY or padding of some kind. The abuse of this kind of thing need not blind us to the advantages it offers.

There are various ways of raising embroidery, the principal of which are illustrated on the sampler overleaf.

In sprig A the underlay is of closely-woven cloth, TO WORK  
A. darker in colour than would be advisable except for the purpose of showing what it is: it is as well in the ordinary way to choose a cloth more or less of the colour the embroidery is to be. The cloth is cut with sharp scissors carefully to shape, but a little within the outline, and pasted on to the linen. When perfectly dry, it is worked over with thick corded silk couched in the ordinary way.

The raised line at B reveals the way the stem in TO WORK  
B. Illustration 86 was worked. Two cords of smooth

string (macramé, for example) are twisted and tacked in place. Over this floss is worked in close satin-stitch.

TO WORK  
C.

In sprig C the underlay is of parchment, lightly stitched in place. The use of a double underlay in parts gives additional relief. The embroidery upon this (in slightly twisted silk) is in satin-stitch.


TO WORK  
D.

The leaf shapes at D are padded with cotton wool, cut out as nearly as possible to the shape required, and tacked down with fine cotton. They are then worked over with floss in satin-stitch. The stalks are not padded with cotton wool, but first worked with crewel wool, which, being soft and elastic, forms an excellent ground for working over in floss silk.

TO WORK  
E.

In working a stalk like that at E, you first lay down a double layer of soft, thick cotton, and then work over it with flatter cotton (made expressly for padding) in slanting satin-stitch. Three threads of smooth round silk are then attached to one side of the padding and carried diagonally across to the other side, where they are sewn down with strong thread of the same colour close to the underlay, so that the stitches may not show. They are then brought back to the side from which they started, sewn down, and returned again, and so backwards and forwards to the end. The crossing threads make a sort of pattern, and it is a point of good workmanship that





66. RAISED WORK SAMPLER.

they should cross regularly. Such pattern is more obvious when threads of three different shades of colour are employed. Threads of twisted silk may, of course, be equally well used this way without padding underneath.


TO WORK  
F. In sprig F the underlay is of cardboard, pasted on to the linen. It is worked over with purse silk, to and fro across the forms, and sewn down at the margin with finer silk. This is a method of work often employed when gold thread is used.

TO WORK  
G. In sprig G the underlay or stuffing is of string sewn down with stitches always in the direction of the twist. It is worked over with floss in satin-stitch.

TO WORK  
H. In sprig H the underwork consists of stitching in soft cotton, over which thick silk is embroidered in bullion-stitch. The rule is to work the first stitching in such a direction that the surface work crosses it at right angles. The small leaf is worked over with fine purse silk in satin-stitch, which is used also for the stalk.

In the smaller sampler of laid-work, Illustration 50, the broad stem is twice underlaid with crewel, excellent for this soft sort of padding, on account of its elasticity. The leaves have there only one layer of understitching.

Raised work in white upon white is often used for purposes which make it inevitable that sooner or later the work will be washed. That is a consideration which the embroidress must not leave



67. RAISED WORK SHOWING UNDERLAY.

out of account. In any case, work over stitchery is more durable than over loose padding such as cotton wool.

The fifteenth-century work reproduced in Illustration 67 is in flax thread on linen, and the underlay (laid bare in the topmost flower) is of stiff linen, sewn down, not at the margins as in the case of the parchment on the sampler (Illustration 66), but by a row of stitching up the centre of each petal. The veins of the leaves in Illustration 88 are padded with embroidery cotton and worked over with filo-floss. The leaves themselves are not padded, though the sewing down of the veins upon them, as well as the fact that they are applied on to the velvet ground, gives some appearance of relief.



## RAISED GOLD.

Our sampler of raised work is done in silk. Underlaying is more often used to raise work in gold, to which in most respects it is best suited. The methods shown in the sampler would answer almost equally well for gold, except that working in gold one would not at H (66) use bullion-stitch, but bullion, first covering the underlay of stitching with smoothly-laid yellow floss.

BULLION consists of closely coiled wire. It is made by winding fine wire tightly and closely round a core of stouter wire. When this central core of wire is withdrawn, you have a long hollow tube of spirally twisted wire. This the embroidress cuts into short lengths as required, and sews on to the silk—as she would a long bead or bugle. Its use is illustrated at A in Illustration 51, where the stems of triple gold cord are clamped down at intervals with bullion, and the leaves, again, are filled in with the same.

It was the mediæval fashion to encrust the robes of kings and pontiffs with pearls and precious stones mounted in gold: the early Byzantine form of crown was practically a velvet

cap, on to which were sewn plaques of gorgeous enamel and mounted stones. When to such work embroidery was added, it was not unnatural that it should vie with the gold setting. As a matter of fact, its design was often only a translation into needlework of the forms proper to goldsmith's work.

Yet more openly in rivalry with the work of the goldsmith was some of the embroidery of the Renaissance, in which the idea—a most mistaken one, of course—seems to have been to imitate beaten metal. This led inevitably to excessively high relief in gold embroidery. You may see in seventeenth-century church work the height to which relief can be carried, and the depth to which ecclesiastical taste can sink.

The Spaniards were, perhaps, the greatest sinners in this respect, seeking, as they did, richness at all cost; but it must be confessed that, in the sixteenth century at least, they produced most gorgeous results: there is in the treasury of the cathedral at Toledo an altar frontal in gold, silver, and coral, and a yet more beautiful mantle of the Virgin in silver and pearls upon a gold ground, which make one loth to dogmatise about excessive richness.

The preciousness of gold and silver, points, in the nature of things, to their use for church vestments and the like; and high relief gives, no doubt, value to the metal; but the consideration of its



68. RAISED GOLD.

intrinsic value leads quickly to display. The artistic value of gold is not so much that it looks gorgeous as that it glorifies the colour caught, so to speak, in its meshes.

Admitting that there is reason for relief in gold embroidery—it catches the light as flat gold does not—one feels that the very slightest modelling is usually enough. Reference was made (page 136) to the effect of gilt gesso obtained in raised gold thread: that really is about the degree of relief it is safe to adopt in gold embroidery, the relief that is readily got by laying on gesso with a brush, not carving or modelling it; and the characteristically blunt forms got by that means repeat themselves when you work with the needle.

There is ample relief in the gold embroidery on Illustrations 68 and 86. The first of these shows both flat and raised work: the latter illustrates not only various degrees of relief, but several ways of underlaying. It scarcely needs pointing out that the flatter serrated leaves are worked over parchment or paper, and the puffy parts of the flowers over softer padding. Allusion has already been made (page 159) to the way the stalk is worked over twisted cords, as on the sampler, Illustration 66. The patterns in which the gold is worked do not tell quite so plainly here as on Illustration 68, where the basket pattern is more pronounced. In the stalk there flat gold wire is used, and again in the broken surface towards the top of the plate.



SPANGLES of gold may be used with admirable effect, at the risk, perhaps, of a rather tinselly look ; but that has been often most skilfully avoided both in mediæval work and in Oriental. In India great and very cunning use is made of spangles, by the Parsees in particular, who, by the way, embroider with gold wire.

Gold foil may be cut to any shape and sewn on to embroidery, but spangles take mainly one of two shapes, best distinguished as disc-like and ring-like. The discs are flat, pierced in the centre, and sewn down usually with two or three radiating stitches (A, Illustration 51, and Illustration 67). The rings may be attached by a single thread. They can easily be made to overlap like fish scales, and most elaborately embossed pictures have been worked in this way. There is a vestment in the cathedral at Granada which is a marvel to see ; but not the thing to do, surely.

Relief is easily overdone, in figure work so easily that one may say safety is to be found only in the most delicate relief. To make figures look round is to make them look stuffed. That stuffy images are to be found in mediæval church work is only too true. In Gothic art one finds this quaint, perhaps, but it is perilously near the laughable. The point of the ridiculous is plainly overpassed in English work of the seventeenth century, which degenerates at last into mere doll work—the dolls duly stuffed and dressed in most

childish fashion, their drapery, in actual folds, projecting. Some really admirable needlework was wasted upon this kind of thing, which has absolutely no value, except as an object-lesson in the frivolity of the Stuarts and their on-hangers.


## QUILTING.

A most legitimate use of padding is in the form of QUILTING, where it serves a useful as well as an ornamental purpose. To quilt is to stitch one cloth upon another with something soft between (or without anything between). Our word "counterpane" is derived from "contre-point," a corruption of the French word for back-stitch, or "quilting" stitch, as it was called.

If you merely stitch two thicknesses of stuff together in a pattern, such as that on Illustration 69, the stuff between the stitches has a tendency to rise: the two layers of stuff do not lie close except where they are held together by the stitching, and a very pleasantly uneven surface results. This effect is enhanced if between the two stuffs there is a layer of something soft. If, now, you sew down the groundwork of your design with small diapering, you get a pattern in relief—more or less, according to the substance of your padding.

Another way is to pad the pattern only, as in Illustration 70, where the padding is of soft cord.

A cunning way of padding is first to stitch the outline of the design, and then from the back to



69. QUILTING, DONE IN CHAIN-STITCH FROM THE BACK.



insert the stuffing. You first pierce the stuff with a stiletto, and, having pushed in the cord, cotton, or what not, efface as far as possible the piercing : the stuffing has then not much temptation to escape from its confinement.

The Persians do most elaborate quilting on fine white linen, which they sew with yellow silk ; but the pattern is stuffed with cords of blue cotton, the colour of which just grins through the white sufficiently to cool it, and to distinguish it from the ground made creamy white by the yellow stitching.

Quilting is most often done in white upon colour, or in one colour upon white. Yellow silk on white linen (as in the quilting opposite, Illustration 69) was a favourite combination, and is always a delicate one. But there is no reason why a variety of colours should not be used in a counterpane. When you stitch down the ground with coloured silk you give it, of course, a tint, besides flattening it.



70. RAISED QUILTING.

## STITCH GROUPS.

There are all sorts of ways in which stitches might be grouped :—according to the order of time in which historically they came into use ; according as they are worked through and through the stuff or lie mostly on its surface ; according as they are conveniently worked in the hand or necessitate the use of a frame ; and in other ways too many to mention. It is not difficult, for example, to imagine a classification according to which the satin-stitch in Illustration 71 would figure as a canvas-stitch.

In the Samplers they are grouped according to their construction, that seeming to us the most practical for purposes of description. They might for other purposes more conveniently be classed some other way. At all events, it is helpful to group them. Designer and worker alike will go straighter to the point if once they get clearly into their minds the stitches and their use, and the range of each—what it can do, what it can best do, what it can ill do, what it cannot do at all.

Any one, having mastered the stitches and grasped their scope, can group them for herself, say, into

stitches suited (1) to line work, (2) to all-over work, (3) to shading, and so on.

These she might again subdivide. Of line stitches, for example, some are best suited for straight lines, others for curved; some for broad lines, others for narrow; some for even lines, others for unequal; some for outlining, others for veining.

And, further, of all-over stitches some give a plain surface, others a patterned one; some do best for flat surfaces, others for modelled; some look best in big patches, some answer only for small spaces.


With regard to shading stitches, there are various ways (see the chapter on shading) of giving gradation of colour and of indicating relief or modelling.

Some stitches, of course, are adapted to various uses, as crewel, chain, and satin stitches; and these are naturally the most in use. Workers generally end in adopting certain stitches as their own. That is all right, so long as they do not forget that there are other stitches which might on occasion serve their purpose. Anyway, they should begin by knowing what stitches there are. Until they know, and know, too, what each can do, they are hardly in a position to determine which of them will best do what they want.

Our Samplers show the use to which the stitches on them may be put.

By way of *résumé*, it may be added that for line





71. SATIN-STITCH IN THE MAKING.

work, more or less fine, crewel, chain, back and rope stitches, and couched cord are most suitable ; crewel for long lines especially, and rope stitch for both curved and straight lines ; for a boundary line, buttonhole is most emphatic ; for broader lines, herring-bone, feather, and Oriental stitches answer better ; ladder-stitch has the advantage of a firm edge on both sides of it. Satin and chain stitches, couching and laying, and basket work make good \*bands, but are not peculiarly adapted to that purpose.

For covering broad surfaces, crewel, chain, and satin stitches (including, of course, what are called long-and-short and plumage stitches) serve admirably, as does also darning and laid-work ; and with gold thread, couching. French knots do best for small surfaces only. The stitches most useful for purposes of shading are mentioned later on.

No sort of classification is possible until the number of stitches has been reduced to the necessary few, and all fancy stitches struck out of the list. Enquiry should also be made into the title of each stitch to the name by which it is known ; and the names themselves should be brought down to a minimum.

Reduce them to the fewest any needlewoman will allow, and they are still, if not too many, more than are logically required. Some of them, too, describe not stitches, but ways of using a stitch. The term long-and-short, it has already been

explained (page 100), has less to do with a particular stitch than its proportion, and the term *plumage-stitch* refers more to the direction of the stitch than to the stitch itself. And so with other stitches. It is its oblique direction only which distinguishes *stem-stitch* from other short stitches of the kind. *Running*, again, amounts to no more than proportioning stitches to the mesh of the stuff, and taking several of them at one passing of the needle ; and *darning* is but rows of running side by side. The term *split-stitch* describes no new stitch, but a particular treatment to which a *crewel* or a *satin stitch* is submitted.

The foregoing summaries of stitches are only by way of suggestion, something to set the embroidress thinking for herself. She must choose her own method ; but it would help her, I think, to schedule the stitches for herself according to her own ways and wants. The most suitable stitch may not suit every one. Individual preference and individual aptitude count for something. It is not a question of what is demonstrably best, but of what best suits you.

## ONE STITCH, OR MANY?

The first thing to be settled with regard to the choice of stitch is whether to employ one stitch throughout, or a variety of stitches. Much will depend upon the effect desired. Good work has been done in either way ; but one may safely say, in the first place, that it is as well not to introduce variety of stitch without good cause—there is safety in simplicity—and in the second, that stitches should be chosen to go together, in order that the work may look all of a piece. When the various stitches are well chosen, it is difficult at a glance to distinguish one from another.

A great variety of stitches in one piece of work is worrying, if not bewildering. It is as well not to use too many, to keep in the main to one or two, but not to be afraid of using a third, or a fourth to do what the stitch or stitches mainly relied upon cannot do.

It tends also towards simplicity of effect if you use your stitches with some system, not haphazard, and in subordination one to the other ; there must be no quarrelling among them for superiority. You should determine, that is to say, at the outset,






72. STITCHES IN COMBINATION.

which stitch shall be employed for filling, which for outline ; or which for stalks, which for leaves, and which for flowers. Or, supposing you adopt one general stitch throughout, and introduce others, you should know why, and make up your mind to employ your second perhaps for emphasis of form, your third for contrast of texture—each for some quite definite purpose.

It is not possible here to point out in detail the system on which the various examples illustrated have been worked ; the reader must worry that out for herself. But one may just point out in passing how well the various stitches go together in some few instances.

Nothing could be more harmonious, for example, than the combination of knot, chain, and button-hole stitches in Illustration 24 ; or of ladder, Oriental, herring-bone, and other stitches in Illustration 72. Again, in Illustration 85 the contrast between satin-stitch in the bird and couched cord for the clouding is most judicious, as is the knotting of the bird's crest. Laid floss contrasts, again, admirably with couched gold in Illustrations 47, 48, 49, and satin-stitch with couching in Illustration 99, where the gold, reserved mainly for outline, serves on occasion to emphasise a detail.

Couched gold and surface satin-stitch are used together again in Illustration 58, each for its specific purpose. The harmony between appliqué



73. FINE NEEDLEWORK UPON LINEN.

work and couching or chain-stitch outline has been alluded to already.

A danger to be kept in view when working in one stitch only is, lest it should look like a woven textile, as it might if very evenly worked. Some kinds of embroidery seem hardly worth doing nowadays, because they suggest the loom. This may be a reason for some complexity of stitch, in which lurks that other danger of losing simplicity and breadth. The lace-like appearance of the needlework upon fine linen in Illustration 73, results chiefly from the extraordinary delicacy with which it is done, but it owes something also to the variety of stitch and of stitch-pattern employed in it.

In complaining of needlework that it looks like weaving, we are apt to overlook the fact that embroidery is after all the needlewoman's way of doing for herself what she cannot get done, or cannot afford to have done for her. The peasant woman may be doing quite right in embroidering what could just as well be woven.



## OUTLINE.

The use of outline in embroidery hardly needs pointing out. It is often the obvious way of defining a pattern, as, for example, where there is only a faint difference in depth of tint between the pattern and its background ; in appliqué work it is necessary to mask the joins ; and it is by itself a delightful means of diapering a surface with pattern of a kind which is never obtrusive.

Allusion to the stitches suitable to outline has been made already (see Stitch-groups), as well as to the colour of outlining (*à propos* of appliqué). It is difficult to overrate the importance of this question of colour in the case of outline ; but there are no rules to be laid down, except that a coloured outline is nearly always preferable to a black one. The Germans of the sixteenth century were given to indulging in black outlines, and you may see in their work how it hardened the effect, whereas a coloured outline may define without harshness. The Spaniards, on the other hand, realised the value of colour, and would, for example, outline gold and silver upon a dark green ground in red, with admirable effect. . A double outline, for which

there is often opportunity in bold work, may be turned to good account. Among the successful combinations which come to mind is an appliqué pattern in yellow and white upon dark green, outlined first with gold cord, and then, next the green, with a paler and brighter green. Another is a pattern chiefly in yellow upon purple, outlined first with yellow couched with gold, and next the ground with silver. In the case of couched cord or gold, the colour of the stitching counts also.

Stitches from the edge of a leaf, inwards, alternately long and short, though they form an edge to the leaf, are not properly outlining. This is rather a stopping short of solid work than outlining, though it often goes by that name.

The first condition of a good outline stitch is that it should be, as it were, supple, so as to follow the flow of the form. At the same time it should be firm. Fancy stitches look fussy; and a spiky outline is worse than none at all.

There is absolutely no substantial ground for the theory that outlines should be worked in a stitch not used elsewhere in the work. On the contrary, it is a good rule not to introduce extra stitches into the work unless they give something which the stitches already employed will not give. The simplest way is always safest.

An outline affords a ready means of clearing up edges; but it should not be looked upon merely

as a device for the disguise of slovenliness. Unless the colour scheme should necessitate an outline, an embroidress, sure of her skill, will often prefer not to outline her work, and to get even the drawing lines within the pattern, by voiding. VOIDING. She will leave, that is to say, a line of ground-stuff clear between the petals of her flowers, or what not; which line, by the way, should be narrower than it is meant to appear, as it looks always broader than it is. It is more difficult, it must be owned, thus to work along two sides of a line of ground-stuff than to work a single line of stitching; but it is within the compass of any skilled worker; and skilled workers have delighted in it even when their work was on a small scale, which determined that the lines of voiding should be as fine as possible (Illustrations 39 and 40).

In work on a bold scale there is no difficulty about it; and it would be remarkable that it is so seldom used, were it not that the uncertain worker likes to have a chance of clearing up ragged edges, and that voiding implies a broader and more dignified treatment of design than it is the fashion to affect.

## SHADING.

One arrives inevitably at gradation of colour in embroidery: the question is how best to get it. But, before mentioning the ways in which it may be got, it seems necessary to protest that shading is not a matter of course. Perfectly beautiful work may be done, and ought more often to be done, in merely flat needlework; the gloss of the silk and its varying colour as it catches the light according to the direction of the stitching, are quite enough to prevent a monotonously flat effect.

Still, embroidery affords such scope for gradation of colour, not, practically, to be got by any process of weaving, that a colourist may well revel in the delights of colour which silks of various dyes allow. And so long as colour is the end in view there is not much danger that a colourist will go wrong.

The real use of shading in embroidery is rather to get gradation of colour than relief of form. As to the stitch to be employed, that is partly a personal matter, partly a question of what is to be done. The stitch must be adapted to the kind





74. PART OF A DESIGN BY WALTER CRANE.

of shading, or the shading must be designed to suit the stitch. It makes all the difference in the world, whether your shading is done deliberately in well-marked shades of colour, or whether one shade merges into another. In the best work it is always done with decision. There is nothing vague or casual, for example, about the shading of Mr Crane's animals in Illustration 74. Everywhere the shading is *drawn*, either in lines or as a sharply defined mass. Given a drawing in which the shadows are properly planned and crisply drawn like that, and you may use what stitch you please.

The more natural way of shading is to let the stitches follow the lines of the drawing, and so make use of them to express form, as with the strokes of the pen or pencil upon paper. Thus in mediæval figurework prior to the fifteenth century the faces were usually done in split-stitch, worked concentrically from the middle of the cheek outward, and so suggesting the roundness of the face (Illustration 87). But just as there is a system of shading according to which the draughtsman makes all his strokes in one direction (slanting usually), so the embroidress may, if she prefer, take her stitches all one way; and in the fifteenth and sixteenth centuries the fashion was to work flesh in short satin-stitches always in the vertical direction (Illustration 79). The term "long-and-short-stitch" is frequently used by way of describing



75. SHADING IN CHAIN-STITCH.

the stitch. It does not, as I have said, help us much. The stitches are in the first place only satin-stitches worked not in even rows, as in Illustration 40, but so that there is no line of demarcation between one row and another. And this, in the case of gradated colour, makes the shading softer. The words long-and-short apply strictly only to the outer row of stitches. You begin, that is to say, with alternately long and short stitches. If you work after that with stitches of equal length, they necessarily alternate or dovetail. If the form to be worked necessitates radiation in the stitching, there results a texture something like the feathering of a bird's breast (Illustration 85), whence the name plumage-stitch, another term describing not so much a stitch as the use of a stitch.

No matter what the stitch, one must be able to draw in order to express form: it is rather more difficult to draw with a needle than with a pen, that is all. True, the designer may do that for you, and make such a workmanlike drawing that there is no mistaking it; but it takes a skilled draughtsman to do it.

In flattish decorative work, where the drawing is in firm lines, as in Illustration 87, the task of the embroidress is relatively easy—there is not much shading, for example, in the drapery of King Abias, and the vine leaves are merely worked with yellower green towards the edges. Even





76. SHADING IN SHORT STITCHES.

where there is strong shading, a draughtsman who knows his business may make shading easy by drawing his shadows with firm outlines. The taste of the artist who designed the roses in Illustration 75 is too pictorial to win the heart of any one with a leaning towards severity of design; too much relief is sought; but the way he has got it shows the master workman; he has deliberately laid in *flat* washes of colour, each with its precise outline, which the worker had only to follow faithfully with flat tambour work. A design like that, given the working drawing, asks little of the worker beyond patient care: of the designer it asks considerable knowledge.

A yet more pictorial effect is produced in much the same way, this time in satin-stitch, in Illustration 76. The artist has for the most part drawn his shadows with crisp brush strokes, which the worker had no difficulty in following; but there is some rounding of the bird's bodies which a merely mechanical worker could not have got. In fact, there are indications that this is the work of a painter embroidress more intent in rendering with the needle the plump forms of the birds than their feathering.

You can embroider, of course, without knowing much about drawing; but you cannot go far in the direction of shading (which has not been drawn for you, or has been but vaguely drawn) without the appreciation of form which comes only of knowing



77. SHADING IN LONG-AND-SHORT AND SPLIT STITCHES.

and understanding. There is evidence of such knowledge and understanding in the working of the lion in Illustration 77. That is not a triumph of even stitching ; but it is a triumph of drawing with the needle. The short satin and split stitches are not placed with the regularity so dear to the human machine, but they express the design perfectly. The embroiderer of that lion was an artist, possibly the artist who designed it. "It might be a *man's* work," was the verdict of an embroidress. At all events it is the work of some one who could draw, and only a draughtsman or draughtswoman could have worked it.

This is not said wholly in praise of shading. Embroidery ought, for the most part, to do very well without it. The point to insist upon is that, if shading is employed at all, it should mean something, and not be mere fumbling after form.

The charm of shading in embroidery is not the roundness of form which you get, but the gradation of colour which it gives. This may be very delicately and subtly got by split-stitch, which is on that account so valuable in the rendering of flesh tints. But the blending of colour into colour which is universally admired is not quite so admirable as people think. One may easily employ too many shades of colour, easily allow them to melt so imperceptibly one into the other that the result is only unmeaning softness. An artist prefers to see few shades employed, and



those chosen with judgment and placed with deliberate intention. If they mean something, there is no harm in letting it be seen where they meet: broad masses give breadth: vagueness generally means ignorance. That is perhaps why one dislikes it, and why it is so common.

## FIGURE EMBROIDERY.

To an accomplished needlewoman embroidery offers every scope for art, short of the pictorial; and the artist is not only justified in lavishing work upon it, but at times bound to do so, more especially when it comes to working with materials in themselves rich and costly. A beautiful material, if you are to better it (and if not why work upon it at all?), must be beautifully worked. Costly material is worth precious work; and there should be by rights a preciousness about the needlework employed upon it, preciousness of design and of execution. To put the value into the material is mere vulgarity.

It seems to an artist almost to go without saying, that the labour on work claiming to be art should be in excess of the value of the stuff which goes to make it. What we really prize is the hand work and the brain work of the artist; and the more precious the stuff we employ, the more strictly we are bound to make artistic use of it. That does not mean *pictorial* use. You can get, no doubt, with the needle effects more or less pictorial—most often less pictorial than the worker means to get; but,

when got, they are usually at the best rather inferior to the picture of which they are a copy.

Work done should be better always than the design for it. That was a project only, a promise: the fulfilment should be something more. A design of which the promise is not likely to be fulfilled in the working-out is, for its purpose, ill-designed. To say that you would rather have the drawing from which it was done (and that is what you usually feel about "needle pictures") is most severely to condemn either the designer or the worker, or perhaps both. Only a competent figure painter, for example, can be trusted to render flesh with the needle; her success is in proportion to her skill with the implement, but in any case less than what might be achieved in painting: then why choose the needle?

Admitting that a painter who by choice or chance takes to the needle may paint with it satisfactorily enough, that does not go to prove the needle a likely tool to paint with. It is anything but that. There was never a greater mistake than to suppose, as some do who should know better, that, to raise embroidery to the rank of art, figure work is necessary. The truth is that only by rare exception does embroidered figure work rise to the rank of art: the rule is that it is degraded—the more surely as it aims at picture. And that is why, for all that has been done in the way of wonderful picture work, say by the Italians

and the Flemings of the Early Renaissance, the pictorial is not the form of design best suited to embroidery.

Needlework, like any other decorative craft, demands treatment in the design, and the human figure submits less humbly to the necessary modification than other forms of life. Animals, for instance, lend themselves more readily to it, and so do birds; fur and feathers are obviously translatable into stitches. Leaves and flowers accommodate themselves perhaps better still; but each is best when it is only the motive, not the model, of design. If only, then, on account of the greater difficulty in treating it, the figure is not the form of design most likely to do credit to the needle, and it is absurd to argue that, figure work being the noblest form of design, therefore the noblest form of embroidery must include it.

The embroidress entirely in sympathy with her materials will not want telling that the needle lends itself better to forms less fixed in their proportions than the human figure; the decorator will feel that there is about fine ornament a nobility of its own which stands in need of no pictorial support; the unbiassed critic will admit that figure design of any but the most severely decorative kind is really outside the scope of needle and thread; and that the desire to introduce it arises, not out of craftsmanlikeness, but out of an ambition which does not pay much regard to the conditions proper to



needlework. Those conditions should be a law to the needlewoman. What though she be a painter too? She is painting now with a needle. It is futile to attempt what could be better done with a brush. She should be content to work the way of the needle. Common-sense asks that much at least of loyalty to the art she has chosen to adopt.

Wonderful and almost incredibly pictorial effects have been obtained with the needle ; but that does not mean to say it was a wise thing to attempt them. The result may be astonishing and yet not worth the pains. The pains of flesh-painting with the needle (if not the impossibility of it for all practical purposes) is confessed by the habit which arose of actually painting the flesh in water colour upon satin. Paint on satin, if you please : there are occasions when there is no time to stitch and it may be necessary, perhaps, for some ceremonial and more or less theatric purpose, to paint what had better have been worked. The more frankly such work acknowledges its temporary and makeshift character the better. Scene painting is art, until you are asked to take it for landscape painting. Anyway, the mixture of painting and embroidery is not to be endured ; and it is a poor-spirited embroidress who will thus confess her weakness and call on paint to help her out. It does not even do that, it fails absolutely to produce the desired effect. The painting quarrels

with the stitching, and there is after all no semblance of that unity which is the very essence of picture.


An instance of painted flesh occurs upon Illustration 99. Can any one, in view of the bordering to the picture, doubt that the worker had much better have kept to what she could do, and do



78. CHINESE CHAIN-STITCHING.

perfectly, ornament? An example, on the other hand, of what may be done in the way of expressing action in the fewest and simplest chain stitches (if only you know the form you want to represent and can manage your needle) is given in the wee figures in the landscape above (78).

In speaking of the necessary treatment of the human figure (as of other natural form) in needlework, it is not meant to contend that there is one



79. FIFTEENTH-CENTURY FIGURE WORK.

only way of treating it consistently, or that there are no more than two or three ways. There are various ways, some no doubt yet to be devised, but they must be the ways of the needle. The flesh, of course, is the main difficulty. A Gothic practice, and not the least happy one, was to show the flesh in the naked linen of the ground, only just working the outlines of the features in black or brown. Another way was to work the face in split stitch, as already explained, and over that the markings of the features, the fine lines in short satin-stitches, the broader in split-stitch, as shown in the figure of King Abias in Illustration 87.

The general treatment of the figure there is of course in the manner of the fourteenth century, better suited, from its severe simplicity, for rendering in needlework than later and more pictorial forms of design. That needlework can, however, in capable hands, go farther than that is shown in Illustration 79, a rather threadbare specimen of fifteenth-century work, in which the character of the man's face is admirably expressed. It is first worked in short, straight stitches, all of white, and over that the drawing lines are worked in brown. The artist gets her effect in the simplest possible way, and apparently with the greatest ease.

More like painting is the head in Illustration 80, worked in short stitches of various shades, which give something of the colour as well as the





80. SIXTEENTH-CENTURY ITALIAN FIGURE WORK,

modelling of flesh. This is a triumph in its way. It goes about as far as the needle can go, and farther than, except under rare conditions, embroidery need go. But it may be carried to that point and yet be essentially needlework.

Equally wonderful in their miniature way are the faces of the little people on Illustration 81, about the size of your finger nail. They are worked in solid satin-stitch, and the two layers of silk (back and front) give a substance fairly thick but at the same time yielding, so that when the stitches for the mouth and eyes are sewn tightly over it they sink in, and, as it were, push up the floss between and give relief. The nose is worked in extra satin-stitch over the other, and the slight depression at the end of the stitch gives lines of drawing. This trenches upon modelling, but, on such a minute scale, does not amount to very pronounced departure from the flat. The method employed does not lend itself to larger work.

The last word on the question as to what one may do with the needle is, that you may do what you *can*; but it is best to seek by means of it what it (or you with it) can best do, and always to make much of the texture of silk, and of the quality of pure and lustrous colour which it gives—in short, to work *with* your materials.



81. CHINESE FIGURES.

## THE DIRECTION OF THE STITCH.

The effect of any stitch is vastly varied, according to the use made of it. Satin-stitch, it was shown (38), worked in twisted silk, ceases to have any appearance of satin; and it makes all the difference whether the stitches are long or short, close together or wide apart. More important than all is the direction of the stitch. By that alone you can recognise the artist in needlework.

The DIRECTION of the stitch deserves consideration from two points of view—that of colour and that of form. First as to colour. It is not sufficiently realised that every alteration in the direction of the stitch means variety of tone, if not of tint. Take a feather in your hand, and turn it about, so that now one side of the quill now the other catches the light; or notice the alternate stripes of brighter and greyer green on a fresh-trimmed lawn, where the garden roller has bent the blades of grass first this way and then that. So it is with the colour of silken stitches. The pattern opposite (82) looks as if it had been embroidered in two shades of silk; in the work itself it has still more that appearance; but





82. INFLUENCE OF STITCH-DIRECTION UPON COLOUR.

it is all in one shade of brownish gold: the difference which you see is merely the effect of light upon it. The horizontal stitches, as it happens, catch the light; the vertical ones do not. Had the light come from a different point, the effect might have been reversed. If there had been diagonal stitches from right to left, they would have given a third tint; and, if there had been others from left to right, they would have given a fourth.

Suppose a pattern in which the leaves were worked horizontally, the flowers vertically, and the stalks in the direction of their growth, all in one stitch and in one colour, there would be a very appreciable difference in tone between leaves, flowers, and stalks. In gold, the difference would be yet more striking. And that is one reason why gold backgrounds are worked in diapers; not so much for the sake of pattern as to get variety of broken tint.

In the famous Syon Cope the direction of the stitching is frankly independent of the design. That is to say, while the pattern radiates naturally from the neck, the stitches do not follow suit, but go all one way—the way of the stuff. This, though rather a brutal solution of the difficulty, saves all after-thought as to what direction the stitches shall take; but it has very much the effect of weaving. The embroiderer of the thirteenth century was not afraid of that (aimed at

it, perhaps?), and was, apparently, afraid of letting go the leading strings of warp and weft.

When stitches follow the direction of the form embroidered, accommodating themselves to it, all manner of subtle change of tone results. You get, not only variety of colour, but more than a suggestion of form.

That is the second point to be considered.

The direction taken by the stitch always helps to explain the drawing; or, if the needlewoman cannot draw, to show that she cannot—as, for example, in the tulip herewith (83). A less intelligent management of the stitch it would be hard to find. The needle-



83. MEANINGLESS DIRECTION  
OF STITCH.

strokes, far from helping in the very slightest degree to explain the folding over of the petals, directly contradict the drawing. The flower might almost have been designed to show how not to do it; but it is a piece of old work, quite seriously done, only without knowing. The embroidress is free, of course, to work her stitches in a direction which does not express

form at all, so as to give a flat tint, in which is no hint of modelling; but the intention is here quite obviously naturalistic. The rendering below (84) shows the direction the stitches should have taken. The turn-over of the petals is even there not very clearly expressed, but that is the fault of the drawing (very much on a par with the workmanship), from which it would not have been fair to depart.



84. MORE EXPRESSIVE LINES  
OF STITCHING.

A more clever fulfilment of the naturalistic intention is to be seen in Illustration 76. The drawing of the doves is in the rather loose manner of the period of Marie Antoinette; but the treatment of the stitch is clever in its way—the way, as I

have said, rather of painting than of embroidery, giving as it does the roundness of the birds' bodies but no hint of actual feathering, such as you find in the bird opposite (85). There, every stitch helps to explain the feathering. By a discreet use of what I must persist in calling the same stitch (that is, satin-stitch and the variety of it known as





85. SATIN AND PLUMAGE STITCHES.

plumage-stitch) the embroiderer has rendered with equal perfection the sweep of the broad wing feathers and the fluffy feathering of the breast. It is by means of the direction of the stitch, too, that the drawing of the neck is so perfectly expressed.

The direction of the stitch is varied to some purpose in the head in Illustration 80, where the flesh is all in straight upright stitches, whilst the hair is stitched in the direction of its growth.

The five petals on the satin-stitch sampler (Illustration 36)—to descend from the masterly to the elementary—show something of the difference it makes in what direction the stitch is worked. It matters more, of course, in some stitches than in others; but in most cases the direction of the stitch suggests form, and has accordingly to be considered.

It scarcely needs further pointing out how the direction of the stitch may help to explain the construction of the form, as in the case of leaves, for example, where the veining may be suggested; or of stalks, where the fibre may be indicated. There is no law as to the direction of stitch, except that it should be considered. You may follow the direction of the forms, you may cross them, you may deliberately lay your stitches in the most arbitrary manner; but, whatever you do, you must do it with intelligent purpose. An artist or a workwoman can tell at once whether your stitch was

laid just so because you meant it or because you knew no better.

Having laid your stitches deliberately, it is best to leave them, and not to work over them with other stitching. Stitching over stitching was resorted to whenever elaboration was the fashion ; but the simpler and more direct method is the best. The way the veins are laid in cord over the satin-stitch in the lotus leaves in Illustration 40 is the one fault to be found with an all but perfect piece of workmanship.

The stitching over the laid silver mid-rib in Illustration 100 is better judged. It may be said, generally speaking, that except where, as in the case of laid-work, the first stitching was done in anticipation of a second, and the work would be incomplete without it, stitching over stitches should be indulged in only with moderation.

Stitching is sometimes done not merely over stitches, but upon the surface of them, not penetrating the ground-stuff. Unless, in such a case the first stitching is of such compact character as to want no strengthening, it amounts almost to a sin against practicality not to take advantage of the second stitching to make it firmer.

## CHURCH WORK.

It is customary to draw a distinction between church or ecclesiastical, as it is called, and other embroidery ; but it is a distinction without much difference. Certain kinds of work are doubtless best suited to the dignity of church ceremonial and to the breadth of architectural decoration ; accordingly, certain processes of work have been adopted for church purposes, and are taken as a matter of course—too much as a matter of course. The fact is, work precisely like that employed on vestments and the like (Illustration 86) was used also for the caparison of horses and other equally profane purposes.

Practical considerations, alike of ceremonial and decoration, make it imperative that church work should be effective : religious sentiment insists that it should be of the best and richest, unsparingly and even lavishly given ; common-sense dictates that the loving labour spent upon it should not be lost. And these and other such considerations involve methods of work which, by constant use for church purposes, have come to be classed as ecclesiastical embroidery. But there is no





86. RENAISSANCE CHURCH WORK.

consecrated stitch, no stitch exclusively belonging to the church, none probably invented by it. For embroidery is a primitive art—clothes were stitched before ever churches were furnished—and European methods of embroidery are all derived from Oriental work, which found its way westwards at a very early date. Phrygia (sometimes credited with the invention of embroidery) passed it on to Greece, and Greece to Italy, the gate of European art.

Christianity produced new forms of design, but not new ways of work. The methods adopted in the nunneries of the West were those which had already been perfected in the harems of the East.

Embroidery for the church must naturally take count of the church, both as a building and as a place of worship; but, as apart from all other needlework, there is no such thing as church embroidery; and the branding of one very dull kind of thing with that name is in the interest neither of art nor of the church, but only of business. "Ecclesiastical art" is just a trade-term, covering a vast amount of soulless work. There is in the nature of things no reason why art should be reserved for secular purposes, and only manufacture be encouraged by the clergy. The test of fitness for religious service is religious feeling; but that is hardly more likely to be found in the output of the church furnisher (trade patterns overladen with stock symbols), than in

the stitching of the devout needlewoman, working for the glory of God, in whose service of old the best work was done.

Many of the examples of old work given on these pages are from church vestments, altar furniture, and the like; information on that point will be found in the descriptive index of illustrations at the beginning of the book; but they are here discussed from the point of view of workmanship, with as little reference as possible to religious or other use: that is a question apart from art.

The distinguishing features of church work should be, in the first place, its devotional spirit, and, in the second, its consummate workmanship. In it, indeed, we might expect to find work beyond the rivalry of trade, controlled as that is by conditions of time and money. Even then it would be but the more perfect expression of the same art which in its degree ennobled things of civic and domestic use.

Church embroidery, as usually practised in these days, is not only the most rigid and frigid in design, but the hardest and most mechanical in execution. The defect of hardness arises in great part from the way it is done. It is not embroidered straight upon the silk or velvet which forms the ground-work of the design, but separately on linen. The pattern thus worked is cut out, and either pasted straight on to the ground-stuff, or, if the linen is at all loose, first mounted on thin paper and then

cut out and pasted on to the velvet, where it is kept under pressure until it is dry. In either case the edges have eventually to be worked over.

This habit of working on linen or canvas and applying the embroidery ready worked on to the richer stuff, though early used on occasion, does not seem to have been common until a period when manufacture generally usurped the place of art. The work in Illustration 87 was done directly on to the silk. But at a comparatively early date there was already a regular trade in embroidery ready to sew on, by means of which purveyors could turn out in a day or two what would have taken months to embroider directly on to the stuff.

Even if it had been the invariable mediæval practice to work sprays or what not upon canvas and apply them bodily to the velvet, that would not make it the more workmanlike or straightforward way of working. If needle stitches are the ostensible means of getting an effect upon a stuff, it seems only right they should be stitched upon that stuff. To work the details apart and then clap them on to it, stands to embroidery very much in the relation of applied fretwork to wood carving. Nor is it usually happy in result. Occasionally, as in the case of Miss Shrewsbury's vine-leaf pattern (Illustration 88), it disarms criticism. More often it looks stuck-on. A way of avoiding that look is to add judicious after-stitching on the stuff itself. This must not be confined to the sewing





87. GOTHIC CHURCH WORK.

on or outlining merely, but should be allowed to wander playfully over the field, so as to draw your eye away from the margin of the applied patch, and lead you to infer that, some of the needlework being obviously done on the velvet, all of it is. But to disguise in this way the line of demarcation, even if you succeed in doing it, is at best the art of prevarication.

No doubt it is difficult to work upon velvet. The stuff is not very sympathetic, and the stitching has a way of sinking into the pile, and being, as it were, drowned in it. But the trailing spirals of split-stitch which play about the applied spots in many a mediæval altar cloth (Illustration 89) hold their own quite well enough to show that silk can be worked straight on to the velvet.

That gold may be equally well worked straight on to velvet may be seen in any Indian saddle cloth. Heavy work of this kind may be rather man's work than woman's; but that is not the point. The question is, how to get the best results; and the answer is, by working on the stuff.


It may be argued that in this way you cannot get very high relief; but the occasions for high relief are, at the best, rare. If you want actual modelling, as in the Spanish work referred to in a previous chapter, that must, of course, be worked separately, built up, as it were, upon the canvas and worked over. And there is no reason why it



88. MODERN CHURCH WORK BY MISS SHREWSBURY.

should not, for in no case does it appear to be stitching. In fact, it aims deliberately at the effect of chased and beaten metal.

Heavy appliqué of any kind affects, of course, not only the thickness but the flexibility of the material thus enriched—an important consideration if it is meant to hang in folds.



89. GOTHIC SPRIG APPLIQUÉ.



## WHITE WORK.

Reference has already been made in passing to the texture given by stitching, and to the variation in colour produced by it according to the direction of the stitch. In white embroidery upon white the contrast between work and ground is entirely a contrast of texture, which thus takes the place of colour. And when it is remembered that in linen damask the pattern is entirely the result of the different direction of the warp and weft threads, it is not surprising that the embroiderer, with the whole range of stitches at her command, can by texture alone, by difference of surface that is to say, produce pattern work of very great variety. The differences are subdued, of course; the worker plays in a minor key—but those who care for delicate work enjoy it none the less that it is played in undertones, “*pianissimo*,” as it were.

White work gains something in effect when it is worked in thread of different material from the ground—in silk on linen, for example—as in some of the old Persian work, which is singularly beautiful. In Indian and Chinese work the difference of texture is accentuated by working in floss or in

twisted silk upon crêpe or "tabby." The contrast obtained in modern embroidery by working in cotton upon cambric is less satisfactory. There is something rather objectionable in ornamenting one material with another that is inferior to it; and cotton is a poor thread with which to decorate linen.

Nevertheless embroidery in white on white has been carried in our own time to a point of very considerable accomplishment, which is the more remarkable because it is practised not as an art but as an industry, and apparently a paying one. We have been able, with the assistance of Mr James Jeffrey, to explain the stitches and processes generally employed by the peasant women of Down and Donegal, and to illustrate them in a series of patterns which he has had worked for us at Belfast, chiefly from designs devised to illustrate the capabilities of the stitches generally in use. The bird pattern, however, in Illustration 90 is by Mr Jeffrey himself, designed by him in the ordinary way of trade. The execution of these examples, by women working for a factory, speaks better for the ability of the needlewomen than for the public taste which they follow. Such work as theirs under existing conditions argues well for what even peasant women might do if only they were directed by some one whose first care and thought was for art.

There is nothing very new about the stitches employed in white work, but they need to be

chosen with a view to the effect that can be got by texture—by the contrast, that is to say, of the



90. WHITE WORK BY JAMES JEFFREY.

surface of one stitch with the surface of another, and of the work generally with the plain linen. It

is by leaving ample surface of this last intact, and judiciously massing the ornament upon it, that the most refined and beautiful results are obtained.

Of the stitches commonly employed the most serviceable is—

SATIN  
STITCH.

Satin stitch, always more or less raised by an under-padding of stitches in the cross direction—"tracing" is the trade name for it. The longer the satin stitches, the more likely they are to open out or get loose and show the under-sewing. Broad



91. WHITE WORK ON LINEN.





92. DETAILS DESIGNED TO BE WORKED CHIEFLY IN  
SHORT SATIN STITCHES.

surfaces are therefore better broken up. A leaf, for example, that is too wide to be satisfactorily worked in single stitches—they are always carried straight across the forms—is crossed by a double series of stitches, in which case (as in the rose leaves in Illustration 92) the dip between the two stitches gives a well-defined mid-rib. The design, in short, is affected by the method of work, and the method of work should affect the design. The leaves above are deliberately designed to be worked in sufficiently short satin stitches.

The common ideal is always to make the design stand out as much as possible from the ground, and the relief is often excessive. Sufficient distinction between the ground and the pattern is all that is necessary, and that is easily got in quite low relief. Outlines (Illustration 91) are worked in satin stitch, sometimes over a cord, but more often over two or three strands of the same kind of thread that is afterwards used in working over them.

PLUMAGE  
STITCH.

Another obvious way of getting over broader masses than it is convenient to work straight across in satin stitch, is to employ what is known as "long and short," or "plumage" stitch (they call it "feather" stitch in Belfast) which, as already explained (page 100), is only another form of satin stitch. It is in this way that the breasts of the birds are worked in Illustration 90; but it is only in design of a rather ambitious kind that there is occasion for this; and it is not often that there is occasion for very ambitious design in white work. A more minute version of the stitch is used to suggest, for example, the texture of fur in the rendering of heraldic animals — which there is, artistically speaking, no need to do, though it may be occasionally advisable to work in the finest possible stitches.

SEEDING.

Great decorative use may be made, and is made, in white work of dots or spots, "seeding" as they call it, which may be executed in French knots, but is more often stitched with a double thread



93. WHITE WORK WITH SEEDING AND MATTING.

from the back, the worker holding the cloth upside down in her hoop while she does it. It is probably only by the association of ideas that the dots of

thread thus left exposed suggest something like seed pearls ; they are not really round, as may be seen in the dotted leaves in Illustration 93. The filling in of the leaves outlined in satin stitch in Illustration 92 shows a very minute variety of seed-  
MATTING. ing technically known as "matting." The value of this kind of stitching in white work is apparent in most of the illustrations to this chapter, where it is used to give texture varying from just a tint, as in Illustration 92, to a more or less conspicuously dotted surface as in the butterfly in Illustration 96.


APPLIQUÉ. By means of appliqué the worker on fine cambric has an opportunity of getting the effect of solid white upon a relatively greyish tint. It is a simple and quite a common device to plant little squares of cambric upon cambric in the way shown in Illustration 94. They are very often sewn down with a sort of herring-bone stitch ; but that is for the worker to decide, according as she may wish to emphasise the outline or not. It will be seen that the stitching down in Illustration 94 draws the threads of the cambric ground apart, and gives the sort of open outline so familiar in hem-stitch.

EYELETS. "Eyelets" such as those forming the berries in Illustration 92, are worked by first piercing little holes in the cloth and then stitching round them in satin stitch—not, as might have been supposed, in buttonhole stitch.



By piercing a number of holes very close one to another, and binding them together at the edges, a kind of open-work is produced which, as may be seen in the vase shape in Illustration 91, need not

SPARRING  
OR SPOKE  
STITCH.



94. WHITE WORK ON CAMBRIC WITH APPLIQUÉ.

by any means follow the square lines of the weaving, as drawn work must do. The lines, for example, across the butterfly's body in Illustration 96 would of necessity have been straight if they had been


"drawn," and the open pattern on the wings could not possibly have followed their outline as it does in this "sparring" or "spoke" stitch as they call it.

DRAWN  
WORK.

What comes of drawn work, also largely used in white embroidery, is shown in Illustration 95, where the square lattice pattern is the natural result of working on the threads of the material. A diaper which followed the radiating lines of the design could not possibly have been executed in drawn work. The drawing of the threads—they are not cut—does not, if judiciously done, appreciably weaken the linen. There is no suggestion of weakness, for example, in the instance given, and such open-work is an excellent foil to the satin stitch and appliqué with which it is constantly associated.

This enumeration of the stitches employed in County Down and Donegal, and the illustration of the practical uses to which they may be put, is only by way of showing the kinds of work which have answered the purpose of white embroidery, and will stand the wear and washing it has ordinarily to undergo. It is probable, too, that women working for their living have discovered for themselves the shortest, simplest, and in so far the best, way of doing what they set out to do. But they have by no means exhausted the possibilities of workmanship in white—there is ample evidence in old work (page 45) to the contrary. Any stitch used in coloured work will serve, provided only that it will give the


texture necessary to relieve the pattern from the ground, and that it is firm and substantial enough



95. WHITE EMBROIDERY WITH APPLIQUÉ AND  
DRAWN WORK.

for its purpose. No artist or amateur will think of limiting herself to the devices current in manufac-

ture ; but to know them is to be the better prepared to make use of the suggestions everywhere to be found in needlework generally, no matter what its colour may be. Our illustrations are enough to show this. The artist in white will in the end work out her own system. It is hardly necessary to insist that there is room in white work for the most delicate and delightful art—none the less delightful that it is modest. It is inherently that.



96. WHITE WORK WITH SEEDING AND SPARRING.



## A PLEA FOR SIMPLICITY.

The simplest patterns are by no means the least beautiful. It is too much the fashion to underrate the artistic value of the less pretentious forms of needlework, and especially of flat ornament, which has, nevertheless, its own very important place in decoration. As for geometric pattern, that is held to be beneath consideration—it is so mechanical! Mechanical is a word as easily spoken as another; but if needlework is mechanical, that is more often the fault of the needlewoman than of the mechanism she employs. The Orientals, who indulged so freely in geometric device, were the least mechanical of workers. It is our rigid way of working it which robs geometric ornament of its charm. The needleworker has less than ever occasion to be afraid of geometric pattern; for it is peculiarly difficult to get with the needle that appearance of rule-and-compass-work which makes ornament so dull.

The one real objection to geometric pattern is that it is nowadays so cheaply and so mechanically got by *weaving* that, however freely it may be rendered, there is a danger of its suggesting

mechanical production, which embroidery emphatically ought not to do. There is a similar objection nowadays to some stitches, such, for example, as chain-stitch and back-stitch: they suggest the sewing-machine.

Embroidery does not to-day take quite the place it once did. It was used, for example, by the early Coptic Christians to supplement tapestry. That is to say, what they could not weave they stitched; it was only to get more delicate detail than their tapestry loom would allow, that they had recourse to the needle. Needlework was, in fact, an adjunct to weaving. Later, in mediæval times, the Germans of Cologne, for their church vestments and the like, wove what they could, and enriched their woven figures with embroidery.

Again, a great deal of Oriental embroidery, and of peasant work everywhere, is merely the result of circumstances. Where money is scarce and time is of no account, it answers a woman's purpose to do for herself with her needle what might in some respects be even better done on the loom. Her preference for handwork is not that it has artistic possibilities, but that it costs her less. She would in many cases prefer the more mechanically produced fabric, if she could get it at the same price. We do not find that Orientals reject the productions of the power-loom—which they would do if they had the artistic instincts with which we credit them.




97. SIMPLE STITCHING ON LINEN.

It results from our conditions of to-day that there are some kinds of needlework we admire, which yet are seldom worth our doing, such, for example, as the all-over work, which does not amount to more than simple diaper, and which really is not so much embroidering on a textile as converting it into one of another kind. Glorified instances of this kind of work occur in the shawl work of Cashmere, and in those beautiful bits of Persian stitching which remind one of carpet-work in miniature, if they are not in fact related to carpet-weaving.

Embroidery was at one time the readiest, and practically the only, means of getting enrichment of certain kinds. To-day we get machine embroidery. As machinery is perfected, and learns to do what formerly could be done only by the needle, handworkers get pushed aside and fall out of work. Their chance is, in keeping always in advance of the machine. There is this hope for them, that the monotony of machine-made things produces in the end a reaction in favour of handwork—provided always it gives us something which manufacture cannot. Possibly also there is scope for amateurs and home-artists in that combination of embroidery and hand-weaving with which the power-loom, though it has superseded it, does not enter into competition.

It is not so much for geometric ornament as for simple pattern that the plea is here made for





98. SIMPLE COUCHING ON LINEN.

that reticent work of which so much was at one time done in this country—mere back-stitching, for example, or what looks like it, in yellow silk upon white linen ; or the modest diaper, archaic, if you like, but inevitably characteristic, in which the naïveté of the sampler seems always to linger ; or again, the admirably simple work in Illustration 97. This last does not show so delicately in the photographic reproduction as it should, because, being in grey and yellow on white linen, the relative value of the two shades of colour is lost in the photograph. In the original the broader yellow bands are much more in tone with the ground, and do not assert themselves so much. Such as it is, only an artist could have designed that border-work ; and any neat-handed woman could have embroidered it.

Think again of the delicate work in white or in self colour, which makes no loud claim to be art, but is content to be beautiful ! Is that to be a thing altogether of the past now that we have Art Needlework ? Art needlework ! It has helped to put an end to the patience of the modern worker, and to inspire her too often with ambitions far beyond her powers of fulfilment.

What one misses in the work of the present day is that reticent and unpretending stitchery, which, thinking to be no more than a labour of loving patience, is really a work of art, better deserving the title than much that is done in the name of

“art needlework.” We plume ourselves too much upon our art. Is any one nowadays modest enough to do work such as the couching in outline in Illustration 98? Yet what distinction there is about it!

## EMBROIDERY DESIGN.

Perfect art results only when designer and worker are entirely in sympathy, when the designer knows quite what the worker can do with her materials, and when the worker not only understands what the designer meant, but feels with him. And it is the test of a practical designer that he not only knows the conditions under which his design is to be carried out, but is ready to submit to them.

The distinction here made between designer and embroiderer is not casual, but aforethought, notwithstanding the division of labour it implies. Enthusiasm has a habit of outrunning reason. Because in some branches of industry subdivision of labour has been carried to absurd excess, it is the fashion to demand in all branches of it the autograph work of one person. That is no less absurd. To try and link together faculties which Nature has for the most part put asunder, is futile.

To insist that designer and worker should be one and the same person is to set up an ideal for the most part impossible of fulfilment. When



that happens (Illustrations 61 and 88) it is well. But the attempt to realise it commonly works out in one of two ways: either a good design is spoilt in the working for want of executive skill on the part of the designer, or good workmanship is spent on poor design, as good, perhaps, as one has any right to expect of a needleworker, skilful as she may be.

The fact is, you can only make out all the world to be designers by reducing design to what all the world can do. And that is not much. There is a point of view from which it does not amount to design at all.


The study of design forms part of the education of an embroidress, not so much that she may design what she works, but that she may know in the first place what good design is, and, in the second, be equal to the ever-recurring occasion when a design has to be modified or adapted. If, in thus manipulating design not hers, she should discover a faculty of invention, she will want no telling to exercise it. A designer wants no encouragement to design—she designs.

There would be no occasion to dwell upon this, were it not for the prevalence at the present moment of the idea that a worker, in whatever art or handicraft, is in artistic duty bound to design whatever she puts hand to do. That is a theory as false as it is unkind: let no embroidress be dis-

couraged by it. Let her, unless she is inwardly impelled to invent, remain content to do good needlework. That is her art. Her business as an artist is to make beautiful things. Co-operation in the making of them is no crime.

And what, then, about originality? Originality is a gift beyond price. But it is not a thing which even the designer should struggle after. It comes, if it is there. There is a revengeful consolation for the pain we suffer from design about us writhing in the endeavour to be up-to-date, in the thought that its contortions tell what pain it cost to do it. The birth of beauty is a less agonising travail; and the thing to seek is beauty, not novelty. Whoever planned the lines of the border in Illustration 99, or treated the leafage in Illustration 100, was not trying to be original, but determined to do his best. Artists and workers of individuality and character *are* themselves, without being so much as aware that originality has gone out of them.

To assume, then, that every needlewoman is, or can ever be, competent to design what she embroiders, is to make very small account of design. How is it possible to take design seriously and yet think it is to be mastered without years of more serious study than workwomen can or will as a rule devote to it? Any cultivated woman may for herself invent (if it is to be called invention) something better worth working than



99. RENAISSANCE ORNAMENT.

is to be bought ready to work. And that may do for many purposes, so long as it does not claim to be more than it is; but in the case of really important work, to be executed at considerable cost not only of material but of patient labour, surely it is worth giving serious thought to its design. The scant consideration commonly given to it hardly suggests a worker very much in earnest. Or has she thought? And is she persuaded that her artless spray of flowers, or the ironed-off pattern she has bought, is all that art could be? It would be rude to tell her she was wasting silk!

A worker should know what is worth working; and the only way of knowing is to study, to look at good work, old work by preference; it is worth no one's while to praise that unduly. And if in all that is now so readily accessible she finds nothing to admire, nothing which appeals to her, nothing which inspires her, then her case is hopeless. If, on the other hand, she finds only so much as one style of work sympathetic to her, studies that, lets its spirit sink into her, tries to do something worthy of it, then she is on the right road. Measure yourself with the best, not with the common run of work; if that should put you out of conceit with your own work, no great harm is done; sooner or later we have got to come to a modest opinion of ourselves, if ever we are to do even moderately good things.





100. LEAF TREATMENT IN APPLIQUÉ.

But the "best" above referred to does not necessarily mean the most masterly. The best of a simple kind is not calculated to discourage any one—rather, it looks as if it must be easy to do that; and in trying to do it we learn how much goes to the doing it. Good design need not be of any great importance or pretensions. It may be quite simple, if only it is right; if the lines are true, the colour harmonious; if it is adapted to its place, to its use and purpose, to execution not only with the needle but in the particular kind of needlework to be employed.

There has of late years been something of a revival of needlework design in schools of art, and some very promising and even most accomplished work has been done; but in many instances it is rather design which has been translated into needlework, than design clearly made for execution with the needle. A really appropriate and practical design for embroidery should be schemed not merely with a view to its execution with the needle, but with a view to its execution in a particular stitch or stitches—possibly by a particular embroidress. To be safe in designing work so minute as that on Illustration 101, one must be sure of the needlewoman who is to execute it.

Reference to old work must not be taken to imply that design should be in imitation of what has been done, or that it should follow on those



101. DELICATE SATIN-STITCH—WORKED BY MISS BUCKLE.

lines. Design was once upon a time traditional ; but the chain of tradition has snapped, and now conscious design must be eclectic—that is to say, one must study old work to see what has been done, and how it has been done, and then do one's own in one's own way. It is at least as foolish to break quite away from what has been done as to tether yourself to it. And in what has been done you will see, not only what is worth doing, but what is not. That, each must judge for herself. To the lover of ornament it will seem that the thing best worth doing in embroidery is ornament. Any way, this much is certain (and you have only to go to the nearest museum to prove it), that there is no need for needleworkers, unless their instinct draws them that way, to take to needle painting, to pictures in silk, or even to flower stitching.

The limitations of embroidery are not so rigidly marked as the boundaries of many another craft. There is little technical difficulty in representing flowers, for example, very naturally—too naturally for any dignified decorative purpose. Embroiderer or embroidery designer will, as a matter of fact, be constantly inspired by flower forms, and silk gives the pure colour of their petals as nearly as may be. But, though the pattern be a veritable flower garden, the embroidress will not forget, to use the happy phrase of William Morris, that she is gardening with silks and gold threads.

Let the needleworker study the work of the



needle in preference to that of the brush ; let her aim at what stuff and threads will give her, and give more readily than would something else. Let her work according to the needle, and take that for her guide, not be misled by what some other tool can do better, but do what the needle can do best, and be content with that. That is the way to Art in Needlework, and the surest way.

## EMBROIDERY MATERIALS.

Embroidery is not among the things which have to be done, and must be done, therefore, as best one can do them. It is in the nature of a superfluity: the excuse for it is that it is beautiful. It is not worth doing unless it is done well, and in material worth the work done on it. If you are going to spend the time you must spend to do good work, it is worth while using good stuff, foolish to use anything else. The stuff need not be costly, but it should be the best of its kind; and it should be chosen with reference to the work to be done on it, and *vice versa*. A mean ground-stuff implies, if it does not necessitate, its being embroidered all over, ground-work as well as pattern; a worthier one suggests that it should not be hidden altogether from view; a really beautiful one asks that enough of it should be left bare of ornament that its quality may be appreciated.

### STUFFS.

It goes without saying, that for big, bold stitching a proportionately coarse ground-stuff should be used, and for delicate work, one of finer texture—whether it be linen, woollen cloth, or silk, your purpose will determine.

Linen is a worthy ground-stuff, which may be worked on with flax thread, crewel, or silk, but they should not be mixed. Cotton is hardly worth embroidering. Of woollen stuffs, good plain cloth is an excellent ground for work in wool or silk, but it is not pleasant to the touch in working. Serge, if not too loose, may serve for curtains and the like, but it is not so well worth working upon. Felt is beneath contempt.

The nobler the material, the more essential it is that it should be of the best. Poor satin is not "good enough to work on"; it looks poorer than ever when it is embroidered.

Satin should be stretched upon the frame the way of the stuff, and it should not be forgotten that it has a right and a wrong way up. If it is backed, the linen should be fine and smooth: on a coarse backing, the satin gets quickly worn away, as you may see in many a piece of old work that has gone ragged.

"Roman satin" and what is called "*satin de luxe*" (perhaps because it is not so luxurious as it pretends to be) are effective ground-stuffs easy to work upon; but there is an odour of pretence about satin-faced cotton.

A corded silk is not good to embroider; the work on it looks hard; but a close twill answers very well. Silk damask makes an admirable ground, beautifully broken in colour, if only it is simple and broad enough in pattern. Generally speaking,

you can hardly choose a design too big and flat; but something depends upon the work to be done on it. In any case, the pattern of the damask ought not to assert itself, and if you can't make out its details, so much the better.

Brocade asserts itself too much to form a good background. There is a practice of embroidering the outlines, or certain details only, of damask and brocade patterns. That is a fair way of further enriching a rich stuff; but it is embroidery merely in the sense that it is literally embroidered: the needlework is only supplementary to weaving.

Tussah silk of the finer sort is easy to work in the hand. The thinner and looser quality needs to be worked in a frame, and with smooth silk not tightly twisted.

#### THREAD.

With regard to the thread to work with: The coarser kinds of flax are best waxed before using. The crewel to be preferred is that not too tightly twisted. Filoselle is well adapted to couching, and may be laid double (24 threads). French floss is smooth, and does well for laid work; for fine work bobbin floss, or what is called "church floss," is better; the slight twist in filo-floss is against it; very thick floss may be used for French knots.

For couching gold, a very fine twisted silk does well. Purse silk, thick and twisted, lends itself perfectly to basket work. Working in coloured silks, one should take advantage of the quality



of pure transparent colour which silk takes in the dyeing. The palette of the embroiderer in silk is superlatively rich.

The purest gold is generally made on a foundation of *red* silk. Japanese gold does not tarnish so readily as "passing," which is in some respects superior to it. For stitching through, there is a finer thread, called "tambour." Flat gold wire is known by the name of "plate," and various twisted threads by the name of "purl."

GOLD.

A not very promising substance to embroider with is chenille. It came into use in the latter half of the seventeenth century, and was still in fashion in the time of Marie Antoinette. The use of it is shown in Illustration 75, where the darker touches of the roses are worked in it. Chenille seems to have been used instead of smooth silk, much as in certain old-fashioned water-colour paintings gum was used with the paint, or over it, to deepen the shadows. The material is used again in the wreath on Illustration 76. It is worked there in chain-stitch with the tambour needle: it may also be worked in satin-stitch; but the more obvious way of using it is to couch it, cord by cord, with fine silk thread. There is this against chenille, that its texture is not sympathetic to the touch, and that there is a stuffy look about it always. Nor does it seem ever quite to belong to the smooth satin ground on which it is worked.

RIBBON. There is less objection to embroidery in ribbon, which also had its day in the eighteenth century. It was very much the fashion for court dresses under Louis Seize. "*Broderie de faveur*" it was called, whence our "lady's favour"—*faveur* being a narrow ribbon. Beautiful work of its kind was done in ribbon, sometimes *shaded* ribbon. Shaded silk, by the way, may be used to artistic purpose. There is, for example, in the treasury of Seville Cathedral a piece of work on velvet, thirteenth century it is said, rather Persian in character, in which the forms of certain nondescript animals are at first sight puzzlingly prismatic in colour. They turn out to be roughly worked in short stitches of parti-coloured silk thread. The result is not altogether beautiful, but it is extremely suggestive.

RIBBON. The effect of ribbon work is happiest when it is not sewn through the stuff after the manner of satin-stitch, but lies on the surface of the satin ground, and is only just caught down at the ends of the loops which go to make leaves and petals. The twist of the ribbon where it turns gives interest to the surface of the embroidery, which is always more or less in relief upon the stuff. It is easy to crush, and of limited use therefore.

An effect of ribbon work, but of a harder kind, was produced by onlaying narrow strips of card or parchment upon a silken ground, twisted about after the fashion of ribbon. These, having been



102. LEATHER APPLIQUÉ UPON VELVET.

stitched in place, were worked over in satin-stitch. The work has the merit of looking just like what it is. But neither it nor ribbon embroidery is of any very serious account.

Passing reference has been made to other materials to embroider with besides thread. Gold wire, for example, and spangles, coral and pearls, which have been used with admirable discretion, as well as to vulgar purpose. Jewels also were lavished upon the embroidery of bishops' mitres, gloves and other significant apparel, and in default of real stones, imitations in glass, and eventually beads (or pearls) of glass, in which we have possibly the origin of knots. Bead embroidery is at least as old as ancient Egypt. Even atoms of looking-glass, sewn round with silk, are used to really beautiful effect (barbaric though it may be) in Indian work. The question almost occurs: with what can one not embroider? In Madras they produce most brilliant embroidery upon muslin with the cases of beetles' wings. In the Mauritius they use fish-scales; in North America, porcupine quills; and everywhere savage tribes use seeds, shells, feathers, and the teeth and claws of animals.

To return to more civilised work, there is embroidery in gold and silver wire, allied to the art of the goldsmith, and on leather (Illustration 102), allied to the art of the saddler. It would be difficult to set any limit to the directions in which



embroidery may branch out, impossible to describe them all. Happily, it is not necessary. A skilled worker adapts herself to new conditions, and the conditions themselves dictate the necessary modification of the familiar way.

## A WORD TO THE WORKER.

A good workwoman will not encumber herself with too many tools ; but she will not shirk the expense of necessary implements, the simplest by preference, and the best that are made.

NEEDLES. Embroidery needles should have large eyes : the silk is not rubbed in threading them, and they make way for the thread to pass smoothly through the stuff. For working in twisted silk, the eye should be roundish ; for flat silk, long ; for surface stitching or interlacing, a blunt “tapestry needle” is best ; for carrying cord or gold thread through the stuff, a “rug needle.”

THIMBLE. For a thimble, choose an old one that has been worn quite smooth.

SCISSORS. For scissors, be sure and have a strong, short, sharp and pointed pair—the surgical instrument, not the fancy article. Nail scissors would not be amiss but for the roughness of the file on the blades.

PINS. For pins, use always steel ones ; and for tacks, those which have been tinned ; or they will leave their mark behind them.

For a frame, get the best you can afford ; a cheap

one is no economy; but a stand for it is not always necessary. It should be rather wider than might seem necessary, as the work should never extend to the full width of the webbing. A tambour frame is also useful, even though you have no intention of doing tambour work.

FRAMES.

In stretching silk (not backed with linen) upon a frame, some preliminary care is necessary. The stuff should first be bordered with strips of linen or strong tape, and into the two sides of this border which are to be laced up a stout string should be tacked, to prevent it from giving when the work is drawn tight.

TO  
STRETCH  
SILK.

The way to put embroidery material (thus bordered or not) into a frame is: first to sew it to the webbing (top and bottom), then to put the laths or screws into the bars, tightening them evenly, and lastly to lace it to the sides with fine string and a packing needle.

FRAMING.

The ordinary ways of transferring a design to embroidery material are well known: the outline may be traced down with a point over transfer paper; it may be pricked upon paper and pounced upon the stuff in chalk or charcoal, and then traced in with a brush or pen; or it (still the outline only) may be stencilled. In any case, the outline marked upon the stuff should be well within what is to be the actual outline of the embroidery when worked. Another way, more peculiarly adapted to needle-work, is to trace the outline in ink upon fine

TRANS-  
FERRING.

tarlatan (leno muslin will do for very coarse work), and, having laid this down upon the stuff, to go over the lines again with a ruling pen and Indian ink or colour. On a light stuff it is possible to use, instead of a pen, a hard pencil. On a dark material one must use Chinese white, to which it is well to add, not only a little gum (arabic), but a trace of ox-gall, to make it work easily. One gets by this method naturally rather a rotten line upon the ground-stuff, but it is enough for all practical purposes.

KEEPING  
CLEAN.

Delicate work is easily rubbed and soiled in the working. It is only reasonable precaution to protect it by a veil or covering of thin, soft, white, glazed lining, tacked round the edges on to the stuff. On this you mark the four lines enclosing the actual embroidery, and, cutting through three of them, you have a flap of lining, which you raise and turn back when you are at work. If the work is very delicate, you may make instead of one flap a succession of little ones ; but you see then only a portion of your work at a time, and cannot so well judge its effect.

STARTING  
AND  
FINISH-  
ING.

In starting work, do not begin by making a knot in your thread ; run a few stitches (presently to be worked over) on the right side of the stuff. In finishing, you run them at the back of the stuff ; for greater security still, one may end with a buttonhole-stitch.

There is less danger of puckering the stuff if



you hold it over two fingers (at least), keeping it taut and the thread loose.

PUCKER-  
ING.

Working without a frame, it often comes handiest to hold the stuff askew, and there is a natural inclination to pull it in that direction. This temptation must be resisted, or puckering is sure to result.

In working with double silk or wool, it is better not to double back a single thread, but to pass two separate threads through the eye of the needle. The four threads (where these are turned back near the eye) make way through the stuff for the double thread, which passes easily; moreover, the thread by this means is not pulled too tight, and the effect is richer.

DOUBLE  
THREAD.

The stitch wants always adaptation to the work it has to do. In working a curved line, for example, say in herring-bone-stitch, one is bound always to take up a larger piece of stuff on its outside than on its inner edge.

When a thread runs short, it is better not to go on working with it, but to take another; and, in finishing off, remember to run the thread in the direction opposite to that from which you are going to run the new one. In starting the new stitch, you naturally bring your needle out as if it were a continuation of that last made.

If your work is faulty, cut it out and do it again. Undoing. Unpicking is not so satisfactory: it loosens the stuff to drag the thread back through it, and the thread

saved is of no further use. Beginners find it hard to undo work once done; but a really good needlewoman never hesitates about it—her one thought is to get the thing right. Don't break your thread ever: that pulls it out of condition: always cut it.

In working, it is well to keep strictly to the stitch you have chosen, but not to the point of bigotry. One may finish off darning, for example, at the edges with a satin-stitch. The thing to avoid is fudging. Moreover, stitches should be laid right at once; there should be no boggling and botching, no working-over with stitches to make good—that is not playing fair.

SMOOTH-  
ING.

When the needlework is done, do not finish it with a flat iron. That finishes it in more senses than one. But suppose it is puckered? In that case, stretch it and damp it. To do this, first tack on to it (as explained on page 263) a frame of strong tape. Then, on a drawing-board or other even wooden surface, lay a piece of clean calico, and on that, face downwards, the embroidery, and, slightly stretching it, nail it down by the tape with tin-tacks rather close together. If now you lay upon it a damp cloth, the embroidery will absorb the moisture from it, and when that is removed, should dry as flat as it is possible to get it.

A rather more daring plan is to damp the back of the stuff with a wet sponge. The work, instead of being nailed on to a board, may just as well be

laced to a frame by the tape. In the case of raised embroidery there must be between it and the wood, not a cloth merely, but a layer of wadding.

The damping above described may take the form of a thin paste or stiffening but upon silk or other such material this wants tenderly doing.

One last word as to thoroughness in needlework. Those who have really not time to do much, should be satisfied with simple work. The desire to make a great show with little work is a snare. Ladies make protest always, "There is too much work in that." Well, if they are not prepared to work, they may as well give themselves up to their play. There was no labour shirked in the old work illustrated in these pages; and nothing much worth doing was ever done without work, hard work, and plenty of it. Should that thought frighten folk away, they may as well be scared off at once. Art can do very well without them.





# INDEX.

	PAGE		PAGE
ADAPTATION of stitch	103,	CABLE-CHAIN - - -	42
	188, 265	CANVAS - - -	- 7, 25
ANTIQUE-stitch - - -	66	CANVAS stitches -	12 <i>et seq.</i>
( <i>See also Oriental-stitch.</i> )		CANVAS-STITCH embroidery	22
APPLIQUÉ 140, 144 <i>et seq.</i> , 220,		CARD underlay -	162, 258
222, 224, 232, 233		CASHMERE embroidery -	240
ARAB work - - -	152	CASHMERE-STITCH - -	18
ARTLESS art - - -	37, 248	CHAIN-STITCH 38 <i>et seq.</i> , 61,	
ATTACHMENT of cord -	124	83, 129, 145, 156, 158,	
		178, 182, 202, 238, 257	
		CHENILLE - - -	257
BACKSTITCH 30, 37, 41, 53,		CHINESE embroidery 78, 96	
83, 86, 172, 238, 242		129, 136, 140, 152	
BASKET patterns - - -	134	CHURCH work 41, 136, 148	
BEADS - - -	260	166, 216 <i>et seq.</i>	
BEGINNING & FINISHING	264	CLASSIFICATION of stitches 9,	
BLANKET-STITCH - - -	56	175 <i>et seq.</i>	
BRAID-STITCH - - -	42, 43	CLOTH - 125, 126, 159, 255	
BROAD surfaces (covering)	178	COLOUR - - -	110, 208
BROCADE - - -	256	COLOUR gradation 98, 114, 118	
BULLION - - -	165	COLOUR and outline 146, 185	
BULLION-STITCH 75, 76, 162,		COMBINATION of stitches -	182
165		COPTIC embroidery -	12, 238
BUTTONHOLE-STITCH 8, 55 <i>et</i>		„ tapestry - - -	2
<i>seq.</i> , 69, 122, 145, 158,		CORAL - - -	166, 260
178, 182		CORD - - -	122
BUTTONHOLING (lace) 84, 86		„ (couched) 128, 144, 178	
BYZANTINE embroidery 12, 24		182	

	PAGE		PAGE
CORD (attachment of) -	124	DOUBLE darning -	106
COTTON -	255	,, thread -	265
COUCHED cord 128, 144, 178,	182	DOVETAIL-STITCH -	103, 104
,, gold 131 <i>et seq.</i> ,	182	( <i>See also Embroidery and</i>	
,, outline -	146	<i>Plumage Stitches.</i> )	
COUCHING 22, 114, 120, 121,	122 <i>et seq.</i> , 256	DRAWING with the needle 192,	194, 196, 199, 211
,, (reverse) -	130	DRAWN work -	2, 4, 234
COUNTERCHANGE -	154		
CRETAN embroidery -	12		
CRETAN-STITCH -	61	EASTERN embroidery. ( <i>See</i>	
( <i>See also Ladder-stitch.</i> )		<i>Oriental.</i> )	
CREWEL -	256	EFFECT and stitch -	36, 78
CREWEL-STITCH 26 <i>et seq.</i> , 83,	86, 103, 105, 178,	EIGHTEENTH century em-	
,, (surface) -	86	broidery -	220, 258
CREWEL work -	26, 36, 37	EMBROIDERY and painting	201, 202
CROSS-STITCH -	12, 14, 16	EMBROIDERY-STITCH -	103
CROSSED buttonhole-stitch	56	( <i>See also Plumage-stitch.</i> )	
CUSHION-STITCH -	20, 21	ENGLISH embroidery 34, 36,	169
CUT-WORK -	156	EYELETS- -	233
DAMASK -	255, 256		
DAMPING -	266, 267	FEATHER-STITCH 62 <i>et seq.</i> ,	83, 100, 178, 230
DARNING 8, 22, 83, 90, 106	<i>et seq.</i> , 178, 179	FELT -	255
,, (Japanese) -	86	FIFTEENTH century em-	
,, (surface) -	84	broidery -	24, 164
DESIGN - 150, 219, 245 <i>et seq.</i>		FIGURE work 116, 169, 190,	198 <i>et seq.</i>
,, traditional -	250, 252	FILLING-IN patterns -	24
DESIGN and stitch -	10, 250	FILO-FLOSS -	164, 256
DESIGNER and embroiderer	244, 245	FILOSELLE -	124, 144, 256
DIAPERS 87, 88, 108, 132, 134,	210	FISHBONE -	21, 47, 51
DIRECTION of stitch 92, 95, 108		FLAX thread -	164, 256
114, 136, 190, 208 <i>et seq.</i> , 225		FLEMISH embroidery 142, 200	
		FLESH -	204, 206

	PAGE		PAGE
FLORENTINE-STITCH	18, 21	INLAY - - -	153
(See also <i>Cushion-stitch</i> .)		INTERLACING stitches	83
FLOSS 95, 114, 116, 118, 120,	256	ITALIAN embroidery	22, 24, 37, 46, 138
FORM and stitch 44, 47, 100,	118, 176, 211, 265	ITALIAN embroidery (Re-	
FRAMING work - -	263	naissance) 22, 41, 120,	142, 154, 199
FRENCH embroidery	88, 257		
„ floss - -	256	JAPANESE darning -	86, 87
„ knots 77, 129, 150,	178, 256	„ embroidery -	80
		„ gold - -	257
		JEWELS - - -	165, 260
GEOMETRIC pattern - -	237		
GERMAN embroidery 110, 125,	126, 156, 185, 238	KNOT-STITCHES 72 <i>et seq.</i> ,	182
„ knot-stitch - -	72		
GOBELIN-STITCH - -	18	LACE - - -	1, 2
GOLD - - -	210, 222, 257	LACE stitches - -	84 <i>et seq.</i>
„ (couched) 131 <i>et seq.</i> ,	182	LADDER-STITCH	59, 61, 182
„ (raised) - 134, 136, 165		LAID-WORK 112 <i>et seq.</i> ,	162, 178
„ thread - -	131, 257	LEATHER - - -	260
„ tinted by couching		LEATHER on velvet -	150
stitches - -	142	LENGTH of stitch -	96, 100
„ wire - -	169, 260	LIMITATIONS of embroidery	252
		LINE work - - -	176, 178
HALF-CROSS-STITCH - -	20	LINEN - - -	164, 255
HEMSTITCH - - -	233	„ (embroidery on) -	24
HERALDIC embroidery -	156	LONG-AND-SHORT-STITCH	36,
HERRING-BONE-STITCH 8, 22,	47 <i>et seq.</i> , 83, 178, 182, 233	98, 100, 178, 190, 192, 230	
HILDESHEIM cope (the) -	126		
HUNGARIAN embroidery -	2	MAGIC-STITCH - - -	41
„ stitch - -	18	MATERIAL (influence of on	
		stitch) 12, 13, 16, 18, 24,	88, 91
INDIAN embroidery 41, 46, 61,	95, 98, 154, 169, 222, 260	MATERIALS - - -	242 <i>et seq.</i>
INDIAN herring-bone -	48	MATTING - - -	232
		MECHANICAL embroidery	237

	PAGE		PAGE
MEDIAEVAL work	92, 136, 140, 190	PEASANT work	12, 13, 238
MILANESE-STITCH - - -	18	PERSIAN embroidery	7, 24, 41, 174, 240
MODELLING - - -	222	PICTORIAL effect	198, 199, 201
MODEST work - - -	242, 243	PICTURES (tent-stitch)	14, 20
MOORISH-STITCH - - -	18, 21	PIERCE - - -	132
MOROCCO embroidery -	152	PINS - - -	146, 262
		PLAIT-STITCH - - -	21
		PLATE - - -	257
NEEDLE (tambour) -	38, 257	PLUMAGE-STITCH	62, 100, 103, 178, 179, 192, 212, 230
NEEDLE pictures - - -	201	PRECIOUSNESS - - -	198
NEEDLES - - -	262	PURL - - -	257
NET passing - - -	86	PURSE silk - - -	116, 162
OLD ENGLISH KNOT-STITCH	75		
OPUS Anglicanum - - -	9	QUILTING - - -	172 <i>et seq.</i>
ORIENTAL embroidery	2, 22, 61, 92, 112, 136, 140, 153, 238		
„ stitch	66 <i>et seq.</i> , 83, 178, 182	RAISED gold -	134, 136, 165 <i>et seq.</i>
ORIGINALITY - - -	246	„ work -	134, 136, 159 <i>et seq.</i>
OUTLINE	22, 77, 108, 146, 158, 178, 184, 185 <i>et seq.</i>	RELIEF -	159 <i>et seq.</i> , 166, 168, 169, 172, 222, 230
„ (couched)	126, 128, 146	RENAISSANCE embroidery	41, 92, 142, 154, 166
„ (double)	146, 185, 186	RENEWING ground -	126
„ (stepped) -	16, 24	REVERSE-couching -	130
„ (voided) -	96, 187	RIBBON - - -	150, 258
OUTLINE embroidery -	138	RIBBON work - - -	258
„ stitch	29, 30, 32, 86	ROLL-STITCH - - -	75
		(See also <i>Bullion-stitch.</i> )	
PADDING - - -	159, 172	ROMAN satin - - -	255
PAINTING - - -	201, 202	ROPE-STITCH -	71 <i>et seq.</i> , 178
PARCHMENT -	160, 168, 258	RUNNING -	83, 106, 179
PARISIAN-STITCH - - -	18		
PATCHWORK - - -	156	SATIN - - -	255
PEARLS - - -	165, 166, 260	„ “de luxe” -	255
		„ on velvet - - -	105



	PAGE		PAGE
SATIN-STITCH -	24, 91 <i>et seq.</i>	STEMS - - -	95
103, 112, 128, 158, 160,		STEPPED outline -	16, 24
162, 175, 178, 182, 192,		STILETTO - -	174
206, 212, 228, 229, 230,		STITCH (definition of) -	11
234, 257		,, adaptation	103, 188, 265
SATIN-STITCH (surface)	98, 182	,, and effect -	36, 78
SATIN-STITCH in the making	91	,, and form	44, 47, 100, 118, 176, 211, 265
SCISSORS - - -	262	,, and stuff	12, 13, 16, 18, 24, 88, 91
SEEDING - - -	230, 231	,, groups	9, 175 <i>et seq.</i>
SERGE - - -	255	,, names - -	8, 9
SEVENTEENTH century		,, patterns -	87, 88
embroidery -	14, 166	,, and design -	10, 250
SHADED silk - -	258	STITCHES - - -	7
SHADING	34, 176, 188 <i>et seq.</i>	STITCHING over stitching	215
SILK - - -	146, 255	STRETCHING work -	263, 266
,, (tussah) - -	256	STRING - - -	159, 160, 162
,, (twisted) -	95, 124, 125	STROKE-STITCH -	16
,, on silk - -	150	STUFFS - - -	254
SILVER - - -	135, 138, 166	SURFACE crewel-stitch -	86
SIMPLICITY -	180, 248, 250	,, darning - -	84
,, (a plea for)	237 <i>et seq.</i>	,, satin-stitch	98, 182
SIXTEENTH century em-		,, stitches - -	84
broidery	22, 120, 125, 142, 185, 199	SYON COPE (the)	7, 130, 210
SOLID chain-stitch -	43, 44		
,, crewel-stitch -	32, 34	TAILORS' buttonhole -	56
SOUDANESE embroidery -	112	TAMBOUR - - -	257
SPANGLES - - -	169, 260	,, frame - -	44
SPANISH embroidery	129, 142	,, needle - -	38, 257
154, 166, 185		,, stitch - -	38
SPANISH-STITCH -	18, 22	,, work - -	44, 194
(See also <i>Plait-stitch.</i> )		TAPESTRY	1, 2, 4, 143, 220
SPARRING - - -	234	TAPESTRY-STITCH -	53
SPLIT-STITCH -	38, 100, 105	TENDRILS - - -	130
114, 179, 190, 196, 222		TENT-STITCH - -	14, 18
SPOKE-STITCH - -	234		
SPOT-STITCH - -	30		
STEM-STITCH - -	32		

	PAGE		PAGE
TEXTURE given by stitch-		VANDYKE chain	42
ing - - - 225, 226, 227		VARIETY of method	148, 158
THIMBLE - - - 262		„ of stitch	180 <i>et seq.</i>
THREAD - - - 256		VELVET - - - 150, 222	
“TRACING” - - - 228		VENETIAN embroidery	138
TRADITIONAL design - 250, 252		VOIDING - - - 96, 187	
TRANSFERRING design - 263			
TURKISH embroidery - 22			
TUSSAH silk - - - 256		WEAVING - - - 2	
TWISTED silk - 95, 124, 125		WHITE on white	162, 225 <i>et seq.</i> , 242
UNDERLAY 159, 160, 165, 228		WOOL. ( <i>See Crewel.</i> )	
UNPICKING - - - 265		WOOLLEN stuffs - - 255	

A CATALOGUE  
OF STANDARD BOOKS ON  
DECORATIVE ART  
ORNAMENT, &  
DESIGN

PUBLISHED AND SOLD BY  
B. T. BATSFORD  
94, HIGH HOLBORN, LONDON





A List of Standard Books  
ON  
**ORNAMENT & DECORATION,**  
INCLUDING FURNITURE,  
WOOD-CARVING, METAL WORK, DESIGN, &c.,

PUBLISHED AND SOLD BY

**B. T. BATSFORD,**

94, *HIGH HOLBORN, LONDON, W.C.*

**THE ART OF THE PLASTERER.** An Account of its Decorative Development, chiefly in England, from the XVI.—XVIII. Centuries, with Chapters on the Stucco of the Classic Period and of the Italian Renaissance, also on Sgraffito, Pargetting, Scottish, Irish and Modern Plaster-work. By **GEORGE P. BANKART**, Architect and Craftsman. Containing about 100 full-page and many smaller Illustrations chiefly from specially taken Photographs, or of specially prepared Sections and Mouldings, comprising in all over 500 Examples, and one Plate in Colour. Demy 4to (12 ins. by 8½ ins.), cloth gilt, price 25s. net. [*In the Press.*]

A book of exceptional interest and value to Plasterers, Architects, Modellers, and all interested in the Practice or Development of the Decorative Arts, forming an exhaustive collection of the choicest English Renaissance Ornament.

**OLD LACE.** A Handbook for Collectors. An Account of the different styles of Lace, their History, Characteristics, and Manufacture. By **M. JOURDAIN**, Joint Editor of Palliser's "History of Lace." Containing upwards of 120 Pages, with nearly 100 Plates comprising over 150 Historic Examples from Photographs. Large square 8vo (8½ ins. by 6½ ins.), cloth gilt, price 10s. 6d. net.

This book is designed to provide, in a handy and inexpensive form, a guide to the different varieties of Lace. The Author gives a brief history of each style, sketches the characteristics of its design and the method of its manufacture. Some of the best specimens from public and private collections in England and abroad are described and illustrated from Photographs. Special attention is devoted to English and Irish Laces.

**CONTENTS.**—Introduction—Early History of Lacemaking—Tests for Real Lace—Lacis—Cutwork—Early Italian Pillow Lace (Punto in Aria)—Venetian and Burano Lace—Rosepoint—Milanese and Cretan Lace—Flanders, Bruges, and Brussels Lace—Valenciennes—Dutch—Argentan and Alençon—Lille—Chantilly—English Needlepoint Lace—Honiton—Devonshire Trolley—Midland—Irish Laces—Blondes—Glossary of Terms—Index,

**DECORATIVE PLANT AND FLOWER STUDIES.** Uniform with "Decorative Flower Studies" (to which it forms a Second Series). By J. FOORD. For the use of Artists, Designers, Students, &c. Containing 40 Coloured Plates printed in facsimile of the original drawings, with a Description and Sketch of each Plant and 450 Studies of Growth and Detail. Imperial 4to, handsomely bound in cloth gilt, with an attractive cover design by the Author, price 30s. net.

*Extract from Introductory Note by Lewis F. Day:*—The author has made careful choice of the most beautiful features of the plant and rendered it simply and broadly in outline and flat tints. Her studies are to be trusted. They are drawn with care and exactness, and with a firm line there is no mistaking.

"This exquisitely printed and coloured book will prove the most desirable of all Yuletide publications."—*The Daily Telegraph*.

**DECORATIVE FLOWER STUDIES** for the use of Artists, Designers, Students and others. A series of 40 Coloured Plates, printed by hand by a stencil process in facsimile of the original drawings, accompanied by 350 Studies of Detail showing the Development of the Plant in successive stages of growth. With Descriptive Notes. By J. FOORD. Imperial 4to, handsomely bound in cloth gilt, price 25s. net.

**STUDIES IN PLANT FORM.** For the use of Students, Designers, and Craftsmen. By G. WOOLLISCROFT RHEAD, R.E., Hon. A.R.C.A. Containing 25 Photo-lithographic Plates, size  $17\frac{1}{2} \times 13$ , reproduced in black and white from the author's drawings, illustrating upwards of 60 varieties of Plants, together with over 80 Illustrations of Detail. Folio, in cloth portfolio, price 20s. net.

**A HANDBOOK OF PLANT FORM FOR STUDENTS OF DESIGN.** By ERNEST E. CLARK, Art Master, Derby Technical College. Containing 100 Plates (size  $10\frac{1}{2} \times 7\frac{1}{2}$  in.), illustrating 61 varieties of Plants with numerous figures in the text, comprising in all 800 Illustrations. With an Introductory Chapter on Design, Notes on the Plants, and a Glossary of Botanical Terms. Large 8vo, cloth, price 5s. net.

**ÉTUDE DE LA PLANTE, SON APPLICATION AUX INDUSTRIES D'ART.** By M. P. VERNEUIL. Comprising 120 Drawings of Natural Plants and 280 Conventional Designs all coloured after Water-colour Drawings, with French text. Large 4to, cloth, price £2 10s. net.

**FLOWERS AND THEIR DECORATIVE DESIGN.** By Professor G. FRAIPONT. A Series of examples, delicately printed in colours, entitled "Décorations Florales." Comprising 20 full-page Plates ( $15$  in.  $\times$   $11$  in.), with 20 examples of the natural flower, and over 100 decorative compositions. 4to, in cloth portfolio, price 12s. 6d. net.

MR. LEWIS F. DAY'S  
HANDBOOKS OF ORNAMENTAL DESIGN.

**ENAMELLING.** A Comparative Account of the Development and Practice of the Art. For the Use of Artists, Craftsmen, Students, &c. By LEWIS F. DAY, Author of "Pattern Design," "Ornament and its Application," "Alphabets," &c. Containing 214 Pages of Text, with 115 Illustrations, reproduced from Special Drawings and Photographs. Demy 8vo, cloth gilt, price 7s. 6d. net.

The plan of Mr. Lewis Day's new book is not quite that of any other work on Enamelling. It does not set out to be a learned history of the subject, though it endeavours to put into concise and easily intelligible form the gist of what learned historians have to tell us. Neither does it pretend to teach the beginner how to enamel, though it goes very thoroughly into the processes employed. What it does undertake is, first, to show what has been done and where it was done; and, secondly, to explain how it was done, and why it was done so. The result is a very comprehensive survey of the course of enamelling, both as an art in itself and as a branch of the jeweller's craft. The book should appeal to all who practise enamelling, and to those who only take an interest in it.

**PATTERN DESIGN.** A Book for Students, treating in a practical way of the Anatomy, Planning, and Evolution of Repeated Ornament. By LEWIS F. DAY. Containing 300 pages of text, with upwards of 300 Illustrations, chiefly from drawings by the author. Demy 8vo, cloth gilt, price 7s. 6d. net.

"Every line and every illustration in this book should be studied carefully and continually by everyone having any aspiration toward designing. It would probably be going a little too far to assert that anyone studying this book throughout would become designer, but it is certainly a fact that designing would be rendered comparatively easy to those having a complete knowledge of its contents; while it is equally true that the best artists could not produce designs of any value unless they understood the principles so clearly explained and admirably illustrated in this work."—*The Decorator*.

"The book is a serious contribution to the question of pattern designing, and is written expressly for the designer. It may be strongly commended to all who are studying the designing of textiles or wall papers, as the counsel it gives is the result of long years of experience."—*The Journal of Decorative Art*.

**ORNAMENT AND ITS APPLICATION.** A Book for Students, treating in a practical way of the Relation of Design to Material, Tools, and Methods of Work. By LEWIS F. DAY. Containing 320 pages, with about 300 full-page and other Illustrations of Decorative Objects and Ornament, reproduced from photographs and drawings. Demy 8vo, cloth gilt, price 8s. 6d. net.

Mr. WALTER CRANE in the *Manchester Guardian*.—"The author brings not only his extensive knowledge of historic styles, but also the results of his ripe and varied practical experience as a designer to the exposition of the nature of ornament itself, and the necessary conditions of its design. His illustrations are extremely rich and varied. . . . The work can be confidently commended as a most workmanlike and accomplished treatise not only to all students of design, but to artists and craftsmen generally."

"It bears the unmistakable impress of originality and practical utility. . . . It deals with its subject far more fully than any previous publication, whilst the numerous excellent illustrations will be an invaluable aid to teacher and student."—*The Studio*.



**MR. LEWIS F. DAY'S WORKS**—*continued.*

**NATURE AND ORNAMENT.** Being a new treatise founded on the author's "Nature in Ornament," which is now incorporated in it. By LEWIS F. DAY. Two vols., medium 8vo (9 ins. by 6 ins.), cloth lettered.

Vol. I.—**NATURE THE RAW MATERIAL OF ORNAMENT.** With special reference to Plant Form. Containing 120 pages and 350 illustrations, including full-pages, comprising 500 examples, and a fine series of specially drawn plates of plant form, growth, and detail. Price 5s. net.

Vol. II.—**ORNAMENT THE FINISHED PRODUCT OF NATURE.** With very numerous full-page and smaller illustrations, either new or re-drawn, of the treatment of Natural form in Design and Decoration.

[*In preparation.*]

*An invaluable Review of the Art and Practice of Embroidery.*

**ART IN NEEDLEWORK: A BOOK ABOUT EMBROIDERY.**

For the use of Needleworkers and other Students of Embroidery, and Designers for it. By LEWIS F. DAY and MARY BUCKLE. Third Edition, revised and enlarged. Containing 81 Plates reproduced from photographs, and 39 text Illustrations, of Historical Examples, special Stitches, and Samplers of executed Work in Various Stages, with a Special Chapter (new to this edition) on White Work, with Illustrations. Crown 8vo, cloth, price 5s. net.

"No worker's table can be considered complete without a copy."—*Home Art Work.*

"An extremely valuable book, forming a much-needed addition to the library of needleworkers, and one which will grow in value the longer and the more closely it is consulted."—*The Queen.*

**WINDOWS.—A BOOK ABOUT STAINED AND PAINTED**

**GLASS.** By LEWIS F. DAY. Third Edition, revised and enlarged, containing 60 full-page Plates and over 200 Illustrations in the text, all of Old Examples. 400 pages, large 8vo, cloth gilt, price 21s. net. The plates have been entirely reproduced afresh, and many are new to this edition.

*The Most Handy, Useful, and Comprehensive Work on the Subject.*

**ALPHABETS, OLD AND NEW.** Containing over 200 complete

Alphabets, 30 Series of Numerals, and numerous Facsimiles of Ancient Dates. Selected and arranged by LEWIS F. DAY. Preceded by a short account of the Development of the Alphabet. With Modern Examples specially Designed by R. ANNING BELL, WALTER CRANE, MUCHA, E. GRASSET, J. WALTER WEST, PATTEN WILSON, the Author, and others. Second Edition, revised and enlarged, with many additional examples. Crown 8vo, art linen, price 3s. 6d. net.

"We receive so many applications asking us to recommend a good reliable book on Alphabets, that it is a pleasure to note the issue of this second edition, which, with its additional alphabets, appears to meet almost every want."—*The Decorator.*



MR. LEWIS F. DAY'S WORKS—*continued.*

**LETTERING IN ORNAMENT.** An Enquiry into the Decorative Use of Lettering, Past, Present and Possible. By LEWIS F. DAY. With 200 full-page and smaller Illustrations from photographs and drawings. Crown 8vo, cloth, price 5s. net.

This work is uniform in size and style with the author's "ALPHABETS, OLD AND NEW," and is at once a companion and a sequel to it. But, whereas that dealt only with the forms of letters, this has to do with their use in ornament, the way they have been and are to be employed in decoration.

CONTENTS—The Printed and Written Page, Inscriptions, Scrolls and Labels, Monograms, Cyphers, Combinations, Initial Letters, Decorative Lettering, &c.

**MOOT POINTS:** Friendly disputes upon Art and Industry between WALTER CRANE and LEWIS F. DAY. Demy 8vo, 90 pages, with 8 Ornamental and very amusing Caricatures of the artists by WALTER CRANE. In paper wrapper, price 1s. net.

SUBJECTS: The Ideal Artist; Designer and Executant; the Artist and his Livelihood; Art and Industry; Work and Pleasure; the Profession of Art; Poetic Ornament; the Living Interest in Ornament.

## PROFESSOR MEYER'S TEXTBOOKS.

**A HANDBOOK OF ORNAMENT.** With 300 Plates, containing about 3,000 Illustrations of the Elements and Application of Decoration to Objects. By F. S. MEYER. Third Edition, revised by HUGH STANNUS, F.R.I.B.A. Thick 8vo, cloth gilt, price 12s. 6d.

"A Library, a Museum, an Encyclopædia and an Art School in one. To rival it as a book of reference, one must fill a bookcase. The quality of the drawings is unusually high, the choice of examples is singularly good. . . . The work is practically an epitome of a hundred Works on Design."—*Studio*.

"As a treasury of ornament drawn to scale in all styles, and derived from genuine concrete objects, we have nothing in England which will not appear as poverty-stricken as compared with Professor Meyer's book."—*Architect*.

**A HANDBOOK OF ART SMITHING.** For the use of Practical Smiths, Designers, and in Art and Technical Schools. By F. S. MEYER, Author of "A Handbook of Ornament." With an Introduction by J. STARKIE GARDNER. Containing 214 Illustrations. Demy 8vo, cloth, price 6s.

"A most excellent manual, crowded with examples of ancient work. The Introduction is by Mr. Starkie Gardner, and students know what that name implies."—*The Studio*.

**AN ALPHABET OF ROMAN CAPITALS,** together with three sets of lower-case letters selected and enlarged from the finest examples and periods. Prepared for the use of Schools. By G. WOOLLISCROFT RHEAD, R.E., HON. A.R.C.A., Lond. Each letter 7 in. square, with descriptive text, printed on strong drawing paper. In stout envelope, price 2s. 6d. net.

**LETTERING AND WRITING.** A series of Alphabets and their Decorative Treatment, with examples and notes illustrative of Construction, Arrangement, Spacing and Adaptation of Letters to Materials. By PERCY J. SMITH, Instructor in Writing and Illuminating at the L.C.C. Camberwell School of Arts and Putney School of Art. Containing 16 Plates in line, reproduced to a large scale from sheets entirely drawn and written by the Author. Printed on stout boards for purposes of teaching, study, &c. Large quarto (13½ ins. by 8½ ins.), in stout cardboard case, price 3s. 6d. net.

**SOME TERMS COMMONLY USED IN ORNAMENTAL DESIGN,** their Explanation Defined and Explained. By T. ERAT HARRISON and W. G. PAULSON TOWNSEND, Examiners to the Board of Education. With numerous illustrations, including many beautiful examples of design. Large 8vo, cloth, price 3s. 6d. net.

**DECORATIVE BRUSHWORK AND ELEMENTARY DESIGN.** A Manual for the Use of Teachers and Students in Elementary, Secondary and Technical Schools. By HENRY CADNESS, Second Master of the Municipal School of Art, Manchester. With upwards of 450 Examples of Design on Plates. Second Edition, revised and enlarged. Crown 8vo, cloth, price 3s. 6d. net.

"One of the most instructive books we have ever seen on this subject. Design is here treated in a masterly way, the author going to the best available sources for his illustrations, all of which are admirable."—*The Schoolmaster*.

**A MANUAL OF HISTORIC ORNAMENT,** being an Account of the Development of Architecture and the Historic Arts, for the use of Students and Craftsmen. By RICHARD GLAZIER, A.R.I.B.A., Headmaster of the Manchester School of Art. Containing 500 Illustrations. Second edition, enlarged. Demy 8vo, cloth, price 6s. net.

"Not since the publication of Owen Jones' celebrated 'Grammar of Ornament' have we seen any book, brought out on popular lines, that could compare with Mr. Glazier's 'Manual.' In many ways it is the better book of the two. . . . It simply abounds with beautiful, delicately-drawn illustrations, and forms a perfect treasury of designs."—*The Bookseller*.

**THE PRINCIPLES OF DESIGN.** A Textbook for Students and others, especially designed to meet the requirements of the Board of Education Examination Syllabus on "Principles of Ornament." By G. WOOLLISCROFT RHEAD, Hon. A.R.C.A. With 16 photographic Plates and over 350 diagrams drawn by the author, on 60 Plates. Large crown 8vo, art linen, gilt, price 6s. net.

"Certainly no one is better qualified to write such a book. . . . The illustrations, consisting of photographic reproductions and several hundred line drawings by the Author, are excellent. The few specimens of Mr. Rhead's own work as a decorative designer, which he introduces, makes one wish for more of them; they remind one of the thorough equipment of this admirable artist to speak with authority on his subject."—*Arts and Crafts*.

**PLASTERING—PLAIN AND DECORATIVE.** A Practical Treatise on the Art and Craft of Plastering and Modelling. With chapters on the History of the Art, illustrated by numerous fine examples. By WILLIAM MILLAR. With an Introduction by G. T. ROBINSON, F.S.A. Third Edition revised, containing 550 Illustrations, of which 50 are full-page Plates. Thick 4to, cloth, price 18s. net.

"Mr. Millar's book is in all respects admirable; written in a simple, effective style, dealing with the whole field of the art, and showing in its criticisms no lack of historical perspective. . . . It is full of technical information, while the illustrations contain some good examples of the best work of all kinds."—*The Studio*.

**THE ART OF BRASS REPOUSSE.** A Manual of Practical Instruction for the Use of Amateurs. By T. G. and W. E. GAWTHORP, Art Metal Workers to His Majesty. Fourth Edition, revised and enlarged, with 50 Illustrations. Cr. 8vo, paper cover, price 1s. net.

**"DER MODERNE STIL."** (THE MODERN STYLE.) An International Review of Art applied to Industry as represented in the best productions of leading decorative artists in England, France and Germany. Containing a rich collection of Illustrations of Art-Work and Design of all kinds, including Wall Papers, Textiles, Lace, Embroidery, Bookbinding, Pottery, Furniture, Carving, Stained Glass, Metal Work, &c. *Each volume is complete in itself and is sold separately:—*

VOLUME I.—With 815 Illustrations on 120 Plates. Large 4to, boards, cloth backs, price 20s. net.

VOLUMES II.—VII., each containing 96 Plates, exhibiting 600 to 800 Illustrations. 4to, boards, price 15s. net each.

**OLD CLOCKS AND WATCHES AND THEIR MAKERS.** Being an Historical and Descriptive Account of the different Styles of Clocks and Watches of the Past in England and Abroad, with a List of 10,000 Makers. By F. J. BRITTEN. Second Edition, much enlarged, containing 740 pages with 700 Illustrations of choice and curious specimens, mostly reproduced from photographs. Medium 8vo, cloth gilt, price 15s. net.

**THE DECORATION OF HOUSES.** By EDITH WHARTON and OGDEN CODMAN, Architect. With 56 full-page Photographic Plates of Interior Views, Doors, Ceilings, Chimney-pieces, examples of Furniture, &c. Large square 8vo, cloth gilt, price 12s. 6d. net.

This volume describes and illustrates in a very interesting way the Decorative treatment of Rooms during the Renaissance period, and deduces principles for the decoration, furnishing, and arrangements of Modern Houses.



**OLD ENGLISH WOOD-CARVING PATTERNS**—from Oak Furniture of the Jacobean Period. A series of examples selected and drawn in facsimile from rubbings, for the use of Teachers, Students and Classes. By MARGARET F. MALIM. Comprising 30 Examples on 20 Plates, reproduced by phototint process. Imperial 4to, in portfolio, price 8s. 6d. net.

This work has been undertaken in the hope of meeting the increased demand for simple wood-carving patterns. The rubbings have been taken from the best specimens of Jacobean furniture, and the details have been drawn in and shaded most carefully in order to reproduce the effect of the carving as accurately as possible. For the purpose of making her selection, the Author has visited many important private collections. The Introduction gives a clear explanation of the method of reproduction and also many valuable suggestions.

"To the amateur wood-carver and elementary student in the craft, this collection of thirty simple examples will be extremely useful. They are confined almost entirely to a flat form of decoration, therefore admirable exercises for beginners."—*Art Workers' Quarterly*.

**WOOD-CARVING DESIGNS.** A Series for Students, Teachers, Designers and Amateurs. By MURIEL MOLLER. With a Foreword by WALTER CRANE. Six Imperial Sheets comprising 31 Working Drawings of Panels, Frames, &c., 12 Reproductions of Photographs from the Carved Objects, and 20 Examples of Furniture suitable for them, designed in conjunction with A. W. SIMPSON. Large Imperial 8vo, in cloth portfolio, price 6s. net.

*Extract from Foreword by Walter Crane.*

MISS MURIEL MOLLER is an accomplished carver in wood, who has also had extensive experience in teaching the craft. In drawing these sheets of patterns she has had in view the need of a clearly defined outline of design for tracing on to the wood for the carver. A useful feature is the sheet of the elevations to scale of executed furniture designs which accompany the patterns and indicate the position and relation of the carved work in use.

**ENGLISH INTERIOR WOODWORK** of the XVI., XVII., and XVIII. Centuries. A series of 50 Plates of Drawings to scale and Sketches, chiefly of Domestic Work, illustrating a fine series of examples of Chimney Pieces, Panelling, Sides of Rooms, Staircases, Doorways, Screens, &c., with full practical details and descriptive text. By HENRY TANNER, Jun., A.R.I.B.A., Joint Author of "Some Architectural Works of Inigo Jones." Folio, cloth gilt, price 36s. net.

"The book contains fifty well-produced plates from ink and pencil drawings, which are excellently done, and the series gives a fairly consecutive view of some of the best wood-work to be found in England."—*The British Architect*.

"Mr. Tanner is certainly a skilled draughtsman, and to the illustrations in the book before us no exception could possibly be taken. The minutest details are given with the greatest exactitude, rendering the book of the utmost value to those who desire to study or possess a record of the styles represented."—*The Cabinet Maker*.

**REMAINS OF ECCLESIASTICAL WOOD-WORK.** A Series of Examples of Stalls, Screens, Book-Boards, Roofs, Pulpits, &c., beautifully engraved on 21 Plates from drawings by T. TALBOT BURY, Archt. 4to, half-bound, price 10s. 6d.



*The Most Artistic and Practical Volume on the craft by a well-known leading Authority.*

**PRACTICAL WOOD CARVING.** A Book for the Student, Carver, Teacher, Designer, and Architect. By ELEANOR ROWE. With 112 Illustrations from Photographs, and 55 from line drawings of Old and Modern Carvings, including Photographs of work in successive stages, and of Carving Methods and Processes in Action. Demy 8vo, cloth, containing about 240 pages, price about 7s. 6d. net.

This is a comprehensive book on the subject, showing the evolution of wood-carving from the simple gouge-cut pattern to the elaborate Renaissance panel. It is hoped that the Student who is compelled to learn wood-carving without a master will find all necessary for beginning his studies.

CONTENTS:—The Wood-Carver's Outfit—Various Woods used by the Carver—Construction—The Outcome of the Tool—Flat Carving—Strap-work and Low-relief—High-relief—Gothic Carving and Mouldings—Renaissance Carving and Mouldings—Lettering—Pierced Carving—Treatment and Design.

**FRENCH WOOD CARVINGS FROM THE NATIONAL MUSEUMS.** A Series of Examples printed in Collotype from Photographs specially taken from the Carvings direct. Edited by ELEANOR ROWE. Part I.: Late 15th and Early 16th Century Examples; Part II.: 16th Century Work; Part III.: 17th and 18th Centuries. The Three Series Complete, each containing 18 large folio Plates, with descriptive letterpress. Folio, in portfolios, price 12s. each net; or handsomely bound in one volume, price £2 5s. net.

"Students of the Art of Wood Carving will find a mine of inexhaustible treasures in this series of illustrations. . . . Each plate is a work of art in itself."—*The Queen*.

"Needs only to be seen to be purchased by all interested in the craft, whether archaeologically or practically."—*The Studio*.

**HINTS ON WOOD CARVING FOR BEGINNERS.** By ELEANOR ROWE. Fourth Edition, revised and enlarged. With 23 full-page Illustrations. 8vo, paper cover, price 1s.

"The most useful and practical small book on wood-carving we know of."—*Builder*.

**HINTS ON CHIP CARVING.** (Class Teaching and other Northern Styles.) By ELEANOR ROWE. 40 Illustrations. 8vo, paper cover, price 1s.

"Full of sound directions and good suggestions."—*Magazine of Art*.

**DETAILS OF GOTHIC WOOD CARVING** of the Fourteenth and Fifteenth Centuries. By FRANKLYN A. CRALLAN. Containing 34 large Photo-lithographic Plates, illustrating some of the finest specimens extant. With introductory and descriptive text. Large 4to, in cloth portfolio, or bound in cloth gilt, price 28s.

**ENGLISH FURNITURE DESIGNERS OF THE XVIII<sup>TH</sup> CENTURY.** By CONSTANCE SIMON. Containing upwards of 200 pages, with 62 full-page Illustrations of choice and little-known Specimens, beautifully reproduced in half-tone from special Photographs. Imperial 8vo, cloth gilt, price 15s. net.

"This is a book of unusual excellence, for which students of Miss Simon's fascinating but obscure subject will have very good cause to be grateful. So little is known of the lives and personalities of the great cabinet-makers of the Georgian period that the additions to our knowledge which her industry and research have enabled her to make are not only of substantial value in themselves, but will entitle her book to a distinguished place in furniture literature. The illustrations add most appreciably to the value of this well-informed, original, and authoritative piece of work, in which nothing is slurred over, and nothing taken for granted."—*The Standard*.

"Miss Simon's book is decidedly most attractive in form and appearance, and its copious illustrations from choice specimens in private collections are particularly excellent and interesting."—*The Times*.

**FURNITURE DESIGNING AND DRAUGHTING.** A Practical Manual on the Preparation of Working Drawings of Furniture. By A. C. NYE. Comprising Notes on the Elementary Forms, Methods of Construction, and Dimensions of Common Articles of Furniture. Fully illustrated by 152 Diagrams. Large 8vo, cloth, price 10s. net.

**COLONIAL FURNITURE IN AMERICA.** An Historical and Descriptive Account of the Old English and Dutch Furniture taken out or manufactured by the early Colonists. By LUKE VINCENT LOCKWOOD. With 300 photographic Illustrations of typical examples of Chests, Couches, Sofas, Tables, Chairs, Settees, Clocks, Cupboards, Sideboards, Mirrors, Chests of Drawers, Bedsteads, Desks, Escritaires, &c. 4to, art linen, price 25s. net.

**THE FURNITURE OF OUR FOREFATHERS.** Being Examples of Old Furniture of the Early Colonists in New England. By ESTHER SINGLETON. With critical descriptions by RUSSELL STURGIS. Containing over 600 pages of text, upwards of 150 Plates, reproduced in photogravure and half tone, and 200 line drawings in the text, exhibiting in all some 500 pieces of Furniture of the Stuart, Queen Anne and Georgian Periods. 2 vols., imperial 8vo, art canvas, price £2 10s. net.

**THE DECORATIVE WORK OF ROBERT AND JAMES ADAM.** Containing 30 large folio Plates illustrating about 100 examples of Rooms, Ceilings, Chimney-pieces, Tables, Chairs, Vases, Lamps, Mirrors, Pier-glasses, Clocks, &c., by these famous 18th-century Designers. Large folio, handsomely bound in old style, price 30s. net.

**CHIPPENDALE'S THE GENTLEMAN AND CABINET-MAKER'S DIRECTOR.** A complete facsimile of the 3rd and rarest Edition (1762), containing 200 Plates of Designs. Folio, strongly bound in half-cloth, price £3 15s. net.

**HEPPLEWHITE'S CABINET-MAKER AND UPHOLSTERER'S GUIDE.** A facsimile reproduction of this rare work, containing 300 charming Designs on 128 Plates. Small folio, cloth gilt, old style, price £2 10s. net. (1794.) *Original copies when met with fetch from £17 to £18.*

**EXAMPLES OF FURNITURE AND DECORATION DESIGNED BY THOMAS SHERATON.** Containing a selection of 167 typical specimens reproduced on 16 Plates (18 inches by 12 inches), from his rare "Cabinet Maker and Upholsterer's Drawing Book," published 1791—1802. Folio, enclosed in portfolio, price 15s. net.

**OLD OAK ENGLISH FURNITURE.** A Series of Measured Drawings, with some examples of Architectural Woodwork, Plasterwork, Metalwork, Glazing, &c. By J. W. HURRELL, Architect. Containing 110 full-page photolithographic Plates. Folio, cloth gilt, price £2 2s. 6d. net.

**USEFUL DETAILS IN SEVERAL STYLES.** Containing 1400 examples of Furniture and Decorative Details in various Historic Styles on 144 Plates. By HERBERT BINSTED, Editor of the "Furniture Record. Tall 8vo (11  $\frac{1}{4}$  × 4  $\frac{1}{2}$ ), price 3s. 6d. net.

The book is the cheapest and most concise guide to the styles of furniture and decoration which has ever appeared.

**PRACTICAL DRAPERY CUTTING.** A Handbook on Cutting and Fixing Curtains, Draperies, &c., with Descriptions and Practical Notes, for the use of Decorators, Upholsterers, Cutters, and Apprentices. By E. NOETZLI, formerly Instructor in Upholstery at the Municipal School of Technology, Manchester. Containing 30 Plates, comprising over 160 illustrations. Large imperial 8vo, cloth gilt, price 12s. 6d. net.

This work is written and arranged on very practical lines, and simply planned. The variety of subjects illustrated is great, and they include practically all the forms of drapery which occur in ordinary work.



**HERALDRY AS ART.** An Account of its Development and Practice, chiefly in England. By GEORGE W. EVE. Containing 320 Pages, with 300 Illustrations of Typical Heraldic Design, Old and New, from Photographs and Drawings. Demy 8vo, cloth gilt, price 12s. 6d. net.

SUMMARY OF CONTENTS.—The Origin, Uses, and Aims of Heraldry—The Evolution of Shield Forms—Heraldic Rules—Animals and Monsters—Heraldic Birds and other Figures—Helm, Crest, and Mantling—Armorial Accessories—Methods and Materials—Architectural Decoration—Embroidered Heraldry—Some Miscellaneous Charges—Marks of Cadency.

**ORNAMENT IN EUROPEAN SILKS.** By ALAN S. COLE, C.B., Author of *Ancient Needlepoint and Pillow Lace* and *Cantor Lectures on the Art of Lace Making, The Art of Tapestry Making and Embroidery, &c.* Containing 220 pages, with 169 full-page and smaller Illustrations of choice specimens, chiefly reproduced from Photographs. 4to, art linen, gilt, price 15s. net.

**OLD AND NEW LACE (DENTELLES, ANCIENNES ET MODERNES).** An Illustrated Catalogue of the choicest specimens displayed at the International Exhibition of Lace, held at the Museum of Decorative Art, Haarlem, comprising examples from Important Public and Private Collections, edited, with Short Historical and Descriptive Text in French, by JOHANNA W. A. NABER. Containing 60 fine Specimens on 30 large Folio Plates (size 19 in. × 14 in.), reproduced from Photographs, in Portfolio, price 30s. net.

**FIFTEENTH-CENTURY ITALIAN ORNAMENT,** chiefly taken from Brocades and Stuffs found on pictures in the National Gallery, London. By SIDNEY VACHER, Architect. A Series of 30 fine folio Plates of characteristic Textile Patterns from Dresses, Draperies, Brocades, Hangings, &c., shown to a good size, and printed in gold and colours. With descriptive Text. Folio, half vellum, in ornamental cover, 24s.

The few remaining copies of this interesting work have been privately purchased, and are now offered. The work has long been out of print.

**ENGLISH AND SCOTTISH WROUGHT IRONWORK.** A Series of Examples of English Ironwork of the best period, with which is included most that now exists in Scotland. By BAILEY SCOTT MURPHY, Architect. Containing 80 fine Plates (size 21½ in. by 14½ in.), 68 reproduced from measured drawings, and the remaining 12 from photographs specially taken. With Descriptive Text. Imperial folio, buckram, gilt, price £3 3s. net.

"This volume stands alone as a unique collection of the best work in wrought iron done in Great Britain. It is replete with exact delineations and precise dimensions technically and thoroughly realised for the student and practical craftsman."—*The Building News*.



OLD SILVERWORK, CHIEFLY ENGLISH, FROM THE XVth TO THE XVIIIth CENTURIES. A series of choice examples selected from the unique loan collection exhibited at St. James's Court, London. Edited, with Historical and Descriptive Notes, by J. STARKIE GARDNER, F.S.A. Containing 121 beautiful collotype Plates reproduced from photographs in the most effective manner. Folio, buckram, gilt, price £5 5s. net.

The edition of this work is limited to 500 copies, of which very few now remain for sale.

"All lovers of old silver will welcome the appearance of this sumptuous volume. The illustrations throughout are admirable, and the whole work deserves great praise."—*The Connoisseur*.

"The illustrations are as faultless as the resources of reproduction and of the typographical art can make them."—*The Daily News*.

THE TREATISES OF BENVENUTO CELLINI ON METAL WORK AND SCULPTURE. From the Marcian Codex, with an Introductory Account of the Origin and Object of the Treatises, and of Cellini's Position as Craftsman and Author. By C. R. ASHBEE, M.A. Illustrated by 11 Plates of Jewels, Seals, Coins, Medals, Ornamental Figures, &c., and 7 Practical Diagrams. Small folio, finely printed at the Essex House Press. In buckram, price 25s. net.

This translation is intended for the workshop, to bring home to English craftsmen the methods of the master goldsmith of the Renaissance. It abounds in information concerning the processes employed by metal-workers and sculptors in the time of Cellini, as well as with those specially introduced by him.

THE ART OF THE JAPANESE STENCIL CUTTER: THE BOOK OF DELIGHTFUL AND STRANGE DESIGNS, BEING ONE HUNDRED FACSIMILE ILLUSTRATIONS OF JAPANESE STENCILS. With an Introduction by ANDREW W. TUER, F.S.A. Containing a series of reproductions to a reduced scale of these extremely decorative compositions, including clever conventionalised renderings of foliage, insects, animals, fishes, birds, waves, &c., and ingenious geometric patterns. With descriptive notes. Oblong 4to, boards, price 4s. 6d.

NATIVE JAPANESE STENCILS. — Mr. BATSFORD has recently secured an extensive collection of stencils, including clever designs suitable for all decorative work. The stencils are all in good condition, and ready for use. They will be found of interest to art students as exquisite decoration and marvels of stencil cutting. The sizes of the stencils range from 7 in. by 12 in. to 10 in. by 14 in., and they are offered in series of 12 Plates, each different, for 3s. 6d. net, or 25 for 6s. net.

## JAPANESE ENCYCLOPÆDIA OF DESIGN.

BOOK I.—Containing over 1,500 engraved curios, and most ingenious Geometric Patterns of Circles, Medallions, &c., comprising Conventional Details of Plants, Flowers, Leaves, Petals, also Birds, Fans, Animals, Key Patterns, &c., &c. Oblong 12mo, fancy covers, price 2s. net.

BOOK II.—Containing over 600 most original and effective Designs for Diaper Ornament, giving the base lines to the design, also artistic Miniature Sketches. Oblong 12mo, price 2s. net.

These books exhibit the varied charm and originality of conception of Japanese Ornament, and form an inexhaustible field of design.

### A NEW SERIES OF BIRD AND FLOWER STUDIES.

BY WATANABE SIETEI, the leading living Artist in Japan. In three Books, containing numerous exceedingly artistic Sketches in various tints. 8vo, fancy covers, price 10s. net.

### A DELIGHTFUL SERIES OF STUDIES OF BIRDS, IN MOST CHARACTERISTIC AND LIFE-LIKE ATTITUDES, SURROUNDED WITH APPROPRIATE FOLIAGE AND FLOWERS. By the celebrated Japanese Artist, BAIREI KONO. In three Books, each containing 36 pages of highly artistic and decorative Illustrations, printed in tints. Bound in fancy paper covers, price 10s. net.

"In attitude and gesture and expression, these Birds, whether perching or soaring, swooping or brooding, are admirable."—*Magazine of Art*.

SHIN-BIJUTSUKAI. The New Monthly Magazine of Decorative Designs by famous Japanese Artists of to-day. Published in Tokio. A complete set of the 40 numbers published, containing 800 Plates, printed in gold and colours, forming a veritable treasury of ornamental designs. 40 volumes, 8vo, in fancy wrappers, enclosed in box, price £4 net. ONLY 10 SETS FOR SALE.

SHIN-BIJUTSUKAI. A set of 12 numbers as published, containing 240 plates. 12 volumes, 8vo, in fancy wrappers, price 25s. net.

A BOOK OF CHRYSANTHEMUMS. Containing 50 exquisite studies of this extremely decorative flower, printed in the beautiful variety of colours for which it is famous: ranging from snowy white, delicate pinks, bright yellows and orange, to rich dark reds. 2 vols. (12 in. by 9 in.), fancy covers price 14s. net.

**JAPANESE ARTISTS' SKETCH BOOK.** A series of 5 books illustrating (1) Fishes, Shells, &c. ; (2) Birds and Flowers ; (3) Landscapes and Water Scenes ; (4) Insects and Foliage ; (5) Scenes from Japanese Life Each contains 46 pages of illustration, drawn in a decorative spirit. Fancy covers, 7s. 6d. net.

**JAPANESE PATTERN BOOK.** Containing 114 fascinating designs, for Embroideries, Textiles, Wall-papers, and Decorative Painting, printed in colours and gold 2 vols. 8vo, fancy wrappers, price 7s. 6d. net.

**THE FLORAL ART OF JAPAN.** Being a second and revised edition of the "Flowers of Japan, and the Art of Floral Arrangement." By JOSIAH CONDER, F.R.I.B.A. With 69 full-page Plates, 14 of which are delicately printed in colours. 4to, cloth gilt, price £2 5s. net.

**ART PRINCIPLES IN PORTRAIT PHOTOGRAPHY.** Composition ; Treatment of Backgrounds, and the Processes involved in Manipulating the Plate. By OTTO WALTER BECK. With 138 full-page and smaller Illustrations, reproduced from specially taken Photographs and Original Diagrams. Large 8vo, cloth gilt, price 12s. 6d. net.

"The book deals very ably with the limitations and with the possibilities of the camera in portraiture. Too often the photographer has neither received any serious artistic training nor had the opportunity for intelligent study. While I do not think there is any short cut to success in Pictorial Portraiture, the book cannot fail to be most helpful and conducive to good if followed out."—MR. FURLEY LEWIS, F.R.P.S.

"The book contains many hints and suggestions which would be useful to the professional photographer, and intelligently carried out would certainly make the present average photographic portrait more interesting."—MR. FRED HOLLYER.

"After reading the text and examining the delightful essays and experiments in personal control with which the work abounds, I have no hesitation in proclaiming its value in helping the ambitious photographer to lift his likenesses from the dead level of mechanical dreariness to a height of pictorialism which should make for a wide measure of appreciation."—HECTOR MACLEAN, in the *Morning Post*.

**PICTORIAL COMPOSITION AND THE CRITICAL JUDGMENT OF PICTURES.** A Handbook for Students and Lovers of Art. By H. R. POORE. With about 150 Illustrations, chiefly reproduced from photographs of celebrated pictures, including numerous elucidatory diagrams. Large 8vo, art linen, price 7s. 6d. net.

One of the best works of its kind. Of particular value to the artist, to the art student, and to all interested in understanding the merits of a picture. The book is, in fact, a liberal education in art.

**THE APPRECIATION OF PICTURES.** An Historical and Critical Handbook of Ancient and Modern Art for the Artist, Student, and Connoisseur. By RUSSELL STURGIS, M.A. With 73 full-page Photographs after famous Pictures. Large 8vo, art linen, price 7s. 6d. net.

"This book is so well founded in the study of the masters, old and new ; so faithful to the true idea of the graphic arts, and so well written, that it could be read with interest and sympathy by anybody who loves paint."—*The Scotsman*.



**THE APPRECIATION OF SCULPTURE.** A Popular Handbook for Students and Amateurs. By RUSSELL STURGIS, M.A. With 64 full-page Photographic Illustrations of some of the most notable Examples of the Sculptor's Art. Large 8vo, art linen, price 7s. 6d. net.

"This interesting and instructive volume, with its admirably chosen illustrations, its skilful criticisms, and its cultured survey of the history of the fine art with which it deals, cannot but prove helpful to any reader who wishes to form well reasoned opinions on its subject."—*The Scotsman*.

**HOW TO JUDGE ARCHITECTURE.** A Popular Guide to the Appreciation of Buildings. By RUSSELL STURGIS, M.A. With 84 full-page Illustrations, reproduced in half-tone, from photographs of some of the chief buildings of the world. Large 8vo, art linen, price 7s. 6d. net.

"The greatest achievement amongst these three books is the treatise on architecture, a really masterly effort of selection, for in truth it is no easy matter to pick out, from the mass of traditions and influences which make the architectural criterion, those leading aspects of form and thought which will guide an untechnical reader into the way of knowing how to begin to know."—*The Art Journal*.

**HOME ART MANUALS.** By MARY WHITE. B. T. BATSFORD is pleased to announce that he has taken up the sale in England of this fascinating series of American handbooks which has met with such great appreciation amongst Teachers and amateurs.

Each volume is fully illustrated by clearly-drawn diagrams and reproductions of photographs. Crown 8vo, artistically bound in canvas, price 5s. net each.

**HOW TO DO BEAD-WORK.** Crown 8vo, 140 pp. This volume deals with the many fascinating branches of the craft and the remarkable effects achieved by the Indian workers.

**HOW TO MAKE BASKETS.** Crown 8vo, 194 pp. Miss WHITE here describes in detail the few necessary implements and materials, and then tells how to weave—first the simpler forms, next the more difficult patterns, and finally the complicated and beautiful work for which the Indians were once famous.

**MORE BASKETS AND HOW TO MAKE THEM.** Crown 8vo, 160 pp. The success of Miss WHITE's first volume has led to this companion work, which treats of more advanced basket making, shapes and weaves of greater beauty and intricacy, with new appliances, unusual materials, and numberless other matters not included in the initial volume.

**HOW TO MAKE POTTERY.** Crown 8vo, 180 pp. This volume describes, in simple language, the various materials, tools, and processes connected with the art.



THE GATE BEAUTIFUL, BEING PRINCIPLES AND METHODS IN VITAL ART EDUCATION. By Professor JOHN WARD STIMSON, formerly Director of Art Education at the New York Metropolitan Museum of Art. Containing about 500 pages, copiously illustrated with reproductions of original drawings, charts, rare and famous studies, drawings and paintings by the old masters. Large 4to, in stiff paper covers, price 17s. 6d. net.

ARCHITECTURAL COMPOSITION. An Attempt to order and phrase Ideas which hitherto have been only felt by the instinctive taste of Designers. By J. BEVERLEY ROBINSON, Architect, some time Lecturer on Architecture, Columbia University. Illustrated by Reproductions of 173 Photographs and line drawings of Ancient and Modern Buildings. Large 8vo. 10s. net.

Mr. ROBINSON formulates in an extremely clear and able manner the most approved practice of architects in designing the exterior of buildings, and illustrates his subject by many apt examples. His book is divided into seventeen chapters as follows:—The Standard of Taste—What is Architecture?—Unity—Individuality—Similarity—Subordination—Analysis of Buildings—Primary Masses—Secondary Masses—Details—Horizontal Division—Proportion—Contrast—Practical Applications—Asymmetrical Composition—Flexibility of Types—Comparison and Criticism.

A CONCISE HISTORY OF ENGLISH ARCHITECTURE FROM THE ROMANESQUE PERIOD TO MODERN TIMES, being the Congress Number of the Architectural Review, July, 1906. Comprising three papers on English Architecture, each richly illustrated by photographic reproductions and line drawings: (1) Mediæval; (2) Early Renaissance; (3) Later Renaissance; also illustrations of the work of living Architects. Foolscap (12 ins. by 8½ ins.), in stiff paper covers, price 5s. net, *postage 6d. extra.*

AN ARTISTIC AND USEFUL SERIES OF FRENCH BOOKS ON ILLUMINATION AND DESIGN AS FOLLOWS:—ILLUMINATED ORNAMENTS FROM MANUSCRIPTS AND BUILDINGS OF THE VTH TO THE XVIIIth CENTURIES. A Series of Six Volumes, each containing 15 Plates, well printed in gold and colours, illustrating over 100 Examples. Oblong 8vo, fancy covers, 2s. 6d. net each. Vol. 1—FROM VTH TO XIIth CENTURIES; Vol. 2—XIIIth CENTURY; Vol. 3—XIVth CENTURY; Vol. 4—XVth CENTURY; Vol. 5—ELEMENTS OF FRENCH ORNAMENTATION OF THE XVIth CENTURY; Vol. 6—ELEMENTS OF FRENCH ORNAMENTATION OF THE XVIIth & XVIIIth CENTURIES.

*The above six can be had bound in one handsome volume, vellum sides leather back, price 16s. net.*

**BUNGALOWS AND COUNTRY RESIDENCES.** A Series of Designs and Examples of executed Works. By R. A. BRIGGS, F.R.I.B.A. 5th and enlarged Edition, containing 47 Photo-lithographic Plates, many of which are new to this edition. With descriptions, including the actual cost of those which have been built, and the estimated cost of those not yet erected. 4to. cloth, price 12s. 6d.

"Economy, convenience, and comfort in small country houses are important elements, and these have been studied with an artistic appreciation of effect and rural charm in Mr. Briggs' designs."—*The Building News*.

**A BOOK OF COUNTRY HOUSES.** Containing 62 Plates, reproduced from Photographs and Drawings of Perspective Views and Plans of a variety of executed examples, ranging in size from a small Suburban House to a fairly large Mansion. By ERNEST NEWTON, Architect. Imperial 4to (15 in. by 11 in.), price 21s. net.

The houses illustrated in this volume have been planned during the last ten years, and may be taken as representative of the English Country House of the present day. They offer much variety in their size, their sites, the character of the materials in which they are constructed, and their types of plans.

The illustrations comprise 41 perspective views, reproduced from photographs and drawings in black-and-white and water-colours, together with 22 plans drawn to a large scale, whilst a few main features and interior views are included.

**HOMES FOR THE COUNTRY.** A Collection of Designs and Examples of recently-executed works. By R. A. BRIGGS, Architect, F.R.I.B.A., Soane Medallist. Containing 48 full-page Plates of Exterior and Interior Views and Plans. With Descriptive Notes. Demy 4to, price 10s. 6d. net.

"Every example given is an illustration of very considerable skill. The plans are all excellent—well devised on economical yet convenient lines, well lit, comfortable, and with every little point thought out; while the elevations are pleasing without being extravagant. Such a book is admirable in its suggestiveness, and useful to all."—*The Architect's Magazine*.

"The arrangement of the plans generally reveals a master hand at this class of architecture."—*The Pall Mall Gazette*.

**MODERN SUBURBAN HOUSES.** A Series of Examples Erected at Hampstead, Bickley, Purley, and elsewhere, from Designs by C. H. B. QUENNELL, Architect. Containing 44 Plates (13 $\frac{3}{4}$  in. by 10 $\frac{1}{2}$  in.) of Exterior and Interior Views, and large scale Plans, reproduced from special Photographs and the Author's Drawings. Large 4to, cloth gilt, price 16s. net.

The houses illustrated in this volume are of the best type of suburban house, generally semi-detached, and of limited frontage—a type upon which very little information has been published, although it is one of which the better class estates are largely composed. Skilfully planned, of quiet, refined design, and financially successful (*all the examples having been built for sale, and sold*), they clearly demonstrate that architecture in the suburbs, even when controlled by speculative builders, may be as refined and beautiful as in the country.

**MODERN COTTAGE ARCHITECTURE**, Illustrated from Works of well-known Architects. Edited, with an Essay on Cottage Building, and descriptive Notes on the subjects, by MAURICE B. ADAMS, F.R.I.B.A. Containing 50 Plates reproduced from the architects' drawings, with the plans of each subject. Royal 4to, price 10s. 6d. net.

**THE COUNTRY HOUSE**. A Practical Manual of the Planning and Construction of the American Country Home and its surroundings. By C. E. HOOPER. Illustrated by E. E. SODERHOLTZ. 330 pages fully Illustrated by over 300 Photographs of Exterior and Interior Views, Details and Gardens, with typical Plans of some of the finest Colonial and Modern Examples. Royal 8vo, cloth, price 15s. net.

**ARCHITECTURAL SKETCHING AND DRAWING IN PERSPECTIVE**. A progressive series of 36 Plates, illustrating the Drawing of Architectural Details and Sketching to Scale; including chapters on the Plan and Measuring Point Methods, the Simplification of Perspective by R's method, and on Figures, Foliage, &c. By H. W. ROBERTS, Author of "R's Method." Large imperial 8vo, price 7s. 6d. net.

**THE PRINCIPLES OF ARCHITECTURAL PERSPECTIVE**. Prepared for the use of Students, &c., with chapters on Isometric Drawing and the Preparation of Finished Perspectives. By G. A. T. MIDDLETON, A.R.I.B.A. With many Diagrams and Plates, including a series of finished perspective views of buildings by various Architects. Second Edition revised, with additional Diagrams. Demy 8vo, cloth, price 2s. 6d. net.

**THE ORDERS OF ARCHITECTURE: GREEK, ROMAN AND ITALIAN**. A selection of typical examples from Normand's "Parallels" and other Authorities, with Notes on the Origin and Development of the Classic Orders and descriptions of the plates, by R. PHENÉ SPIERS, F.S.A., Master of the Architectural School of the Royal Academy. Fourth Edition, revised and enlarged, containing 27 full-page Plates. Imperial 4to, cloth gilt, price 10s. 6d.

**CLASSIC ARCHITECTURE**. A series of Ten Plates (size 20 in. x 15 in.) of examples of the Greek and Roman Orders, with full details and a selection of Classic Ornament. By CHARLES F. MITCHELL and GEORGE A. MITCHELL, Lecturers on Architecture, Regent Street Polytechnic, W. With descriptive letterpress, in portfolio, price 6s. net, or the Set of 10 plates without text or portfolio, price 5s. net.



**EXAMPLES OF CLASSIC ORNAMENT FROM GREECE AND ROME.** Drawn from the Originals by LEWIS VULLIAMY, Architect, Gold Medallist, and Travelling Student of the Royal Academy (1790—1871). A Series of 20 Selected Plates, with Introductory and Descriptive Notes by R. PHENÉ SPIERS, F.S.A., F.R.I.B.A., Author of "The Orders of Architecture," "Architecture, East and West," &c. Royal Folio (19½ ins. by 13½ ins.), in strong portfolio, 12s. 6d. net; or strongly bound in cloth boards, 15s. net.

This volume contains a selection of the most characteristic and useful plates from the rare folio work of Vulliamy, first published in 1825, and long since out of print and practically unobtainable. The plates display in their spirited execution an intimate appreciation of the refinement and vigour which characterizes the best work in Athens and Rome, and form an exceptionally fine series of illustrations of the choicest examples. It is believed the series will prove to be of great value to students, not only on account of the large scale to which the drawings are made, but because they include elaborate examples of Greek carving which are not to be found elsewhere.

**THE ARCHITECTURE OF GREECE AND ROME. A SKETCH OF ITS HISTORIC DEVELOPMENT.** By WILLIAM J. ANDERSON, Author of "The Architecture of the Renaissance in Italy," and R. PHENÉ SPIERS, F.S.A., Author of "The Orders of Architecture." Second Edition revised and enlarged. Containing 350 pages of text, and 255 Illustrations from photographs and drawings, including many full-page Plates, of which 24 are finely reproduced in collotype. Large 8vo, cloth gilt, price 18s. net.

**THE ARCHITECTURE OF THE RENAISSANCE IN ITALY.** A General View for the Use of Students and Others. By W. J. ANDERSON, A.R.I.B.A., Director of Architecture, Glasgow School of Art. Third Edition, containing 64 full-page Plates and 100 Illustrations in the text from photographs and drawings. Large 8vo, cloth gilt, price 12s. 6d. net.

**A HISTORY OF ARCHITECTURE ON THE COMPARATIVE METHOD.** By BANISTER FLETCHER, F.R.I.B.A., late Professor of Architecture in King's College, London, and BANISTER F. FLETCHER, F.R.I.B.A. Fifth Edition, revised and greatly enlarged. With about 2000 Illustrations from photographs and drawings. Demy 8vo, cloth gilt, price 21s. net.



**ESSENTIALS IN ARCHITECTURE.** An Analysis of the Principles and Qualities to be looked for in Buildings. By JOHN BELCHER, A.R.A., Fellow and Past President of the Royal Institute of British Architects. With 74 Illustrations (mostly full-page) of Old and Modern Buildings. Demy 8vo, cloth gilt, price 5s. net.

Mr. R. NORMAN SHAW, R.A., writes :—"I have read the proofs of this work with the greatest interest. I am quite sure it will arouse enthusiasm in hundreds of readers, but if it attracted only a dozen, it would not have been written in vain. Mr. Belcher wishes his readers to think of Architecture—architecturally; tells them how to do so, and no one is more competent to teach them."

"Excellentlly printed and generously illustrated by many beautiful photographs of well-chosen subjects, it is a pleasure to the eye. Perhaps it may be best described as a series of charming conversations on his chosen art addressed to the general reader by a veteran architect of great ability, deeply anxious to stimulate a higher standard of appreciation on the part of the public."—*The Athenæum*.

"This attractive and beautifully equipped volume is . . . full of charming photographs, supplying in themselves the materials of a sound architectural education."—*The Daily Telegraph*.

**A HISTORY OF ARCHITECTURE.** Having Special Regard to the Natural Artistic Results of Construction and those Methods of Design which are the Result of Abstract Thinking and of the Pure Sense of Form. By RUSSELL STURGIS, M.A., Ph.D., Editor of "A Dictionary of Architecture," Author of "How to Judge Architecture," &c. 3 vols., Imp. 8vo, cloth gilt, price £3 15s. net, the set.

The first volume, "ANTQUITY," is now ready. Volumes II. and III., dealing with the Mediæval and Renaissance Periods, will be published during 1908. Each volume will contain about 500 pages, with some 350 full-page and smaller illustrations, reproduced in collotype, half-tone, and line, from special photographs and drawings.

"A very full and finely-illustrated treatise, very interesting to read, and likely to appeal to a large circle of people outside of the profession of architecture. . . . It is a brilliant production, the result of very wide and comprehensive study of the subject; and in print, illustrations, and general make-up, it is a credit to the publishers."—*The Builder*.

**THE PETIT TRIANON, VERSAILLES.** Illustrated by a Series of Measured Drawings and Photographs of the Exterior and Interior, including Furniture and Iron Work and Brass Work, together with an Historical Account and Descriptions. By J. A. ARNOTT and J. WILSON, Architects. Three Parts, each part containing 31 Plates, size 19½ ins. by 14½ ins., in portfolio. Just completed. Price £3 3s. net, complete in three portfolios, or bound in half morocco £3 13s. 6d. net.

The Palace of the Petit Trianon is a complete example of the best period of the 18th century. It was designed by a pupil of Mansard called Gabriel, and is one of the purest and most perfect examples of that time, and the exterior, the interior, and furnishing are in thorough harmony.

"The authors are to be heartily congratulated on both the conception and execution of their undertaking. No more useful work can be done than the complete and careful study of a particular building . . . . The Petit Trianon remains an almost perfect example of the purest and best work of the late eighteenth century in France. The drawings are beautifully executed and excellently reproduced, the plates of the carving and wrought metal work drawn to a large scale being particularly good."—*The Athenæum*.

## AN EPOCH-MAKING BOOK.

**GOTHIC ARCHITECTURE IN ENGLAND.** An Analysis of the origin and development of English Church Architecture, from the Norman Conquest to the Dissolution of the Monasteries. By FRANCIS BOND, M.A., Hon. A.R.I.B.A. Containing 800 pages, with 1,254 Illustrations, comprising 785 photographs, sketches, and measured drawings, and 469 plans, sections, diagrams, and moldings. Imperial 8vo, cloth gilt, price 31s. 6d. net.

"The fullest and most complete illustrated treatise on the subject which has yet appeared. . . . It is a book which every student of architecture, professional or amateur, ought to have."—*The Builder*.

"Perfectly orderly, and most complete and thorough, this great book leaves nothing to be desired."—*The Building News*.

"This is, in every sense of the word, a great book. . . . It is a book that at once steps to the front as authoritative, and it will be long before it is superseded."—*The Athenæum*.

**EARLY RENAISSANCE ARCHITECTURE IN ENGLAND.**

An Historical and Descriptive Account of the Tudor, Elizabethan and Jacobean Periods, 1500–1625. By J. ALFRED GOTCH, F.S.A. With 88 Collotype and other Plates and 230 Illustrations in the text from Drawings and from Photographs. Royal 8vo, cloth gilt, price 21s. net.

"The book is quite a storehouse of reference and illustrations, and should be quite indispensable to the architect's library."—*The British Architect*.

**EXAMPLES OF ENGLISH MEDIÆVAL FOLIAGE AND COLOURED DECORATION.** By JAS. K. COLLING, Architect, F.R.I.B.A. Taken from Buildings of the XIIth to the XVth Century. Containing 76 Lithographic Plates, and 79 Woodcut Illustrations, with text. Royal 4to, cloth, gilt top, price 15s. net (published at £2 2s.).


*Dedicated by Special Permission to Sir Edward J. Poynter, P.R.A.*

**EXAMPLES OF GREEK AND POMPEIAN DECORATIVE WORK.** Measured and Drawn by J. CROMAR WATT. Containing 60 Collotype Plates, reproduced from the original Pencil Drawings of the author, comprising Architectural Details and Ornament, Terra Cotta, and Ornamental Bronze Work, &c. A handsome folio volume, cloth, price £1 10s. net.

**SOME ARCHITECTURAL WORKS OF INIGO JONES.** Illustrated by a Series of Measured Drawings of the Chief Buildings designed by him, together with Descriptive Notes. By H. INIGO TRIGGS and HENRY TANNER, Junr., A.R.I.B.A. Containing 40 full-page Plates and over 40 Illustrations in the text. Large folio, cloth gilt, price 30s. net.

"The plates are quite perfect as specimens of draughtsmanship, and possess a crispness and freedom of handling which differentiate them from ordinary measured drawings."—*A. A. Notes*.

B. T. BATSFORD, 94, HIGH HOLBORN, LONDON.









**BINDING DEPT. JUL 2 1959**

**PLEASE DO NOT REMOVE  
CARDS OR SLIPS FROM THIS POCKET**

---

**UNIVERSITY OF TORONTO LIBRARY**

---

NK  
9206  
D38  
1907  
C.1  
ROBA

